

# Millerton Wastewater Preliminary Engineering Report

Village of Millerton

March 2020 REVISED June 2020 REVISED April 2022 REVISED April 2024 REVISED July 2025 CWSR# C3-5339-02-00 EPG# 76549



Services Provided in New York by T&B Engineering, PC

Tighe&Bond



\*Revised July 2025

Section 1	. Project Planning	
1.1	Introduction	1-1
1.2	Previous Planning Efforts	1-1
1.3	Site Information	1-3
	1.3.1 Location & Population Trends	1-3
	1.3.2 Geologic & Topographic Conditions	1-3
	1.3.3 Environmental Resources & Floodplain	1-4
	1.3.4 Land Use/Zoning	1-6
	1.3.5 Environmental Justice Areas	1-7
1.4	Community Engagement	1-8
Section 2	Need for Project*	
Section 3	Wastewater Disposal Needs Analysis	
3.1	General	3-1
3.2	Determining and Prioritizing Need	3-2
	3.2.1 Wastewater Survey	3-2
	3.2.2 Site Conditions	3-4
	3.2.3 Village Priorities	3-6
	3.2.4 Summary	3-9
3.3	Service Area Prioritization	
3.4	Wastewater Flows and Loads*	3-10
	3.4.1 Wastewater Flow Estimates	3-10
	3.4.2 Future Flows and Loads*	3-14
	3.4.3 Discharge Limits	3-15
Section 4	Alternatives Considered*	
4.1	Individual Onsite Wastewater Systems	4-1
4.2	Wastewater Collection Systems	
	4.2.1 Conventional Gravity and Pumped Collection Systems	4-2
	4.2.2 Alternative Collection Systems	4-3
4.3	Wastewater Treatment Systems	4-5
	4.3.1 Conventional Treatment Systems	4-5
	4.3.2 Water Resource Recovery Systems	4-6
	4.3.3 Treatment System Comparison	4-6
	4.3.4 Water Resource Recovery Technologies	4-7
4.4	Water Resource Recovery Return	4-13
	4.4.1 Return to Surface Water	4-13



4.5	Potential Treatment System Locations4-18
	4.5.1 Initial Parcel Screening4-19
	4.5.2 Additional Parcel Considerations4-23
	4.5.3 Return to Groundwater System Potential4-27
	4.5.4 Return to Surface Water Locations*4-29
Section 5	Alternative Analysis
5.1	Proposed District & Alternative Development5-1
	5.1.1 Individual Onsite Wastewater Treatment Systems5-2
	5.1.2 Wastewater Collection Systems*5-2
	5.1.3 Wastewater Treatment Systems5-4
	5.1.4 Recovered Water Return Systems5-6
	5.1.5 Water Resource Recovery System Sites5-8
	5.1.6 Definition of Alternatives5-8
5.2	Alternative No. 1: No-Action5-8
5.3	Alternative No. 2: Biofiltration with Absorption Field5-9
5.4	Alternative No. 3: MBR with Surface Return5-10
5.5	Alternative No. 4: Biofiltration with Surface Return5-12
5.6	Alternative Cost Comparison5-13
	5.6.1 Cost Estimate Approach*
	5.6.2 Alternative Cost Estimates*
	5.6.3 Life Cycle Cost Analysis*5-16
5.7	Non-Monetary Considerations5-17
Section 6	Recommended Alternative
6.1	Summary of Recommended Alternative6-1
6.2	Project Costs*6-2
6.3	Annual Operating Budget6-2
	6.3.1 Income6-2
	6.3.2 Annual O&M Costs6-2
	6.3.3 Dept Repayment & User Fees*6-3
	6.3.4 Reserves
6.4	Project Implementation & Schedule*6-3
Appendic	es
Α	Figures
В	NRCS Soil Report
С	Town of North East Zoning District Map
D	Wastewater Survey Cover Letter and Questionnaire
Е	EDU Methodology and Assignments
F	Alternative Wastewater Treatment Technology Supplemental Information
	<del>-</del> , ·,



- G Village of Millerton Flood Insurance Rate Map
- H Mill Street Site Deep Test and Percolation Data Sheets
- I Detailed Cost Estimates
- J Engineering Report Certification
- K Smart Growth Assessment Form
- L Project Financing\*
- M Anticipated Project Schedule\*

### List of Tables\*

Table 3.1	Survey Response Summary by Sub-area
Table 3.2	Reported Wastewater Disposal Problems by Sub-area
Table 3.3	Parcels Less than 1 Acre
Table 3.4	Average Lot Density
Table 3.5	Reported Basement Flooding Problems
Table 3.6	Comprehensive Plan Goals & Wastewater Disposal Impacts
Table 3.7	Wastewater Treatment Impacts
Table 3.8	Wastewater Needs Ranking
Table 3.9	Priority of Sub-Areas
Table 3.10	Village of Millerton Water Use Summary (2017 - 2020)
Table 3.11	Wastewater Flow Estimates Using the EDU Method
Table 3.12	Anticipated Design Flows for Entire System
Table 3.13	Expanded Service Area Anticipated Flows
Table 3.14	Anticipated Discharge Limits for Surface Disposal
Table 4.1	Typical Septic Tank Influent & Effluent Concentrations
Table 4.2	Treatment Systems Not Analyzed
Table 4.3	Ovivo MicroBLOX Typical Effluent Concentrations
Table 4.4	Orenco Treatment System Typical Effluent Concentrations
Table 4.5	Potential Locations and Initial Parcel Screenings
Table 4.6	Recommended Separation Distances
Table 4.7	Estimated Return to Groundwater Capacity at the Mill Street Site
Table 5.1	Millerton Anticipated Sewer District Design Flow Summary
Table 5.2	Treatment System Comparison
Table 5.3	Recovered Water Return Comparison
Table 5.4	Alternative No. 2 Preliminary Cost Estimate
Table 5.5	Alternative No. 3 Preliminary Cost Estimate
Table 5.6	Alternative No. 4 Preliminary Cost Estimate



Table 5.7	Alternative No. 2 Annual O&M Cost Estimate	
Table 5.8	Alternative No. 3 Annual O&M Cost Estimate	
Table 5.9	Alternative No. 4 Annual O&M Cost Estimate	
Table 5.10	Life Cycle Cost Analysis	
Table 5.11	Non-Monetary Considerations	
Table 6.1	Recommended Project Costs	
Table 6.2	Short Lived Assets	
of Figures*		

# List of F

Figure 1.1	Village of Millerton NYSDEC Environmental Resources Mapper
Figure 1.2	Millerton/North East Area Environmental Justice Areas
Figure 3.1	Ten States Standards Peak Hour Factor Calculation
Figure 3.2	MOP 9 Daily Peaking Factor Calculation
Figure 4.1	Typical Residential Wastewater Treatment System
Figure 4.2	Typical Septic Tank
Figure 4.3	Typical STEG and STEP System Schematic
Figure 4.4	Alternative Treatment System in Dix Hills, NY
Figure 4.5	Ovivo MicroBLOX System
Figure 4.6	Ovivo MicroBLOX Simplified Process Flow Diagram
Figure 4.7	Orenco's AdvanTex Units (AX-100 Models Shown)
Figure 4.8	Typical Orenco AdvanTex System Layout For Subsurface Disposal
Figure 4.9	Typical Trench Absorption Field Under Construction
Figure 4.10	Seepage Bed with Infiltration Chambers Under Construction
Figure 4.11	Drip Dispersal System Before Backfill
Figure 4.12	Typical Drip Dispersal System
Figure 4.13	Gravelless Geotextile Sand Filter Trench System (by Infiltrator)
Figure 4.14	Potential Wastewater Treatment Sites – Flood Zones
Figure 4.15	Potential Wastewater Treatment Sites – Topography
Figure 4.16	Floodway Fringe and Floodway Guidance
Figure 4.17	Approximate Right-of-Way Location at the Mill Street Site
Figure 4.18	Potential Surface Return Locations
Figure 5.1	Village of Millerton Topography Impacting Gravity Flow
Figure 5.2	Preliminary Layout of Alternative No. 2
Figure 5.3	Preliminary Layout of Alternative No. 3
Figure 5.4	Preliminary Layout of Alternative No. 4



M1784-009 July 17, 2025

Jennifer Najdek, Mayor Village of Millerton 21 Dutchess Avenue Millerton, NY 12546

Re: Updated Wastewater Feasibility Evaluation

Dear Mayor Najdek:

Tighe & Bond, whose services are provided in New York by T&B Engineering and Landscape Architecture, PC (Tighe & Bond), is pleased to submit our updated Wastewater Feasibility Evaluation Report for the Village of Millerton. This report has been revised from its original March 2020 date, revision of June 2020, revision of April 2022, and revision of April 2024.

#### **Executive Summary**

Tighe & Bond has evaluated various wastewater collection, treatment, and water resource recovery return options to determine a viable solution for the Village. The enclosed report summarizes our evaluation including a prioritization of service areas, a discussion of conventional and alternative wastewater systems, identification of alternatives, a summary of the recommended alternative, and anticipated costs for implementing and maintaining these improvements.

The results of the wastewater survey revealed problems with individual wastewater systems throughout the Village and that there is a desire amongst survey respondents for a Village wastewater system. The wastewater evaluation presented in the attached report considered reported wastewater problems, lot sizes, lot density, depth to restrictive layers, and the Village comprehensive plan goals to determine the need for a wastewater system and to prioritize certain areas of the Village.

#### **Alternatives Analysis**

Based on the community feedback, it was determined that the proposed service area should incorporate parts of each sub-area with the primary focus on serving the Village General Business District, commercial areas along Route 22, and the Town of North East Boulevard District along Route 44. The anticipated sewer district is shown in Figure A.9 of the report.

The alternatives and costs comparisons presented in this report are based on the proposed sewer district and the estimated average day design flow of 70,000 gpd as discussed in Section 5.1 of the report. Based on the alternative development discussed in Sections 4 and 5 of the enclosed report, four alternatives were identified for consideration including:

- Alternative No. 1 No-Action
- Alternative No. 2 STEP Collection System with Biofiltration Resource Recovery System and Groundwater Return at the Mill Street Site
- Alternative No. 3 STEP Collection System with Membrane Bioreactor Resource Recovery System and Surface Return to Webatuck Creek at the Mill Street Site
- Alternative No. 4 STEP Collection System with Biofiltration Resource Recovery System and Surface Return to Webatuck Creek at the Mill Street Site

We have recommended a project that includes construction of a septic tank effluent collection system for the proposed sewer district, a resource recovery system at the Mill Street site treatment and surface resource recovery system sized to treat and recover 70,000 gpd at the Mill Street property and Webatuck Creek, respectively.

#### **Recommended Alternative**

The no-action alternative (Alternative No. 1) was not recommended because it would not address issues with existing septic systems and it would fail to promote growth of business development in the proposed district. Therefore, a life cycle cost analysis was performed for Alternative No. 2, Alternative No. 3, and Alternative No. 4 and is summarized in Table E.1 below.

**Table E.1**Life Cycle Cost Analysis Summary

	Alt. No. 2	Alt. No. 3	Alt. No. 4
Capital Costs	\$10,726,000	\$10,008,000	\$10,406,000
Annual O&M Costs	\$116,200	\$201,000	\$146,000
Present Worth of O&M Costs	\$2,820,000	\$4,880,000	\$3,550,000
Present Worth of Salvage Value	\$1,150,000	\$890,000	\$1,080,000
Net Present Value	\$14,812,000	\$15,979,000	\$15,182,000
		Planning Period	20 years
		Inflation Rate	2.30%
		Discount Rate	0.30%

Although the capital construction costs for Alternative No. 2 are more than Alternative No. 3 and Alternative No. 4, the lower annual operation and maintenance costs associated with Alternative No. 2 ultimately result in a lower life cycle cost. However, Alternative No. 2 is no longer feasible due to the inability to acquire the vacant parcel resulting in insufficient area for a groundwater recovery system at the Mill Street site. Alternative No. 4 has the second lowest life cycle cost analysis. Several non-monetary considerations such as public perception, visual impacts, simplified operation and maintenance, and ease of expandability also favor Alternative No. 4 and therefore, Alternative No. 4 is the recommended alternative.

#### **Opinion of Probable Costs**

There are several financial grant or low-interest loan programs available which may assist the Village with funding this project such as the Clean Water State Revolving Fund. The enclosed engineering report has been prepared in anticipation of pursuit of a low-interest loan or grant. Table E.2 on the following page provides the conceptual opinion of probable cost for implementation of Alternative No. 4 in a format that is consistent with funding agency requirements.

**Table E.2**Recommended Alternative Costs

Recommended Alternative Costs			
Item	Cost <sup>1</sup>		
1. Construction Costs	\$9,476,000		
2. Engineering Costs			
a. Design	\$736,000		
b. Construction	\$1,137,000		
3. Other Expenses			
a. Local Counsel	\$71,000		
b. Bond Counsel	\$118,000		
c. Work Force	\$0		
d. Financial Services	\$0		
e. Miscellaneous	\$0		
4. Equipment	\$0		
5. Land Acquisition	\$0		
6. Project Contingency (20%)	\$2,292,000		
7. Total Project Costs	\$13,830,000		
8. Less Other Sources of Financing			
a. Dutchess County MIG	-\$200,000		
b. CPF Grant	-\$959,752		
c. IMG Grant	-\$5,082,099		
9. Project Costs to be Financed	\$7,588,149		

<sup>&</sup>lt;sup>1</sup>Costs presented are in 2025 dollars

#### **Next Steps**

It is recommended that the Village use the enclosed engineering report to apply for additional financial assistance for funding the design and construction of the recommended alternative. In addition, we also recommended the following:

- Apply for financial assistance for funding the design and construction of the recommended alternative.
- Collect and analyze updated flow information for the service area following completion of the water meter replacement project.
- Complete necessary engineering and design tasks for the recommended alternative including a site survey and parcel investigations.
- Obtain easements for sewer mains not passing through a parcel being served and permanent easements necessary for system maintenance.
- Obtain necessary permits including a SPDES permit and construction permits where sewer mains cross state roads.
- Construction will be awarded and commence following receipt of reasonable bids.
- Testing and start-up will begin as construction nears completion and service connections are made.

We understand that installation of a new wastewater collection and treatment system is a complex and costly undertaking, but we hope that this report will meet the Village's goal of understanding the options available for implementing a wastewater system and we look forward to assisting the Village with the next steps in the process.

#### **Funding Agency Comments**

Comments on the revised April 2024 Wastewater Feasibility Evaluation report were received on February 10, 2025. Modifications to the report to address these comments were made in this July 2025 revision of the report but did not impact the report conclusions which are summarized in this letter.

Please contact Erin Moore at 845-516-5835 if you have any questions regarding this report.

Very truly yours,

**T&B Engineering and Landscape Architecture, PC** 

Erin K. Moore, PE, BCEE Senior Project Manager



# Section 1 Project Planning

#### 1.1 Introduction

This report presents a wastewater preliminary engineering report performed for the Village of Millerton, New York. This evaluation has been performed to determine whether a municipal wastewater disposal system is needed within the Village and, if it is determined to be necessary, the most appropriate and cost-effective means of wastewater collection and disposal for the Village.

The need for community wastewater collection and treatment systems is constantly evolving. Historically, initial efforts were focused on collection and disposal and were driven by the need to reduce human disease. That era was followed by a focus on the elimination of water pollution effects, allowing native marine organisms to return to normal growth patterns and allowing full human recreational use. Currently, community wastewater collection and treatment systems have begun to redefine wastewater as a valuable resource. As such, when proposing alternatives for addressing wastewater needs this document uses the term "water resource recovery and return systems". This modern terminology embraces the concept that water is the most valuable resource in the world.

The Village is currently served by individual (residential/commercial) subsurface wastewater disposal systems (primarily septic tanks with leachfields) and is un-sewered. The study area boundary for this evaluation is the water service area which encompasses portions of the Town of North East and the entire Village of Millerton. The study area boundary is shown in Figure A.1.

The following tasks were performed as part of this evaluation and are described in the Sections that follow:

- 1. Service Area Delineation
- 2. Wastewater Flow Estimates
- 3. Evaluation of Collection, Treatment, and Disposal Alternatives
- 4. Cost Estimates for the Developed Alternatives
- 5. Recommendations & Implementation Procedures

Tighe & Bond, who provides services in New York through T&B Engineering and Landscape Architecture, PC (Tighe & Bond), has been engaged by the Village of Millerton to prepare this Engineering Report in a format consistent with NYS Environmental Facility Corporation (EFC) New York State Clean Water Revolving Fund Engineering Report guidelines and the United States Department of Agriculture (USDA) preliminary engineering report guidelines per RUS Bulletin 1780-2.

### 1.2 Previous Planning Efforts

Prior planning efforts for the Village of Millerton were reviewed as part of this evaluation to obtain background information and previous approaches. The following documents were reviewed or referenced as part of this effort and are described in this report Section:

- Preliminary Engineering Report for Millerton Central Sewer District Village of Millerton and Town of North East, C.T. Male Associates, P.C., 2009
- Groundwater Resource Report, Dutchess County Aquifer Recharge Rates & Sustainable Septic System Density Recommendations, The Chazen Companies, 2006
- Town of North East & Village of Millerton Comprehensive Plan, Dutchess County Department of Planning and Development, 1992
- Town of North East / Village of Millerton Comprehensive Plan, 2019

#### **Preliminary Engineering Report Millerton Central Sewer District (2009)**

This document is a preliminary engineering report for the establishment of a sewer district for the Village of Millerton. The report provides general cost estimates for several potential services areas as well as construction costs for the recommended wastewater treatment system. The Preliminary Engineering Report recommended a wastewater collection system consisting of conventional gravity sewers and grinder pumps which would deliver the raw wastewater to a steel packaged extended air activated sludge plant capable of treating 80,000 gallons-per-day (gpd).

While the C.T. Male report does provide costs for several conventional treatment scenarios, potential service areas were based only upon zoning and use analysis completed by the Joint Committee; no formal wastewater needs analysis was completed. Additionally, the report focused on conventional wastewater collection and treatment systems and did not consider alternative technologies which could present substantial cost savings for the Village.

#### **Groundwater Resource Report (2006)**

The Groundwater Resource Report was intended to provide updated understandings of aquifer recharge rates as well as provide updated guidance for sustainable densities of septic systems throughout Dutchess County, NY. The septic system density analysis is relevant to this report and provides general guidance for the minimum densities of onsite septic systems in the Village.

The Groundwater Resource Report recommended the minimum average parcel sizes for traditional onsite septic design (septic tank and leachfield) between 1.2 and 1.4 acres per system where hydrologic soil group (HSG) Type A is present, between 1.6 and 1.9 acres per system where HSG Type B is present, between 3.0 and 3.5 acres per system where HSG Type C is present, and as much as 5.4 to 6.2 acres where HSG Type D is present.

#### Comprehensive Plan (1992 & 2019)

The 1992 Comprehensive Plan discusses the Town and Village goals and objectives which are described in greater detail in Section 3.2.3 of this report. The 1992 Comprehensive Plan recognized ongoing issues with septic systems in the Village and established a goal to further investigate the need for a centralized sewage disposal system which would primarily serve the Village of Millerton and a portion of the surrounding areas (the water supply area).

The joint Comprehensive Plan between the Town of North East and the Village of Millerton was updated and adopted in 2019. One of the capital improvement projects identified in the 2019 Comprehensive Plan to meet the economic vibrancy goal is to plan and construct a public sewer system for the Village and areas adjacent to the Village.

#### 1.3 Site Information

#### 1.3.1 Location & Population Trends

The Village of Millerton is in the northeastern corner of Dutchess County within the Town of North East, near the border of Connecticut. The Village of Millerton lies within the Long-Island Sound Watershed. The Village is approximately 1.0 square mile including residential and commercial uses. The entire study area is approximately 1.7 square miles. Figure A.1 shows the Village of Millerton boundary and the study area boundary.

The Town of North East had a total population of 2,971 at the time of the 2020 census. The population of the Village of Millerton according to the 2020 census was 921, representing approximately 31% of the Town population. The Town of North East and the Village of Millerton had populations of 3,037 and 956, respectively at the time of the 2010 census. The most recent population estimate for the Town of North East was 2,957 and for the Village of Millerton it was 871 according to the American Community Survey (ACS) 2021 population estimates.

While there are no formal population projections for the Village of Millerton or Town of North East, the census data and population estimates from 2010 through 2021 indicate a relatively stable population. Based on previous trends, the population in the planning area is expected to remain relatively stable over the 20-year planning period.

#### 1.3.2 Geologic & Topographic Conditions

The study area is composed mainly of silty loam soils of two main soil types, Stockbridge silt loam and Copake gravelly silt loam. Stockbridge silt loam, of which most of the study area is composed, consists of very deep, well drained soils formed from calcareous loamy till. They are somewhat level to moderately steep soils on till plains, smooth hills, and low ridges, with slope ranges from 3 to 25 percent. Permeability ranges from moderate in the surface layer and subsoil to moderately slow or slow in the substratum. The Stockbridge soils are generally HSG Type C or D.

Copake gravelly silt loam, which is present in the center of the study area, consists of well drained soils formed from loamy mantled stratified drift and glacial outwash. They are nearly level to steep soils on outwash plains and terraces with slope ranges from 0 to 30 percent. Permeability ranges from moderate to moderately rapid in the surface layer and subsoil and from rapid to very rapid in the substratum. The Copake soils are generally HSG Type A or B. Figure A.2 identifies all soil types located in the study area.

Bedrock in the study area is Wappinger Limestone which is a light to medium gray, banded travertine. Depth to bedrock is commonly more than 6 feet. The National Resource Conservation Service (NRCS) Soils Report for the study area is attached in Appendix B.

A brief description of each of the primary soil types found in the study area is below:

Cu, Cx - Copake fine sandy loam consists of well drained soils formed in loamy mantled stratified drift and glacial outwash. The soils are moderately deep to stratified sand and gravel and are very deep to bedrock. They are nearly level to very steep soils on outwash plains, terraces, kames, eskers, and moraines. Permeability is moderate or moderately rapid in the surface layer and subsoil, and rapid or very rapid in the substratum.

Sk, Sm - Stockbridge loam consists of very deep, well drained soils formed in loamy calcareous till. They are somewhat level to moderately steep soils on till plains, smooth hills, low ridges and drumloidal landforms. Slope ranges from 3 to 25 percent. Permeability is moderate in the surface layer and subsoil and moderately slow or slow in the substratum.

Gs - Georgia loam consists of very deep, moderately well drained soils on glaciated uplands. They formed in loamy till. Permeability is moderate in the solum and slow in the substratum. Saturated hydraulic conductivity is moderately high or high in the solum and moderately low or moderately high in the substratum. Slope ranges from 0 to 60 percent.

Mn - Massena silt loam consists of very deep, somewhat poorly drained or poorly drained soils on uplands. They are nearly level to strongly sloping soils that formed in till dominated by siliceous rock with some limestone. Slope ranges from 0 to 15 percent.

Nw, Nx - Nassau channery silt loam consists of shallow, somewhat excessively drained soils formed in till. They are nearly level to very steep soils on bedrock controlled, glacially modified landforms. Bedrock is at a depth of 10 to 20 inches. Slope ranges from 0 to 70 percent.

Dw – Dutchess cardigan complex consists of well drained soils formed from phyllite, slate, schist, and shale. They are slightly sloping to steep soils. Slope ranges from 5 to 20 percent. Bedrock is at a depth of 20 to 40 inches.

Most of the topography in the study area is relatively level (0-15% slope). However, the steepness of the topography increases towards the south and northwest sides of the study area. Figure A.3 shows the topography in and around the study area.

#### 1.3.3 Environmental Resources & Floodplain


The study area was found to be within the New York State Department of Environmental Conservation (NYSDEC) rare plants and rare animals check zone as shown on their Environmental Resource Mapping tool, Figure 1.1 below. The locations shown in the Environmental Resource Mapper Rare Plants and Rare Animals layer are not precise locations. Rather, they show those generalized areas where NY Natural Heritage has information in its databases regarding rare animals and/or rare plants. These generalized areas show the vicinity of actual, confirmed observations and collections of rare animals and rare plants. The precise locations are not provided by this tool.

Webatuck Creek flows generally north to south through the Village of Millerton. The Kelsey Brook flows generally east to west through the Village to its confluence with the Webatuck Creek just south of South Center Street. An unnamed tributary also flows into Webatuck Creek from the west. All streams within the study area are Class C waterbodies as defined by the NYSDEC, and Webatuck Creek is also noted as trout waters.

As shown on Figure 1.1, there are NYSDEC regulated freshwater wetlands within the study area and a registered natural community to the north. The natural community is noted as an Appalachian oak-hickory forest at Alander Mountain. The specific species of rare plants and/or rare animals that are in this vicinity are not provided by the Environmental Resource Mapper Tool.

Figure A.4 identifies the U.S. Fish and Wildlife National Wetlands Inventory (NWI) wetlands; much of the NWI wetlands overlap with the NYSDEC regulated wetlands shown on Figure 1.1.

The 100- and 500-year flood zones as delineated by the Federal Emergency Management Agency (FEMA) are shown on Figure A.4. The mapped flood zones are adjacent to Webatuck Creek and Kelsey Brook. As shown on Figure A.4, portions of the study area are within or adjacent to the flood zones.



Village of Millerton NYSDEC Environmental Resources Mapper

#### 1.3.4 Land Use/Zoning

The Village of Millerton makes up most of the study area; the parcels within the Village boundary fall under the Village of Millerton zoning districts. Figure A.5 shows the zoning districts for the Village of Millerton. The parcels within each of the zoning districts in the Village and the minimum lot sizes for each district are summarized below:

#### Low Density Residential (R1A)

- Includes areas to the far south and far west of the Village.
- Minimum lot size is 1 acre.

#### **Medium Density Residential (R20,000)**

- Comprises large areas to the north, south, and west parts of the Village.
- Minimum lot size varies depending on availability of sewer service.

#### **High Density Residential (R10,000)**

- Includes the developed area between South Center Street and Route 62.
- Minimum lot size varies depending on availability of sewer service.

#### **General Business District (GB)**

- Includes the lots along Main Street.
- Minimum lot coverage must be 30% of the land area. No minimum lot sizes.

#### **Planned Residential/Business District**

- Includes a small group of lots along Route 22.
- Minimum lot coverage must be 30% of the land area. No minimum lot sizes.

#### **Limited Business District**

- Includes an area towards the north side of the Village along Route 22.
- Minimum lot size is 1 acre.

#### **Highway Business Districts I (HB-I)**

- Includes four lots near the intersection of Main Street and Maple Avenue.
- Minimum lot sizes are 1 acre.

#### Land Conservancy District (LC)

- Includes lots along Webatuck Creek and several larger lots in the northeast section of the Village.
- Minimum lot size is 1 acre.

#### **Industrial District (M)**

- One large industrial parcel off Route 22 occupied by Arnoff Moving and Storage.
- Minimum lot size is 3 acres.

The remaining parcels in the study area (outside the Village boundary) fall under the Town of North East zoning districts. A map of the zoning districts for the Town of North East is attached in Appendix C. The parcels within each of the Town zoning districts in the study area and the minimum lot sizes for each district are summarized below:

#### Agricultural (A5A)

- Generally, to the west of the Village of Millerton.
- Minimum lot size is 5 acres.

#### **Boulevard Districts**

- Generally, to the east of the Village of Millerton along Route 44.
- No minimum lot sizes.

#### **Highway Business III (HBIII)**

- Generally, to the north of the Village of Millerton along Route 22 and Route 60.
- Minimum lot size is 1 acre.

#### Land Conservation (LC)

- Primarily along Webatuck Creek.
- Minimum lot size is 1 acre.

#### **Medium Density Residential (R20000)**

- Includes areas to the north and east of the Village of Millerton.
- Minimum lot size varies depending on availability of sewer service.

#### **Very Low Density Residential (R3A)**

- Includes areas to the south of the Village of Millerton.
- Minimum lot size is 3 acres.

#### 1.3.5 Environmental Justice Areas

The Village of Millerton nor the Town of North East (shaded yellow) was not found to be in a Potential Environmental Justice Area (PEJA) as indicated (in purple shading) by the NYS DECinfo Locator mapping presented in Figure 1.2, below.




FIGURE 1.2
Millerton/North East Area Environmental Justice Areas

# 1.4 Community Engagement

The Village of Millerton and Town of North East have taken several steps to engage the community regarding the implementation and feasibility of a new sewer system. Below is a timeline which illustrates the actions already taken, as well as the planned approach to continuously involve the community and encourage civic participation throughout the project.

 2018 – Village of Millerton sends out 478 wastewater surveys to businesses and homeowners in the Village and Town to collect input from community members regarding their need and desire for a sewer system. The Village of Millerton hired Tighe & Bond to perform the wastewater feasibility evaluation.

- 2019 Several public meetings and workshops were held to discuss updates to the Town of North East & Village of Millerton Comprehensive Plan. These discussions included the feasibility of creating and funding a sewer system. The comprehensive plan was adopted in November 2019 and includes a capital improvement project to provide a public sewer system serving the Village and immediate surrounding areas in the Town.
- <u>2019</u> Village of Millerton met with Tighe & Bond several times to discuss progress on the wastewater feasibility evaluation, discuss district delineation, review results of the study, and prepare for public presentations.
- 2020 Presentations of the wastewater feasibility evaluation were held for the draft report and the final report. The presentations were a joint effort between the Village, Town, and Tighe & Bond. The presentations were given to the public to explain the results, recommendations, financial impacts, and next steps. The meeting was held for the stakeholders in the proposed sewer district and the public and many of the property and business owners attended the meeting, provided feedback, and asked questions regarding the proposed sewer district.
- 2021/2022 The Village of Millerton, Town of North East, and Tighe & Bond worked together to update the preliminary engineering report in 2021 and 2022. This included revisions to the service area delineation, flow estimate, and treatment and disposal system approach as the property that was originally intended for the system could not be acquired. During this process, the Village contacted parcel owners to gauge their interest in connecting to the system the feedback from the property owners was used to revise the service area delineation. Several meetings and presentations were held during the revision process and to present the final revisions including public meetings on August 2, 2021, October 25, 2021, March 7, 2022, March 21, 2022, June 6, 2022, October 11, 2022, and November 28, 2022.
- <u>2022</u> Tighe & Bond worked with the Village of Millerton and Town of North East to develop a Map & Plan for the Village and a Map, Plan, and Report for the Town of North East. These documents were critical steps to define the service areas and move towards the next steps in the project.
- August 2, 2022 The Village received a \$200,000 Dutchess County Municipal Investment Grant (MIG) for preliminary engineering.\*
- <u>January 9, 2023</u> The Village of Millerton Village Board approved a resolution to accept the Map and Plan for the Village Sewer System
- <u>January 23, 2023</u> The Village of Millerton as Lead Agency completed the State Environmental Quality Review Act (SEQR) process for the project. The Village Board adopted a negative declaration finding that the proposed action would not result in any significant adverse environmental impacts and that a draft environmental impact statement would not be prepared.
- March 29, 2023 A public presentation regarding the Town Map, Plan & Report was completed.
- June 20, 2023 A public hearing for the formation of the Town of North East Sewer District was held.
- <u>July 2023</u> The Qualifications Based Selection Process for Wastewater System Design Engineering was completed and an engineering contract for Preliminary Design was awarded.\*

- <u>2023</u> Intermunicipal agreement between the Village of Millerton and Town of North East developed.\*
- <u>2024</u> The Village and Town have received a \$5,082,099 Intermunicipal Grant (IMG) and a \$959,752 Congressionally Directed spending Community Project Funding Grant (CPF)\*
- <u>2024</u> The Village and Town advanced the preliminary design phase which included house-to-house inspections of the properties in the service area, surveying, and geotechnical investigations.\*
- Ongoing The Village/Town Wastewater committee have engaged directly via in person or telephone meetings with most parcel owners that would be impacted by the project and/or located in the proposed service area.
- Ongoing The Village of Millerton & Town of North East intend to continue to update the public regularly regarding the status of this wastewater project and the funding and revenue strategies.
- Ongoing The Millerton News, an independently owned community weekly newspaper covering both Millerton and North East has regularly run articles on the project starting in 2020.

# Section 2 Need for Project\*

The Village of Millerton identified issues with septic systems in the Village over three decades ago. The Village does not currently have a public wastewater collection or treatment system although there is relatively dense development in the Village center and commercial areas in the Town of North East. Most of the parcels are served by individual subsurface septic tanks and leachfields while some have even older disposal systems such as seepage pits or cesspools. Some of these older systems are generally regarded as outdated and no longer allowed in new construction.

The 1992 Comprehensive Plan identified the need to evaluate the feasibility of various sewage management options and, more recently, the 2019 Comprehensive Plan listed the construction of a public sewer system as one of the capital improvement projects necessary to meet the economic vibrancy goal. Construction of the sewer system is expected to allow for expansion of businesses and encourage growth within the sewer district thus limiting urban sprawl, which will help achieve another goal of the Comprehensive Plan which is to preserve the rural character of the Town.

As discussed later in this report, a survey was administered by the Village as part of this study. The survey included 105 respondents and identified the threat that the lack of sewer infrastructure imposes on the protection of natural resources and on controlled infrastructure growth. The survey also confirmed that there are wastewater disposal problems in the Village most likely due to site specific and localized conditions and that there are a significant number of property owners who feel that wastewater improvements are necessary for the Village.

In speaking with residents and business owners in the Village and Town, several community members have expressed that expansion of their business or residential housing is limited due to their septic system capacity. Businesses could expand or upgrade their existing systems to meet the required capacity; however, the expansion or replacement of their existing onsite septic system is often not feasible due to the relatively small parcel sizes and since they are required to have enough space for a 100% reserve area for any new or renovated system.

A central sewer system would make it easier and more attractive for businesses to expand and would allow lot sizes to be smaller in the sewer district which would allow for greater density and number of businesses. It would also allow for mixed-uses such as apartments to be built above storefronts which would otherwise be futile without providing a public wastewater system as the small existing lots are not able to support the larger flow demands.

A community wastewater system would provide several benefits, including:

- Replace outdated septic systems
- Allow existing businesses to reach their full capacity
- Encourage additional growth and new businesses in service area
- Allow for multi-use buildings
- Provide environmental protection by replacing failing or outdated septic systems
- Promote sustainable community development that benefits all residents
- Encourage capital investments in-Town



# **Section 3 Wastewater Disposal Needs Analysis**

#### 3.1 General

The first component of this study is the evaluation of the need for wastewater disposal improvements in the study area. A sewer district can be delineated once the need for wastewater disposal is determined. The Village is currently served by individual subsurface wastewater disposal systems (including septic tanks with seepage pits, leachfields, or sand filters) and wastewater storage tanks (i.e. tight tanks) which are pumped on a regular basis.

From review of previous documentation and reports discussed in Section 1.2, it appears likely that failing wastewater disposal systems and properties with no on-site disposal methods are a serious issue of concern to the Village and are strong encouragements for forming a sewer district. Although previous reports have used zoning and use methodologies for the basis of service area delineation, this evaluation utilized several additional steps to determine the correct delineation for a potential sewer district. Wastewater disposal need was determined by several methods, including:

- Evaluation of the results of a wastewater survey distributed to each business/resident served in the Village of Millerton water district;
- Evaluation of site conditions that may indicate constraints to individual onsite wastewater disposal systems including soil type, shallow depth to groundwater or bedrock, parcel size, and parcel density;
- Evaluation of existing land use and zoning constraints, and;
- Evaluation of comprehensive plan goals and priorities which may impact the need for wastewater treatment improvements.

For the purposes of this evaluation, the study area has been divided into eight sub-areas as shown in Figure A.6. The sub-areas were created based upon zoning, similar use characteristics, geographical features, and constructability considerations. The sub-areas have been delineated for comparison purposes and to help identify the areas of highest priority. The portions of the study area not included in one of the eight sub-areas were excluded due to their large parcel sizes, low parcel density, and/or geographic isolation. The eight sub-areas are:

- Main Street: based around the center of the Village including most of Main Street and all of Century Boulevard. The west border of this sub-area is Webatuck Creek.
- Main North: includes the portion of the study area to the north of Simmons Street, bordered to the west by North Center Street, to the east by North Maple Avenue, and to the north by Highland Street.
- Main East: includes mostly commercial parcels to the east of North Maple Avenue along Route 44. Most of this sub-area is outside of the Village boundary.
- Main South: includes the high density residential areas immediately south of the Main Street sub-area. The area is bordered on the south by Fish Street.

- Main West: includes eleven mixed use parcels around the intersection of Main Street and Route 22.
- Route 22 North: includes a mix use of planned residential parcels and limited business parcels along Route 22.
- Route 22 South: mostly includes medium density residential parcels along Route 22, Mill Road, and West Street.
- Travers Place: Includes the residential neighborhood off Travers Place on the far east side of the Village.

# 3.2 Determining and Prioritizing Need

#### 3.2.1 Wastewater Survey

Questionnaire surveys were mailed to each of the 478 water service users in the study area and the Village of Millerton. The surveys requested information about each individual's on-site wastewater disposal system and related residence information. This survey was intended to evaluate homeowners' and business owner's experiences and the perceived need for wastewater disposal improvements such as new sewers, within their individual neighborhoods, or anywhere in the Village. The survey also included areas for comments on the needs of wastewater improvements in the Village. In addition, the survey inquired about groundwater conditions in basements to collect information about neighborhoods with groundwater problems, which can lead to failing wastewater systems. A cover letter from the Village was also attached with each survey. A copy of the wastewater survey questionnaire and cover letter are included in Appendix D.

A total of 105 surveys were returned, representing a 22% response rate overall.

The responses for each sub-area are provided in Table 3.1. The total percent response rate shown in Table 3.1 is less than 22% because only 434 of the 652 parcels in the study area are included in the sub-areas.

**TABLE 3.1** – Survey Response Summary by Sub-area

Sub-Area	Number of	Number	%
Sub-Alea	<b>Parcels</b>	Responding	Responding
Main Street	82	15	18%
Main North	132	26	20%
Main East	21	1	5%
Main South	57	12	21%
Main West	11	1	9%
Route 22 North	34	4	12%
Route 22 South	37	6	16%
Travers Place	60	13	22%
TOTAL:	434	78	18%

The results of the wastewater questionnaire survey are discussed below:

Out of all of the responses, 8% reported problems with their wastewater disposal system. These problems included failing leachfields, frequent pumping, and frequent back-ups. Table 3.2 summarizes the location of the respondents reporting problems. The remaining 93% did not report any problems with their wastewater disposal system. Figure A.7 shows the parcels where issues were reported.

Millerton Wastewater Preliminary Engineering Report

Sub-Area	Number Reporting	% Reporting WW Problems	<b>Problem Streets</b>
Main Street	1	7%	Main Street
Main North	1	4%	North Center Street
Main East	0	0%	-
Main South	2	17%	S Center St
Main West	0	0%	-
Route 22 North	1	25%	Brook Lane
Route 22 South	1	17%	Mill Road
Travers Place	0	0%	-

TABLE 3.2 - Reported Wastewater Disposal Problems by Sub-area

Of the 105 respondents, 40% felt that a wastewater treatment system is required for the Village; 45% felt no treatment system was required, and 15% were unsure. Of the 40% who felt a treatment system is needed, 3% felt the entire Village requires a treatment system, 12% felt a wastewater system should be constructed for the Business District, 19% felt a wastewater system should be constructed at the highway garage, 5% felt the wastewater system should be constructed outside of town, 40% were unsure, and 21% did not answer. However, it appears that the question concerning the service area was misinterpreted by most respondents. The question was intended to ask what area they believe should be serviced by a sewage system, not where, specifically, a wastewater treatment system should be constructed. Therefore, the responses to this particular question are not being considered as part of this evaluation.

A total of 24% of respondents reported having problems with water in their basements. Of the 24% who reported problems with water in their basement, 4% reported that problems occur every day, 68% reported that problems occur during rain events, and 28% reported that problems occur during the Spring. Figure A.7 shows parcels where basement water problems were reported.

As previously noted, comments on wastewater disposal needs were solicited in the survey. These are not quantifiable by percentage as not every respondent chose to comment. In general, those who had wastewater problems or felt the Village needs additional wastewater treatment systems, made comments supporting a wastewater treatment project. One comment was received expressing that the cost of the system should only be paid for by those who would be serviced by the system. No other respondents who opposed the system provided comments.

The overall indication that the wastewater survey results provide is that:

- There was a significant number of respondents who felt wastewater improvements were necessary for the Village (40%).
- Generally, the Village of Millerton has isolated wastewater disposal problems most likely due to site specific and localized conditions.
- The majority of basement water problems were reported in the developed residential areas.

#### 3.2.2 Site Conditions

Several site conditions can contribute to poor wastewater disposal systems. Some of which include:

- Small Lot Sizes
- High Parcel Density
- Poor Soil Conditions
- High Groundwater Levels
- Shallow Depth to Bedrock
- Inappropriate/Heavy Usage

#### **Lot Sizes and Density**

To provide adequate space for a septic tank, soil adsorption system, and reserve area, as well as sufficient room for a building and setback requirements, a minimum lot size is typically required. As discussed in Section 1.2 of this report, review of the Groundwater Resource Report indicated a recommended minimum lot size between 1.2 - 1.4 acres for HSG Type A soils and 1.6 - 1.9 acres for Type B soils. For the purpose of this evaluation, a parcel size of less than 1 acre was considered inadequate for onsite waste disposal.

In the Village, separation distances between wells and septic systems are not an issue as there is a public water system. Parcels less than 1 acre may have difficulty conforming to the New York State Department of Health (DOH) regulations. The DOH regulations include:

•	Minimum distance from septic tank to building	10 feet
•	Minimum distance from leachfield to building	20 feet
•	Minimum distance from leachfield to the street	10 feet
•	Minimum distance from leachfield to adjacent property line	10 feet
•	Minimum distance from leachfield to well	100 feet

In many cases, the building takes up a significant portion of the parcel, leaving very little area for an adequate wastewater disposal system. Table 3.3 provides the percentage of lots within each sub-area that are less than 1 acre in size.

Parcel size is typically related to parcel density. Highly developed areas usually have small lot sizes spaced closely together. These areas are not well suited for onsite disposal systems simply due to limited space. The average lot density for each sub-area was computed for comparison purposes and is summarized in Table 3.4. As shown in Table 3.4, the average lot density is greatest in the Main Street sub-area and second greatest in the Main South sub-area. Main North also has a relatively high lot density and the Main East, Main West, and Route 22 North sub-areas have the lowest relative lot densities.

**TABLE 3.3** – Parcels Less than 1 Acre

Sub-Area	% Lots less than 1 Acre
Main Street	96%
Main North	97%
Main East	62%
Main South	95%
Main West	91%
Route 22 North	59%
Route 22 South	81%
Travers Place	83%

**TABLE 3.4** – Average Lot Density

Sub-Area	Density (Lots/Acre)
Main Street	3.2
Main North	2.2
Main East	0.8
Main South	2.7
Main West	0.8
Route 22 North	0.6
Route 22 South	1.7
Travers Place	1.5

#### **Poor Soil Conditions**

When soils are 'tight' and have percolation rates greater than 60 minutes/inch, wastewater disposal fields are much more likely to fail and create surface ponding or clogging problems. In general, the soils in the study area are well drained Copake and Stockbridge soils and are not likely to have excessive percolation rates. As long as percolation rates are in accordance with NYS DOH Standards, and considering there is a public water supply, these soils should be appropriate for wastewater disposal adsorption fields. In general, there are no large groups of parcels that appear to be significantly affected by poor soils. The HSG soil types for the study area are shown in Figure A.2.

#### **High Groundwater or Shallow Bedrock**

The vertical separation to seasonal high ground water is an additional important requirement in siting subsurface disposal systems. A minimum depth of 4 feet between the bottom of the leachfield to groundwater is required per NYS DOH regulations. There are isolated portions of the study area where the depth to groundwater is less than 4 feet. One of the largest of the areas is around the Millerton Recreation Park and may explain some of the septic system and basement issues reported in that area. A significant portion of the study area along Gay Road also has high groundwater levels, however this portion of the study area is not included in the sub-areas and had no reported basement problems. No other sub-area besides Main East has areas of shallow depth to groundwater (see Figure A.2).

The surveys distributed to the Village also inquired about flooded basements and inquired as to when the flooding occurred. Parcels that reported basement flooding problems are highlighted on Figure A.7. Table 3.5 displays the basement flooding reports for each subarea.

IABLE 3.3 - F	TABLE 3.5 - Reported basement Flooding Problems					
Sub-Area	% Reporting Problem (All causes)	% Reporting Problem (Seasonal only)				
Main Street	27%	13%				
Main North	31%	12%				
Main East	0%	0%				
Main South	25%	0%				
Main West	0%	0%				
Route 22 North	50%	25%				
Route 22 South	17%	0%				
Travers Place	15%	8%				

TABLE 3.5 - Reported Basement Flooding Problems

It is important to note that several respondents noted that rain appeared to cause water to enter their basement. This is not typically considered an indicator of a high ground water table, rather, it indicates that the basement walls may be improperly sealed or the house improperly guttered. Respondents who indicated flooding is a problem that occurs typically in the spring and during snowmelt are more likely to have their basements affected by a high water table.

Although there are areas of groundwater impacting basements, the results of the survey indicate few problems with failing leachfields in these areas. It is likely that seasonal groundwater in these areas is high enough to impact a basement which extends 6 feet into the ground, but not high enough to significantly affect disposal fields. It should be made clear that individual wastewater disposal systems contribute very little to groundwater and have almost no influence on groundwater elevation. Installation of a wastewater collection system would have no effect on seasonal basement flooding. Discharge of sump pumps to a wastewater collection system is also prohibited.

In addition to ground water levels, the vertical separation to bedrock is an important requirement in siting subsurface disposal systems. A minimum depth to bedrock of 4 feet is required per NYS DOH regulations. There are small isolated portions of the study area where bedrock can be found shallower than 4 feet according to the NRCS soil type designations for the area. This may explain some reported basement water problems, particularly for a series of reported problems in the Route 22 South sub-area along Mill Street. There are no other areas of shallow bedrock within the boundaries of the sub-areas.

#### 3.2.3 Village Priorities

The comprehensive plan, a joint plan for the Town of North East and the Village of Millerton, provides goals and recommendations regarding the following topics:

- Rural Character
- Agriculture
- Environment
- Maintain Village Center
- Encourage Limited Growth
- Promote Housing Alternatives
- Supply of Clean Drinking Water
- Provide Sound Disposal of Wastes
- Transportation
- Historic Conservation
- Recreation

In review of the comprehensive plan, wastewater disposal improvements are believed to impact the above items in the following manner as discussed in Table 3.6:

**TABLE 3.6** – Comprehensive Plan Goals & Wastewater Disposal Impacts

TABLE 3.0 - Comprehensive Plan Goals & Wastewater Disposal Impacts					
Item	<b>Brief Description of Goals</b>	Impact			
Rural Character/ Development	Encourage high quality in new development Discourage high density development Provide designated areas for commercial development	A wastewater treatment system may encourage development in previously undeveloped areas, which may oppose the goals to prevent development in these areas.			
Agriculture	Support more efficient land use Protect agricultural operations Cooperate with local land trusts Maintain significant areas of prime agricultural land	A wastewater treatment system is not expected to affect agriculture or agricultural activities.			
Maintain Village Center	Encourage the location of community facilities in the Village Discourage development outside the Village	A wastewater treatment system is expected to have positive impacts for maintaining the development within the Village.			
Environment	Control and provide for proper disposal of wastes Protect surface and groundwater resources Protect natural drainage areas Limit erosion and sedimentation	An improved wastewater treatment system should have positive impacts on protecting water resources.			
Encourage Limited Growth	Encourage the expansion of employment opportunities Encourage small businesses Encourage the development of light industry	A wastewater treatment system is expected to encourage limited growth in the Village.			
Promote Housing Alternatives	Encourage access for all residents Encourage housing for people of all ages Concentrate relatively dense housing to the Village area	A wastewater treatment system is expected to encourage housing alternatives.			
Supply of Clean Drinking Water	Pursue the development of a centralized water system Ensure protection of surface and groundwater resources	A centralized wastewater treatment system is expected to further protect the water supply system.			

**TABLE 3.6 Continued -** Comprehensive Plan Goals & Wastewater Disposal Impacts

Item	Brief Description of Goals	Impact
Provide Sound Disposal of Wastes	<ul> <li>Pursue the development of a centralized sewage disposal system.</li> <li>Ensure protection of surface and groundwater resources.</li> </ul>	The goal of this evaluation is to identify the level of wastewater treatment required. An improved wastewater treatment system is expected to improve the health of local groundwater resources.
Transportation	<ul> <li>Encourage public transportation that would serve the Town and Village</li> <li>Ensure adequate off-street parking is provided.</li> <li>Encouraged planned pedestrian walkways and bikeways.</li> </ul>	A wastewater treatment system is expected to have no specific impact on transportation goals.
Historic Conservation	<ul><li>Designate historic sites and districts</li><li>Identify and protect scenic roads</li></ul>	A wastewater treatment system is expected to have no specific impact on historical goals.
Recreation	<ul> <li>Encourage the use and improvements of all community facilities</li> <li>Encourage public access to lakes and streams</li> </ul>	A wastewater treatment system discharging directly to Webatuck Creek may been seen negatively.

Based upon the results of Table 3.6, the following Table 3.7 summarizes the Village goals that a wastewater treatment system may impact, and whether the impact is negative or positive. Note that the "Provide Sound Disposal of Wastes" is a Comprehensive Plan goal, and the goal of this report is to determine the level of wastewater treatment necessary to meet that goal, therefore it is not included in Table 3.7 as being influenced positively or negatively.

TABLE 3.7 - Wastewater Treatment Impacts

Mastewater freatment impacts			
Issue	Treatment System Impact	Comments	
<ul> <li>Rural</li> <li>Character/Dev.,</li> <li>Maintain Village</li> <li>Center,</li> <li>Encourage</li> <li>Limited Growth</li> </ul>	Positive	Intelligent delineation of a sewer district will encourage limited development in the Village Center by meeting the needs of high sewer demand business while not facilitating unneeded expansion of residential areas.	
<ul><li>Environment,</li><li>Drinking Water</li></ul>	Positive	Removal of old and unmaintained on-site disposal systems will aid in protection of local water sources.	
- Recreation	Negative	A wastewater treatment system discharging to Webatuck Creek may been seen negatively by some members of the community who rely on the water way for recreation activities.	

#### **3.2.4 Summary**

The items described in the Sections above were used to develop a priority of wastewater treatment needs. To create a wastewater treatment needs priority ranking, each of the sub-areas were given a 0-7 ranking per each issue which affects wastewater treatment, 7 being the highest need, and 0 being the lowest. Table 3.8 summarizes the results.

**TABLE 3.8** – Wastewater Needs Ranking

Sub-Area	WW Problems	Small Lots	Lot Density	High GW	Shallow BD	Village Goals	Total
Main Street	5	6	7	5	6	7	36
Main North	4	7	5	6	6	2	30
Main East	3	1	2	1	6	6	19
Main South	6	5	6	4	6	3	30
Main West	3	4	2	1	6	4	20
Route 22 North	7	0	1	7	6	5	26
Route 22 South	6	2	4	3	7	1	23
Travers Place	3	3	3	2	6	0	17

#### **Wastewater Problems**

Refer to Table 3.2. The Route 22 North sub-area had the highest reported percentage of problems followed by Main South, Route 22 South, Main Street, and Main North. The Main East sub-area, Main West, Route 22 North, and Travers Place had no reported wastewater problems.

#### **Small Lots**

Refer to Table 3.3. The Main North sub-area has the highest percentage of lots less than 1 acre, followed by Main Street, Main South, Main West, Travers Place, Route 22 South, Main East, and the Route 22 North sub-area.

#### **Lot Density**

The Main Street sub-area has the highest lot density by far. Main South and Main North also have high lot densities. The remaining sub-areas were ranked accordingly as shown in Table 3.4.

#### **High Groundwater**

The sub-areas were ranked based on the percent of reported basement flooding problems as summarized in Table 3.5. Route 22 North had the highest percentage of reported basement flooding problems. The Main Street, Main North, Travers Place, and Main South sub-areas also had basement flooding problems. The other two sub-areas had no reported basement flooding problems.

#### **Shallow Bedrock**

Refer to Figure A.2. Only two rankings were appointed to this category since only the Main South sub-area has areas where the depth to a restrictive bedrock layer was less than four feet.

#### Village Goals

The Village goals were merged into a single category. A potential sewer district in any of the sub-areas is expected to benefit the environment, therefore each sub-area was primarily ranked based on the development/limited growth goals for each sub-area. Main Street was ranked as the highest need for wastewater improvements because development in this area is encouraged per the Comprehensive Plan. The Main East sub-area was ranked second highest followed by Route 22 North based on land use and zoning types. Main North, Main South, and Travers Place were all ranked lower in this category because they are primarily residential areas where expansion and development are discouraged to maintain rural character.

#### 3.3 Service Area Prioritization

The wastewater needs analysis identified the Main Street area as the area with the greatest need for wastewater improvements. Main South ranked the second highest followed by Main North and Route 22 North. Table 3.9 summarizes the sub-areas from highest priority to lowest priority based on the wastewater needs analysis.

<b>TABLE 3.9</b> – Priority of Sub-Areas			
Priority No.	Sub-Area		
1	Main Street		
2	Main South		
3	Main North		
4	Route 22 North		
5	Route 22 South		
6	Main West		
7	Main East		

Travers Place

The rankings in Table 3.9 can be used to prioritize wastewater service areas.

### 3.4 Wastewater Flows and Loads\*

8

#### 3.4.1 Wastewater Flow Estimates

The 2009 report by C.T. Male Associates, P.C. titled "Preliminary Engineering Report for Millerton Central Sewer District" cited a required treatment capability of 80,000 gpd for their recommended sewer district area. The basis of this calculated flow rate was determined by the Equivalent Dwelling Unit (EDU) method. The EDU method uses a typical single-family house in the district and compares it to all other parcels in the district to assign them an appropriate EDU based on the expected wastewater flow. The sum of all EDUs equates to the total design flow for the district. EDU counts were performed by the Dutchess County Water and Wastewater Authority (DCWWA) in 2018 for the parcels included in the 2009 report. A single EDU was equated to 250 gpd.

A revised wastewater design flow estimate was developed for the newly proposed subareas utilizing the EDU method by adapting the EDU methodology and assignments from the 2009 Report to the newly delineated service areas. The parcels that did not have an assigned EDU from the 2009 report were assigned an EDU based on the water usage (if reliable data was available), zoning designation, and/or publicly available property information. Additionally, historical drinking water production data and flow meter readings were provided by the Village of Millerton and were used for comparison of the estimated wastewater flows. There are 376 metered users in the water district, with 64 of those being non-residential users.\* Flow meter readings for several months were provided and reviewed as part of this evaluation. However, upon review, only 55% of the parcels in the sub-areas had reviewable flow meter data and the data available had significant inconsistencies with typical anticipated water demand and the overall water system production, resulting is very low usage per EDU that was unsuitable to assess per parcel demand.\* This is considered an inadequate portion of users and therefore the flow meter readings were not used for flow estimating purposes.

In lieu of flow meter readings, the daily total water consumption data for the Village of Millerton Water District for the years 2017 - 2022 was provided.\* A summary of the average daily water usage during this time is provided in Table 3.10.

TABLE 3.10 - Village of Millerton Water Use Summary (2017 - 2024)\*

	IADLE 5.	TO VIIIG	ge of Mille	iton wate	1 030 3411	illiary (20	11 202	7)
	2017	2018	2019	2020	2021	2022	2023	2024
Average Daily Flow (gpd)	116,000	122,000	123,000	147,000	157,000	169,000	138,000	120,000
2017-2024 Average Daily Flow (gpd)							136.500	

As shown in Table 3.10, the average daily flow for the entire Millerton Water District from 2017 to 2024 was approximately 136,500 gpd and in total, there are 936 EDUs for the entire Water District. This equates to a flow of approximately 146 gpd per EDU which suggests that the previously used value of 250 gpd is overly conservative. However, using a 146 gpd/EDU approach may underestimate the flows from high use facilities since it takes the entire Water District into account. Therefore, applying the 136,500 gpd to the proposed wastewater service area only (671 EDUs) results in a flow rate of 204 gpd/EDU. To be conservative, flow estimates for the proposed wastewater service areas have been determined using a flow rate of 215 gpd/EDU.\*

A water meter replacement project for the Village of Millerton is currently underway. During this project, all of the existing water meters will be replaced with new meters. As of June 2025, water meters have been installed for approximately 66% of parcels in the proposed wastewater service area. Water usage data for these parcels from June 2023 through June 2025 was reviewed and flow per EDU calculated based on the EDU assignments provided in Appendix E. For the June 2023-June 2024 period for all metered parcels the flow rate was 94 gpd/EDU, for residential only parcels for the same period the flow rate was 122 gpd/EDU. For the June 2024-June 2025 period for all metered parcels the flow rate was 106 gpd/EDU, for residential only parcels for the same period the flow rate was 153 gpd/EDU. These flow rates are much less than calculated using the total water consumption data in Table 3.10 above; the variance is most likely attributable to losses in the water system rather than a sudden decrease in water usage by users. As the water meter replacement project is ongoing and metered data is not available for all parcels in the proposed wastewater service area, the flow conservative rate based on calculated total water consumption data with an added safety factor has been used (215 apd).\*

The resulting flow estimates calculated using the EDU method for each sub-area are summarized in Table 3.11. The EDU assignments for each parcel are in Appendix E.

**TABLE 3.11** – Wastewater Flow Estimates Using the EDU Method


Sub-Area	Residential EDUs	Commercial EDUs	Total EDUs	Estimated Wastewater Flow (gpd)
Main Street	40	91	131	29,000
Main North	67	153	220	48,000
Main East	1	30	31	7,000
Main South	74	12	86	19,000
Main West	9	7	16	4,000
Route 22 North	23	40	63	14,000
Route 22 South	57	2	59	13,000
Travers Place	49	17	66	15,000
TOTAL	319	352	671	149,000

Table 3.11 assumes the same flow per EDU for both residential and non-residential users. There are a total of 81 non-residential users and the majority are office spaces or retail spaces where usage does not typically exceed that of residential users. There are 25 non-residential users with activities such as food preparation where the usage would be expected to exceed that of residential users. As the basis for the flow per EDU is the overall system usage, the higher flow from these users is captured in the average flow calculation and, if anything, this produces a more conservative flow estimate for the other non-residential users. Section B.6.b of the 2014 Design Standards does not state that separate flow estimates for non-residential users should be determined, only that water usage data should be from "existing and similar facilities", which is met through the use of the overall system water usage data.\*

As noted above, a water meter replacement project for the Village of Millerton is currently underway. During this project, all of the existing water meters will be replaced with new meters. Once the new meters are installed, precise flow estimates can be obtained on a parcel by parcel basis. For the purpose of this report, the EDU flow estimates have been used. However, it is anticipated that actual flows for each sub-area will be less than the EDU method flow estimates and thus it is recommended that the flow estimates presented in this report are re-evaluated following completion of the flow meter replacement project and prior to final design of a wastewater system.


#### **Peak Flow Considerations**

Several peak flows should also be considered when discussing the design flows of wastewater treatment systems including the anticipated peak hourly flow and the anticipated peak daily flow. Figure 3.1 provides the 10 States Standards (10 SS) peak hour peaking factor computational methodology. Assuming the entire wastewater service areas serve 90% of the Village population (a population of approximately 900, see Section 1.3.1), the peak hour peaking factor is 3.8. Applying the total estimated average daily flow of 149,000 gpd produces a peak hourly flow of up to 566,000 gpd if all sub-areas were serviced. Note that as the service area increases, the peaking factor is predicted to decrease. This calculation does not account for inflow and infiltration (I&I), which would not be expected for a newly constructed sewer system, regardless.



**FIGURE 3.1**Ten States Standards Peak Hour Factor Calculation

Figure 3.2 below provides the American Society of Civil Engineers (ASCE) Manual of Practice No. 9 Sewer Design and Construction (MOP 9) daily peaking factor curves. The estimated average daily flow of 149,000 gpd produces a maximum day peaking factor of approximately 2.8, which results in a peak daily flow of 417,000 gpd if all sub-areas were serviced.



**FIGURE 3.2** MOP 9 Daily Peaking Factor Calculation

A summary of the anticipated design flows if all sub-areas were serviced is provided in Table 3.12. It should be noted that the daily peaking factor calculation is intended for conventional treatment systems that may be subject to I&I. A newly installed system will be subject to minimal I&I and therefore would have a much lower peak day flow.

<b>TABLE 3.12</b> – Anticipated Design Flows for E	ntire System
Average Daily Flow (gpd)	149,000
Peak Daily Flow (gpd)	417,000
Peak Hourly Flow (gpd)	566,000

#### 3.4.2 Future Flows and Loads\*

The design wastewater constituents should be based upon the service area at its full potential. Additional residential and commercial development and high demand businesses such as restaurants in the service area may increase the daily average flows. Additionally, and although this would be a new system, typical practice also accounts for inflow and infiltration as well as prohibited flows into the wastewater system.

For this application, future flows will be considered the other parcels within the water district but outside of the delineated sub-areas as defined in Section 3.1 and shown in Figure A.6. There are 209 parcels outside of the sub-areas, which are mostly residential, consisting of 133 single family, multi-family, or apartment units, 23 commercial units, and 53 vacant parcels. Refer to Appendix E for the EDUs for each parcel; total EDUs for the parcels outside of the sub-areas is 234. The estimated average daily flow for the expanded service using the EDU method is 234 EDUs x 215 gpd/EDU = 51,000 gpd. Applying the

same peaking factors discussed in Section 3.4.1 to the expanded service area results in an additional peak hour flow of 194,000 gpd and an additional peak daily flow of 143,000 gpd. The anticipated flows for the expanded service area are summarized in Table 3.13.

<b>TABLE 3.13</b>	<ul> <li>Expanded</li> </ul>	Service Area	<b>Anticinated</b>	Flows
IMPLE 3.13	- Labanacu	Selvice Alea	Allucibateu	1 10 10 5

Expanada del vide / li da / lindiel	, acca : 10115
Average Daily Flow (gpd)	51,000
Peak Daily Flow (gpd)	143,000
Peak Hourly Flow (gpd)	194,000

#### 3.4.3 Discharge Limits

The discharge limits of a new wastewater treatment system will depend on the type of disposal system selected. Generally, subsurface disposal systems do not have as many discharge limitations as a more conventional municipal wastewater treatment plant (WWTP) discharging to a surface water. In New York State, a WWTP discharging to a surface water body or to the subsurface at flows over 1,000 gpd is subject to a NYSDEC State Pollutant Discharge Elimination Permit (SPDES). A new WWTP discharging to a non-intermittent stream such as Webatuck Creek at a flow of 50,000 gpd, for example, would generally be expected to meet the following discharge limits summarized in Table 3.14.

**TABLE 3.14** – Anticipated Discharge Limits for Surface Disposal

Wastewater Component	Effluent
рН	6.5 – 8.5 s.u.
Ultimate Oxygen Demand (UOD):	
June 1 – October 31	16 mg/L
November 1 – May 31	27 mg/L
Dissolved Oxygen	7.0 mg/L
Total Suspended Solids (TSS):	
Summer	10.0 mg/L
Winter	15.0 mg/L
Settleable Solids	0.3 ml/L
Total Ammonia Nitrogen (TAN):	
June 1 – October 31	1.24 mg/L
November 1 – May 31	1.81 mg/L
Total Residual Chlorine	0.03 ug/L
Coliforms:	
30 Day Consecutive Geometric Mean	200 mg/L
7 Day Consecutive Geometric Mean	400 mg/L

Conversation with NYSDEC Region 3 indicated that there has typically been no SPDES monitoring limits established for subsurface wastewater disposal regarding many of the constituents typically measured for surface disposal. However, groundwater monitoring will be required by the NYSDEC for discharges to the subsurface for flows greater than 30,000 gpd with an applicable Nitrite limit (as N) of 10 mg/L. Additionally, similar projects have been subject to a Nitrate limit after treatment and prior to disposal of 20 mg/L.

The surface disposal limits presented in Table 3.14 and the subsurface disposal limits for Nitrite and Nitrate presented above have been assumed for the alternative analysis presented herein. Final conversations with the NYSDEC would be required to establish effluent limits during design of a wastewater treatment system based on the selected

treatment and disposal method and verified design flows for the selected service area. As well, these limits may be changed based on the full technical and water quality review of the SPDES application by NYSDEC.\*



## Section 4 Alternatives Considered\*


## 4.1 Individual Onsite Wastewater Systems

In portions of the study area, primarily undeveloped areas or large parcels, continued use of individual homeowner septic systems may be appropriate and cost-effective. For example, the areas around Gay Road had no reported wastewater problems and the lot sizes are generally larger. The limited amount of problems in these areas coupled with sufficient sub-surface conditions can support continued use of properly maintained individual septic systems.

The cost to replace a conventional homeowner septic system in its entirety, (septic tank, distribution box, and leachfield) can vary significantly, typically ranging from \$5,000 to \$20,000, but can be greater depending on family size and site conditions.

The septic system problems identified in the study area can, in many cases, be attributed to small property lots, although small areas of poor soils and shallow groundwater or bedrock may also cause these problems. Where these difficult site conditions exist, continued use of conventional septic systems (septic tanks, distribution boxes, and leachfields) is not expected to provide effective, trouble-free wastewater treatment and would likely require that residents modify use of the property to accommodate their septic systems.

However, upgrades to the individual septic systems may be effective in addressing the isolated problems currently experienced in some of these areas. For example, where septic system failures are the result of high groundwater alone, construction of a "mounded" leachfield, set at a sufficient elevation above the high groundwater level, may mitigate the septic system problems experienced. Again, this is a provided example, since no homeowner reported any leachfield failures resulting from high groundwater.



Typical Residential Wastewater Treatment System

It is important to note that although siting wastewater disposal fields in areas of very high groundwater (< 2' from the ground surface) is not appropriate, due to the likelihood of the groundwater to surcharge the disposal system causing its failure, individual wastewater disposal fields are not a significant cause of elevated groundwater. In comparison with the effects of precipitation, infiltration, and runoff, wastewater contributes minimally to groundwater elevation.

Alternative technologies for sub-surface wastewater disposal are often considered to upgrade failing septic systems in areas that cannot accommodate conventional systems. Alternative treatment systems provide additions or modifications to one or more of the components of a conventional system, while providing at least an equivalent degree of environmental and public protection. These technologies are generally better at removing solids and other pollutants from wastewater before discharging to the soil absorption system (leachfield), which typically increases the life of the soil absorption system and may make it possible to overcome difficult site conditions.

Most of the alternative onsite treatment systems such as an aerobic treatment system, require mechanical equipment (blowers and/or pumps) to operate effectively and, as a result, require more frequent maintenance than a conventional septic system. Typically, a licensed operator will need to perform annual or biannual maintenance.

The construction cost of a typical alternative individual household septic system is approximately \$30,000-\$40,000. However, this cost can vary significantly, depending on family size and site conditions, similar to a conventional septic system. The annual operation and maintenance cost of this biological treatment system, including sampling, testing, reporting, electricity, and facility maintenance, is estimated at approximately \$1,000 per year.

On parcels with small lot sizes and reported wastewater problems, upgrades to septic systems are not expected to be effective in correcting current wastewater disposal problems due to the lack of area for an individual treatment system. Because upgrades to individual septic systems alone are not expected to be sufficient for the entire Village, other wastewater system improvements have been considered in the following Sections.

## 4.2 Wastewater Collection Systems

A wastewater system consists of three components; the collection system, the treatment system, and the disposal system. Each component of a wastewater system has several different methods and technologies available. The relevant collection system methods for the Village of Millerton are discussed below and the treatment and disposal options are discussed in the Sections to follow.

## 4.2.1 Conventional Gravity and Pumped Collection Systems

A conventional collection system consists of PVC piping installed by an open trench method. This involves removing pavement or sod on the ground surface, excavating to depths of 5-12 feet (typically, but can be deeper) installing crushed stone bedding, installing rigid PVC pipe, and backfilling and repairing the disturbed surface. Gravity piping must be installed carefully to maintain a constant downward slope. Access for inspection and cleaning is by pre-cast concrete manholes spaced approximately every 250 feet. Generally, the smallest gravity main is no less than 8-inches with a minimum slope of 0.4%.


Gravity systems are appropriate when there is sufficient grade to ensure required pipe slopes. However, since maintaining slope is vital to these systems, open trench construction is necessary. Open trench construction in shallow cross-country routes with sufficient space and only requiring loaming and seeding for repair can be very cost effective. Open trench construction through well trafficked paved areas can have expensive restoration costs.

Where site conditions and topography do not allow for conveyance to the treatment site, gravity piping will discharge to a pump station. Conventional pump stations typically consist of a pre-cast concrete wet well with two submersible wastewater pumps. Pump stations discharge to a smaller diameter forcemain. The minimum sanitary forcemain diameter is typically 4-inches and the pumps must maintain a flow velocity of 2 fps. Sanitary forcemains must have clean out structures every 400 – 500 feet and may require air release structures at high points.

Rather than pumping stations, grinder pumps may be used to convey untreated wastewater directly from a buildings sewer into the collection system. This option requires a grinder pump at each household but is often a good option if site conditions and topography don't allow for gravity lines.

### 4.2.2 Alternative Collection Systems

A significant difference between conventional and alternative collection systems is the use of septic tanks. Septic tanks are typically plastic or concrete tanks which detain raw wastewater discharge from a building service. The tank is baffled which allows solids to settle to the bottom of the tank, and floatable material to form a scum layer at the top of the tank. Waste in the tank are decomposed by aerobic digestion. Wastewater leaving the tank (septic tank effluent) is of improved quality as solids remain within the septic tank. Septic tanks must be pumped regularly (typically every 3 – 7 years) or solids will build up in the tank and discharge in the effluent. A typical septic tank schematic is shown in Figure 4.2.



**FIGURE 4.2** Typical Septic Tank

While conventional wastewater collection systems convey raw wastewater, alternative collection systems typically convey septic tank effluent. Septic tank effluent alternatives include both gravity and pressure collection systems, including:

#### **Septic Tank Effluent Gravity Systems**

Septic tank effluent gravity systems (STEG) use small diameter gravity collector lines to convey septic tank effluent to a treatment location. These gravity lines have a minimum diameter of 4-inches and no minimum slope but typically have a minimum velocity of 0.5 fps. Gravity lines have the advantage of not requiring any power to operate and will continue to provide appropriate wastewater service even in cases of electricity outages.

#### **Septic Tank Effluent Pumps**

Low pressure sewers consist of smaller diameter forcemains through which sewer flow is pumped. Septic tank effluent pumps (STEP) force wastewater through the main regardless of pipe slope. Low pressure sewers can be installed by conventional open trench methods, but smaller diameter piping can also be installed by directional drilling. Directional drilling utilizes exit and entry pits, and access for service connections, but does not disturb the ground surface over the entire pipe length, significantly reducing restoration costs. The minimum diameter for low pressure sewer piping is 2-inches and there are no minimum slope requirements. Individual effluent service lateral lines may be as small as 1.25" in diameter. Similar to conventional sanitary sewer forcemains, low pressure sewers must have regular clean out structures every 500 to 1,000 feet and will require air release valves at high points. Effluent pumps will be sized for parcel flow, typically 50 gpm minimum for residential homes, and two pumps will be provided at each septic tank for redundancy. Septic tanks and effluent pumps will be located on each parcel, except where space is limited multiple parcels may discharge to a single septic tank.

A schematic of STEG and STEP systems is shown in Figure 4.3.



**FIGURE 4.3**Typical STEG and STEP System Schematic

## 4.3 Wastewater Treatment Systems

#### **4.3.1 Conventional Treatment Systems**

Many larger communities have "conventional" wastewater treatment systems which generally consist of the following components:

- Primary treatment for the removal of solids;
- Secondary treatment which typically consists of biological treatment for the removal of additional contaminates;
- Tertiary treatment for further removal of contaminants by biological, chemical, or physical means;
- Disinfection by chemical treatment or by UV light, and;
- Return to a surface water body.

Since most wastewater treatment systems were built for large municipalities, extensive centralized systems were justifiable due to the significant flows requiring treatment and the site constraints faced by densely developed communities. However, a conventional system may not be the best match for a smaller, rural community such as Millerton.

There is strong interest in many smaller communities about alternative technologies for wastewater treatment; however, considering the significant cost burden it takes a small community to implement any wastewater treatment system, there is a tendency to utilize the 'tried and true' approach of a conventional system. Unfortunately, a conventional system has energy, economic, and environmental impacts that place additional cost burdens on small communities.

One of the most significant disadvantages of a conventional wastewater treatment system for small communities is solids handling. Conventional wastewater treatment systems typically consist of screening for large solids removal, comminutors, large above ground settling basins to remove the remaining solids, pumps to remove the collected solids, digesters to further break down sludge or mechanical dewatering devices and then loading facilities for trucking to conventional landfills. These components are generally expensive to build and operate especially at a small scale. From a technical standpoint, sludge removal, collection, and disposal are one of the most significant challenges to any wastewater treatment system. When considering the economic scale of small community systems, successfully addressing sludge management is vital.

For proper operation, conventional wastewater treatment facilities require a full time licensed operator and generally at least one other trained staff member. Due to the size of the Village, associated costs, and staffing requirements of a conventional wastewater treatment system, an alternative treatment system is recommended for the Village of Millerton in leu of a conventional wastewater treatment system.

#### 4.3.2 Water Resource Recovery Systems

Water Resource Recover Systems are alternative treatment systems that typically include:

- Use of individual septic tanks for solids removal and primary treatment;
- Use of several treatment locations for one community;
- Packaged modular secondary/tertiary biological treatment units located at a regional location near denser development/neighborhoods, and;
- Subsurface disposal systems.



**FIGURE 4.4**Alternative Treatment System in Dix Hills, NY

#### 4.3.3 Treatment System Comparison

There are several differences between the conventional treatment systems and water resource recovery (WRR) treatment systems. The significant differences include:

- Sludge Management
- Piping Costs
- Operation & Maintenance

As discussed in Section 4.3.1, one of the most challenging aspects of a conventional wastewater treatment system is solids handling. However, with many WRRS treatment systems, solids removal occurs at each parcel or a combination of a few parcels. This allows typical residential septic tank pumpers and haulers to handle solids removal and disposal. Typically, the community is responsible for all maintenance of septic tanks, ensuring that efficient solids removal is occurring.

By removing solids before the wastewater is conveyed to a treatment location, a wastewater collection system can be sized at a smaller diameter, lowering installation costs. For instance, gravity lines can be reduced to 4-inches where an 8-inch diameter is normally required, and pressure lines can be reduced to 2-inches where 4-inches would normally be required.

However, septic tank effluent systems that utilize pumping may be difficult to manage during power outages. Frequently, a home with no municipal wastewater services has no municipal water service either. Thus, if a power outage occurs, the well is without power, as well as the wastewater system pump. If a home has a generator, it typically will be sized to accommodate the well pump, as well as the wastewater pump, also avoiding a conflict. However, if a home that has municipal water service, which typically remains unaffected by power outage, also has septic wastewater pumps as part of an alternative collection system, there may be a continued source of wastewater, with no means of wastewater pumping during a power outage.

If a sustained power outage lasted for several days, the municipality would need to pump each septic tank into the collection system. For a conventional collection system, this would require simply providing emergency power at a central pump station, rather than requiring service at many individual systems. Both conventional and alternative systems that utilize gravity collection avoid these problems. All treatment systems, conventional and alternative, require emergency power at the main treatment location.

In general, conventional wastewater treatment facilities are treating higher flows, and have more complex treatment systems due to on-site sludge management. For proper operation, conventional wastewater treatment facilities require a full-time licensed operator and generally at least one other trained staff member. WRR systems typically treat smaller flows and have simpler treatment systems; thus, staffing is usually part time.

Due to the size of the potential service district, the anticipated daily flows, the status of septic systems in the Village, and relative costs, further consideration of WRR systems is appropriate for the Village. Additional information regarding alternative treatment technologies have been presented in the following Section.

#### 4.3.4 Water Resource Recovery Technologies

A water resource recovery system accomplishes treatment in two locations; primary treatment occurs in the on-site septic tanks, and secondary treatment which occurs at a site where the flow has been collected.

Treatment efficiency for small systems is generally characterized by their efficiency at removal of organic constituents and solids. The most commonly used parameter to define the organic strength of municipal wastewater is biochemical oxygen demand (BOD). BOD is the quantity of dissolved oxygen utilized by microorganisms in the aerobic oxidation of the organic matter in wastewater over a period of time. The depletion of dissolved oxygen in wastewater is directly related to the amount of organic matter present in the wastewater.

The quantity of solids in wastewater is typically expressed as total suspended solids (TSS). Suspended solids are those removable by filtration or settling. Wastewater may also have quantities of dissolved solids, which require additional treatment for removal.

Another parameter used to gauge the strength of wastewater is nitrogen. Common forms of nitrogen are ammonia, nitrite, and nitrate. Large quantities of nitrogen in wastewater returned to a water body can cause growth of algae. Ammonia is considered a serious water pollutant as it is toxic to fish. Nitrate can easily pass through the soil to the groundwater, where it can accumulate to high levels over time, potentially contaminating drinking water sources.

Typically, a permit for subsurface wastewater discharge for flows above 1,000 gpd will have limitations set for nitrogen. Typical individual disposal system absorption fields remove little or no nitrogen from the septic tank effluent. Primary treatment by a traditional septic tank is effective at removing quantities of BOD and TSS and some nitrogen species. Table 4.1 below provides typical septic tank influent and effluent concentrations.

**TABLE 4.1** – Typical Septic Tank Influent & Effluent Concentrations

Davamentov	Influent	Effluent	
Parameter	Concentration	Concentration	
BOD	350 mg/l	150 mg/L	
TSS	400 mg/l	60 mg/L	
TKN	300 mg/l	60 mg/L	
NH <sub>3</sub> -N	70 mg/l	50 mg/L	
FOG	150 mg/l	20 mg/L	

There are many suitable water resource recovery technologies available for wastewater treatment. However, there are minimum criteria that each system must meet, including:

- Ability to meet regulatory effluent limits, and;
- NYSDEC Region 3 familiarity with the system and past approval.

WRR system technologies that have not been previously approved by the NYSDEC for a community application will have a much longer review period and have a significant chance of delaying project schedule. Therefore, for the purpose of this evaluation, technologies that have not been previously installed for a community application were eliminated from further consideration.

Table 4.2 summarizes the treatment systems that were considered for Millerton but were not analyzed.

**TABLE 4.2** – Treatment Systems Not Analyzed

Treatment System	Reason(s) Not Considered	
Conventional Activated Sludge WWTP	<ul><li>Complexity</li><li>Inappropriate size</li><li>Construction costs</li><li>Staffing requirements</li><li>O&amp;M requirements</li></ul>	
Packaged Steel WWTP	<ul><li>Complexity</li><li>Longevity concerns</li><li>O&amp;M requirements</li></ul>	

Cluster Treatment Systems

Few locations available for clusters

Alternative Individual
Onsite Treatment Systems

- O&M requirements and costs
- Does not address concerns with reserve area

Two of the most appropriate WRR technologies for the Village of Millerton investigated as part of this report include:

- Membrane Bioreactor Treatment System Ovivo microBLOX
- Biofiltration Treatment Systems Orenco AdvanTex

#### **Membrane Bioreactor System - Ovivo microBLOX**


Membrane bioreactors (MBR) combine biological oxidation of the activated sludge process with membrane separation. MBR systems treat wastewater through aerobic digestion and membrane filtration. This allows both to occur in a single unit operation and eliminates the need for large settling tanks required in a conventional treatment system. Air is introduced into the tank housing the membranes which provides oxygen for the biological process, mixes the tank, and scours the membranes to reduce fouling.

The Ovivo microBLOX MBR is a packaged system designed to be simple to operate and with options ranging from initial solids removal through disinfection. The packaged system includes a small waste activated sludge holding tank (WAS), however, this can be increased to store additional sludge or a separate sludge holding tank is often constructed to reduce the frequency of sludge removal. The MBR system would require construction of a building to properly winterize the MBR units and other components. Effluent pH control and dissolved oxygen systems would also be required to meet the anticipated effluent parameter limits for surface discharge. In addition, an equalization tank can be added to the system to equalize the influent flows and loadings. A standard Ovivo microBLOX packaged unit is shown in Figure 4.5.



**FIGURE 4.5**Ovivo MicroBLOX System

Ovivo has single unit systems capable of treating average flows of up to 150,000 gpd and multi-unit systems capable of treating flows of up to 500,000 gpd. Figure 4.6 shows the simplified process flow diagram for a single Ovivo microBLOX system and Table 4.3 shows the typical reported effluent quality achieved with Ovivo's microBLOX systems:



**FIGURE 4.6**Ovivo MicroBLOX Simplified Process Flow Diagram

**TABLE 4.3** – Ovivo MicroBLOX Typical Effluent Concentrations

Parameter	Effluent	
BOD <sub>5</sub>	<2 mg/L	
Total Nitrogen (TN)	<3 mg/L	
Ammonia (NH₃)	<0.3 mg/L	
Total Phosphorus (TP)	< 0.03 mg/L	
Fecal Coliform	< 2.2 CFU/100 mL	
Total Suspended Solids (TSS)	< 2 mg/L	

For an average day flow of 75,000 gpd, a dual-tank system with one tank for the MBR and one tank dedicated to flow equalization and WAS storage would be required to treat the flows and meet the effluent requirements. Approximately 4,500 square feet of building space to house the units would be required. Additional membranes and the addition of a supplemental oxygen system could be added to the system to achieve a greater treatment capacity should the wastewater service area be expanded. Supplemental information about the Ovivo microBLOX units can be found in Appendix F.

The Ovivo microBLOX packaged systems have been installed in over 200 applications across the country including over 40 units in Massachusetts. A similar system was approved and installed within NYSDEC Region 3 at the Storm King School in Cornwall.


#### **Biofiltration Systems - Orenco AdvanTex**

The Orenco AdvanTex Wastewater Treatment System is a packed bed biofiltration system that uses lightweight synthetic textile to treat septic tank effluent. The textile media has a high porosity and large surface area for microbial attachment and high loading rates. The septic tank effluent is sprayed onto the textile media and percolates down where it is filtered and treated by microorganisms that populate the textile. There are several AdvanTex models available, which range in size and flow capacity. An image of the AdvanTex AX-Max treatment units prior to backfill is shown in Figure 4.7.



FIGURE 4.7
Orenco's AdvanTex Units (AX-Max Models Shown)

Primary tankage is supplied to receive the influent flow and provides two functions including equalization and acting as pre-anoxic tanks. Pumps are installed in the primary tankage which distribute the flow to the biofiltration treatment units. The wastewater percolates down through the media where it is filtered, cleaned, and nitrified by the naturally occurring microorganisms that populate the media. Aeration is provided at each of the treatment units and after passing through the media, the treated effluent flows out of the units to a final effluent tank for a subsurface disposal system. The treated effluent typically enters a second stage for polishing for surface disposal systems. In either scenario, the flow from the effluent tank is dispersed by gravity or is pumped to the disposal location. A calibrated portion of the treated wastewater is also sent back to the pre-anoxic tanks to pass through the system again. A post anoxic tank is typically incorporated into surface disposal systems for denitrification between the first and second stages. Figure 4.8 represents a simplified system layout for the Orenco AdvanTex System for a subsurface disposal system.



Typical Orenco AdvanTex System Layout for Subsurface Disposal

Table 4.4 shows the typical reported effluent quality achieved with the Orenco AdvanTex System:

**TABLE 4.4** – Orenco Treatment System Typical Effluent Concentrations

Parameter	Effluent
BOD₅	< 15 mg/L
Total Nitrogen (TN)	< 20 mg/L
Ammonia (NH <sub>3</sub> )	N/A
Total Phosphorus (TP)	N/A
Fecal Coliform	N/A
Total Suspended Solids (TSS)	< 20 mg/L

An Orenco treatment system sized for 75,000 gpd with a subsurface disposal system would consist of approximately one influent equalization/pre-anoxic tank, ten treatment tanks, one effluent tank, and the associated pumps, equipment, and controls.

An Orenco treatment system sized for 75,000 gpd with a surface disposal system would consist of approximately one influent equalization tank/pre-anoxic tank, ten stage 1 treatment tanks, one post anoxic tank, one effluent tank, five stage 2 treatment tanks, and the associated pumps, equipment, and controls. These systems are NSF/ANSI Schedule 40 approved for residential wastewater treatment systems. More information on the Orenco AdvanTex systems can be found in Appendix F.

The Orenco AdvanTex Systems are installed in over 75 residential applications and in several municipal locations in New York including the communities of:

- Hyde Park 120 Service Connections 30,000 gpd Surface Return
- Hillsdale 73 Service Connections 35,000 gpd, Subsurface Return

- East Schodack 23 Service Connections 7,500 gpd Surface Return
- Schodack Landing 75 Service Connections 20,000 gpd Surface Return
- Bethlehem 23 Service Connections 7,500 gpd Surface Return

## 4.4 Water Resource Recovery Return

Two alternatives exist for water resource recovery return of the treated effluent;

- Return to a surface water body, or;
- Return to groundwater.

#### 4.4.1 Return to Surface Water

The method of a conventional community wastewater treatment facility that can also be utilized by alternative water resource recovery systems is to return to a surface water body, which was historically accomplished by piping the treated wastewater effluent to a concrete headwall, where it flows by gravity into the surface water. For the Village of Millerton, the surface water body for water resource return is Webatuck Creek.

Return to surface water requires disinfection, which can be accomplished two ways; by chemical means, or by UV light. Chemical disinfection requires multiple sets of pumps for chlorination and dechlorination chemicals, on-site storage of these chemicals which can be hazardous to employees and the environment, delivery of monthly chemical supplies through local streets, frequent water testing to ensure effectiveness of disinfection, and subsequent removal of disinfection chemicals.

UV disinfection is accomplished by exposing the treated wastewater to very high doses of ultraviolet light. It does not require the use of chemicals but is a system higher in capital costs and has significant energy usage impacts. UV disinfection also requires frequent water quality testing. Both disinfection methods would require the construction of a building to house the processes, an additional capital cost.

#### 4.4.2 Return to Groundwater

There are several different options for water resource return to groundwater. The most widely used conventional groundwater systems include absorption fields (leachfields) which can be configured as trenches or beds. Other methods include drip dispersal systems or gravelless geotextile sand filters, which may also be applicable for the Village of Millerton. All three options are discussed in the following sub-sections.

#### **Absorption Fields**

Water resource return to groundwater is typically accomplished using absorption fields, especially for smaller systems. However, absorption fields can also be used for larger systems if the space is available. There are generally two types of absorption fields; absorption trenches and absorption beds. The trench is the most common and preferred of the two options and consists of a trench or series of trenches in which a perforated PVC pipe is placed in a bed of gravel or synthetic aggregate. Sewage is delivered to the PVC pipes by gravity, pressure, or by dosing and seeps slowly out of the perforated PVC pipe, into the aggregate, and finally into the soil. A typical trench absorption field utilizing perforated PVC pipe and gravel aggregate is shown in Figure 4.9.



**FIGURE 4.9** Typical Trench Absorption Field Under Construction

In lieu of perforated PVC pipes, infiltration chambers can also be used in trenches. Infiltration chambers are similar to conventional trench absorption fields except that the perforated PVC pipes are replaced with high-density polyethylene arches that interlock to form a continuous drainage area with a much greater storage volume than a PVC pipe-ingravel system. The infiltration chambers have an open bottom which allows the sewage to seep into the ground. With the infiltration chambers, sewage has more time to percolate slowly and effectively, ensuring greater strength, performance, and longevity. Using infiltration chambers in lieu of perforated PVC pipes may allow for a smaller drainage field size compared to pipe-in-gravel trenches. Infiltration chambers can also be installed without an aggregate if soil conditions allow. However, aggregates are typically used regardless for best practice, particularly for higher flow systems. Infiltration chambers can be gravity fed or pressurized.

Absorption beds (also referred to as seepage beds) are similar to trenches in that they also utilize perforated PVC pipes or infiltration chambers and an aggregate. The difference between absorption trenches and absorption beds is that for beds there is no native soil that separates the rows of PVC pipes or infiltration chambers; rather, the pipes or chambers are all placed in a common bed of aggregate. Trenches are preferred over beds because beds have very little sidewall area and lower oxygen transfer. Beds are also better suited for pressure systems and for flat sites in order to minimize the potential groundwater mounding and/or down gradient seepage. A bed absorption field utilizing infiltration chambers and gravel aggregate is shown in Figure 4.10.



**FIGURE 4.10**Seepage Bed with Infiltration Chambers Under Construction

When absorption fields are used for treatment (such as with conventional septic tanks and leachfields), it is anticipated that microorganisms in the soil assist in removal of any remaining organic matter, solids, and nutrients. When absorption fields are used after secondary treatment, they are primarily intended for return of the treated effluent into the ground. In this case, a 33% increase in application rate is allowed when a "Responsible Management Entity" owns the treatment system such as a municipality (Appendix 75-A.6(6)(ii)(d)). Therefore, it has been assumed for the remainder of this report that the Village of Millerton would qualify as a responsible management entity and that a 33% increase in application rate would be appropriate, provided that secondary treatment is supplied.

In general, the subsurface return of treated effluent avoids the significant costs and maintenance concerns associated with disinfection. Subsurface return is considered by regulators as having lower environmental impacts, as it allows recharge of the water table rather than return to a surface water body where it is immediately removed from the watershed. The absorption fields also have no visual impact on the surrounding community. Additionally, subsurface return allows for much less licensed operator involvement and water quality testing. However, subsurface return requires significant area for the disposal field, which may not be available within every community.

#### **Drip Dispersal Systems**

Subsurface drip dispersal technologies apply recovered water to the root zone using perforated small diameter piping or porous diffusers, typically placed 6 to 12 inches below the soil surface (minimum of 18 inches in cold climates such as New York). This technology has been successfully used in the northeast for several years and has been accepted as a reliable method of wastewater disposal. Drip dispersal systems are often used in areas where marginal or shallow soils are found. Figure 4.11 shows a typical drip dispersal system under construction.



**FIGURE 4.11**Drip Dispersal System Before Backfill


Drip dispersal subsurface systems consist of a pre-treatment unit, a pump tank, filtration system, subsurface drip tubing, and a controller. Primary settling or septic tank treatment is the minimum level of pre-treatment necessary for a drip dispersal system. Additional pre-treatment to remove specific pollutants, such as FOG, which may adversely impact the soil or receiving environment or foul the drip dispersal system may be necessary.

For drip dispersal systems, the pump tank stores effluent until the controller turns on the pump to dose pre-treated wastewater through a filtering system into the soil. The filtration system removes solids from the effluent and flushes them back to the pretreatment device. Drip tubing is placed directly into the soil without the use of trenches. The system relies on specially designed emitters to apply effluent uniformly.

Drip tubing is typically placed approximately 2' apart in the landscape so emitters are on a grid pattern within the existing landscape. Drip lines are buried relatively shallow so the soil can provide treatment, landscape plants can use the nutrients and water, and the system can maximize evaporation. A typical drip dispersal layout is shown in Figure 4.12.

A benefit of the drip dispersal systems is that they require minimum backfill compared to traditional leachfields thus cutting down on excavation costs for installation. Drip dispersal systems also have controls which allow for monitoring of the system performance. The drip dispersal system allows the water to very slowly disperse into the ground over a larger area and does not require gravel placement.

One of the disadvantages of a drip dispersal system compared to a standard absorption field is that they are more maintenance heavy. The drip dispersal system needs to be monitored, cleaned, and filters changed on a regular basis for efficient operation. There is also greater risk associated with a drip dispersal system if the dispersal tubing becomes fouled due to a failed filter, or lack of maintenance.



**FIGURE 4.12**Typical Drip Dispersal System

Similar to conventional absorption fields, drip dispersal requires a significant area for the disposal field. The design of drip dispersal fields must meet the same design standards as a conventional absorption field. Therefore, there is no distinct advantage of a drip dispersal system in terms of reduced field area compared to a conventional absorption field. The advantage for using a drip dispersal field comes when a particular site has marginal soils, a shallow depth to a restrictive layer, or high groundwater. If a site does not have one of these conditions, then a conventional absorption field is preferred.

#### **Gravelless Geotextile Sand Filters**

The use of gravelless absorption systems is becoming more common as the technology is easier to install compared to more traditional absorption fields and also provides distinct advantages at certain sites. There are several types of gravelless absorption systems including open-bottom gravelless chambers/galleys, gravelless media-wrapped corrugated pipe sand-lined systems, and gravelless geotextile sand filters.

Gravelless geotextile sand filters (GGSF) are similar to conventional absorption trench systems but consist of a geotextile wrapped "unit" surrounded by system sand instead of a single pipe surrounded by gravel aggregate. There are several manufacturers of GGSF products which vary slightly from one manufacturer to the next, but each generally consists of a perforated pipe surrounded by or placed on top of a synthetic aggregate or media which is then contained around the diameter of the pipe or covered by a geotextile fabric. The unit(s) are placed in a 4 foot wide trench and are surrounded by 6 inches of system sand below and on the sides of the unit(s).

In accordance with NYSDEC design standards, a trench bottom sizing criteria of 6 square feet per linear foot of trench may be used for the design of GGSF systems provided that the GGSF product has an overall unit width of 3 feet, a storage capacity of 12 gallons per linear foot, and six inches of system sand is installed below and on the sides of the unit(s). The GGSF systems must have a minimum of 4 foot edge-to-edge trench separation. An example of a gravelless geotextile sand filter trench system (manufactured by Infiltrator) is shown in Figure 4.13.



**FIGURE 4.13**Gravelless Geotextile Sand Filter Trench System (by Infiltrator)

## 4.5 Potential Treatment System Locations

Determining the correct siting for a wastewater treatment system is challenging. However, the use of alternative treatment technologies, with their low visual, audio, and odor impact, allow for a much greater number of sites to be considered.

#### 4.5.1 Initial Parcel Screening

For the purpose of this evaluation, only parcels owned by the Village of Millerton were considered for potential wastewater treatment system sites. The potential wastewater treatment system sites which are owned by the Village are shown in Figure A.8. As shown in Figure A.8, there are 11 parcels owned by the Village. Six of the parcels were eliminated based on initial review as indicated below in Table 4.5.

**TABLE 4.5** – Potential Locations and Initial Parcel Screenings

Parcel	Location	Status
1	North of Millerton Recreation Park	Eliminated, slopes greater than 15%
2	Millerton Recreation Park	Eliminated, recreation park
3	Off Highland Street	Eliminated, village water tower
4	Dutchess Ave & Simmons St	Eliminated, village offices/police
5	Main St & Dutchess Ave	Eliminated, village park on Main St
6	Near Irondale Cemetery	Eliminated, wetlands
7	Town Highway Garage	Potential Site
8 - 11	Mill Street Site	Potential Site

After initial screening, there are two remaining sites which are potentially suitable for an alternative wastewater treatment system. They are referred to as the Town Garage Site and the Mill Street Site for the remainder of this report. Figure 4.14 shows the two site options with an overlay of the flood zones and wetlands and Figure 4.15 shows the topography at each of the sites. Each of the two sites are described in further detail below:

#### **Town Garage Site**

The Town Garage Site is 1.1 acres and is at the corner of South Center Street and Mill Street. The Village has indicated that the town garage will be relocating, and the property will be turned over to the Village of Millerton. The lot is bordered to the west by Webatuck Creek and is mostly within the 100-year flood zone as shown in Figure 4.14 except for the northernmost part of the parcel. The lot is cleared and contains one large building that is currently used by the Town Highway Department. There are residential properties bordering the north, east, and west sides of the property. The site is mostly level but slopes down slightly from north to south. The Webatuck Creek runs along the western property border. The property is in the high density residential and land conservation zoning districts.

#### **Mill Street Site**


The Mill Street Site is a cluster of four parcels owned by the Village of Millerton on the south side of Mill Street. The total size of the Mill Street Site is 8.9 acres. Current access to the property is at the corner of South Center Street and Mill Street. Village staff have indicated that there is also a right-of-way to the property off South Maple Avenue that is overgrown and no longer used. The location of the right-of-way is shown approximately on Figures 4.14 and 4.15.

The Webatuck Creek runs along the north side of the site. The north half of the lot is wooded and rises up steeply to the south from Webatuck Creek. The south half of the lot is mostly cleared, overgrown pasture which slopes down to the northwest towards Webatuck Creek. The lots are primarily medium density residential zoning districts, however portions of the lots along Webatuck Creek are in the land conservation zone.


Overall, the Mill Street site is relatively isolated from nearby residential houses; the closest of which is off Maple Avenue. As with the Town Garage Site, the north portion of the Mill Street Site is within the 100-year flood zone as shown on Figure 4.14.

One benefit of the Mill Street site is that there is a large vacant parcel immediately to the south. This parcel is 27.7 acres and has access from Sharon Road. Approximately 5 acres of this parcel is already cleared. This lot also generally slopes down to the northwest towards Webatuck Creek.

Given the potential need for treatment capacity, the Village initiated preliminary conversations regarding parcel acquisition with the owner of the vacant parcel. It was determined by all parties that a suitable path may exist for future Village ownership of the vacant parcel, and therefore the alternative analysis may base its assumptions on the Village acquiring the vacant parcel, or portions thereof.



**FIGURE 4.14**Potential Wastewater Treatment Sites – Flood Zones



**FIGURE 4.15**Potential Wastewater Treatment Sites – Topography

#### 4.5.2 Additional Parcel Considerations

The New York State Department of Environmental Conservation outlines considerations in selecting sites for wastewater treatment systems in order to minimize potential adverse impacts. These criteria provided the basis for the secondary screenings as discussed in the following sub-sections.

#### **Separation Distances**

Table 4.6 provides the recommended separation distances that should be maintained between treatment facilities and dwellings or property lines to provide some attenuation of airborne nuisances such as aerosols, pathogens, odors, and noise as provided by the NYSDEC Design Standards for Intermediate Sized Wastewater Treatment Systems, 2014.

**TABLE 4.6** – Recommended Separation Distances

Treatment Type	Radial Distance to Existing Downwind Dwellings	Distance to Property Line from Treatment Unit
Wastewater Treatment Process Open to the Atmosphere e.g. Open Sand Filter, and Oxidation Ditches	400 feet	350 feet
Wastewater Treatment Processes Enclosed in a Building, and Buried or Covered Sand Filters	200 feet	150 feet
Facultative and Aerated Lagoons	1,000 feet	800 feet
Effluent Recharge Bed	750 feet	550 feet

Using Table 4.6 as a guideline, a minimum distance between the nearest dwelling unit and the water resource recovery system of 200 feet is desirable. Additionally, the treatment system should be a minimum of 150 feet from the property line. Maintaining either of these distances at the Town Garage Site is not feasible. However, maintaining both recommended separation distances at the Mill Street Site is attainable.

#### **Zoning and Other Land Use Restrictions**

The Town Garage Site is approximately 60% within the land conservation zoning district and 40% within the high density residential zoning district. Development is discouraged in the land conservation zone per the Comprehensive Plan. However, public utility installations are permitted in these areas according to the Village of Millerton zoning code.

The Mill Street Site is mostly within the medium density residential zoning district besides portions of the lot along Webatuck Creek which are in the land conservation zoning district. However, this section of the lot is steep and would not be utilized for a wastewater treatment system and is therefore not expected to be a restriction. The vacant parcel to be obtained by the Village is zoned as low density residential.

#### Topography

Areas with unsuitable topography were eliminated in the initial screening. Of the remaining sites, the Town Garage Site has nearly flat slopes and topography is therefore not expected to be an issue. The Mill Street Site is relatively steep along Webatuck Creek but the cleared area of the site (approximately 5 acres) has a slope of 5-10%. This slope is within the acceptable range per NYSDEC design standards for certain subsurface disposal systems.

#### **Area for Future Expansion**

A larger parcel is preferable to allow for expansion, should the entire Village be added to the sewer system and to control and maximize the buffer areas between adjacent property owners. Unfortunately, none of the lots surrounding the Town Garage Site would be available for future expansion.

#### **Direction of Prevailing Wind**


Prevailing winds in the Village are from the west. However, prevailing wind direction is a more significant consideration for larger traditional wastewater treatment plants with open tanks and sludge and septage processing. It is assumed that odors will be minimal for either of the proposed alternative treatment technologies and will be adequately addressed by the separation buffer criteria discussed previously in this Section.

#### Flood Considerations and Accessibility

Wastewater treatment systems and disposal areas should be located above the 100-year flood plain. Additionally, the NYSDEC *Design Standards for Wastewater Treatment Works*, requires that all treatment and disposal systems be located to minimize or eliminate flood damage. This is of greatest concern for the Town Garage Site since nearly all of the site is within the 100-year floodplain (see Figure 4.14). In order to protect the area of the site from flooding, the area would need to be filled to elevate the treatment system or built with all structures above the 100-year floodplain level. Access to the site during a flood would also need to be provided.

In accordance with 6 NYCRR Part 502 – Floodplain Management Criteria For State Projects, paragraph (15); in riverine situations, no project (including fill) shall be undertaken unless it is demonstrated that the cumulative effect of the proposed project, when combined with all other existing and anticipated development, will not increase the existing water surface elevation of the base flood more than one foot at any point. Provided, the provisions of this paragraph shall not apply to any project being undertaken on a site where there is less than one square mile of drainage area for the watercourse involved above such site, and where the administrator has not provided final flood base elevations on a city, town or village's flood insurance rate map (FIRM). The flood base elevation across the Town Garage Site is 681 feet as shown on the Village's FIRM (attached in Appendix G).

The Flood Insurance Study for Dutchess County indicates that "The area between the floodway and the 1% annual chance floodplain boundaries (100-year flood) is termed the floodway fringe. The floodway fringe encompasses the portion of the floodplain that could be completely obstructed without increasing the water surface elevation of the 1% annual chance flood by more than 1.0 foot at any point." This is accompanied by the following Figure 4.16.




**FIGURE 4.16** Floodway Fringe and Floodway Guidance

Thus, to utilize the available portion of the Town Garage site, the site could be filled to an acceptable level such that the treatment system would be above the 100-year flood elevation, while not causing a significant increase in flood elevation. A modeling study would need to be completed to demonstrate that the improvements to the site would not adversely affect the surrounding properties or raise the base flood level by more than 1 foot. A subsurface disposal system is not recommended for this site due to its position relative to the flood plain and the limited space.

While the higher elevation area on the Mill Street Site is well above the 100-year floodplain, the access to the site at the corner of South Center Street and Mill Street would be cut off during a 100-year flood event. Therefore, the right-of-way from South Maple Lane would need to be used as a secondary access route during a flood event. However, due to the flood elevations, a right-of-way line adjustment would likely be necessary in order to keep the right-of-way out of the 100-year flood zone. The approximate location of the right-of-way and anticipated lot line adjustments are shown in Figure 4.17.

However, if the vacant parcel was acquired, permanent access to the Mill Street site from Sharon Road could be provided which would have no flood restrictions and void the need for the right-of-way and lot line adjustments.



**FIGURE 4.17**Approximate Right-of-Way Location at the Mill Street Site

#### **Geologic Considerations**

The geology of the area is shown on Figures A.2. The soil type at the Town Garage Site is Copake gravelly silt loam, which is a well-drained, HSG Type A soil. Depth to a restrictive layer is reportedly more than 80 inches. The soil type at the Mill Street Site is mostly Stockbridge silt loam, which is a moderately well-drained, HSG Type C soil. Depth to a restrictive layer is reportedly more than 80 inches. Shallow bedrock is not expected to be an issue at ether location.

The Village is in seismic design category C.

#### **Protection of Groundwater**

As a regulatory minimum, groundwater return systems are required to be located 100 feet from groundwater wells. This is not expected to be a problem for the Mill Street Site and is not relevant to the Town Garage Site because a return to groundwater system would not be feasible at that location.

The separation to seasonal high ground water is an additional important requirement in siting subsurface return to groundwater systems. A minimum vertical separation distance of 4 feet is required. Areas with suspected high groundwater levels are shown in Figure A.2. As shown, high groundwater is not expected to affect either site and no basement problems were reported near either of the sites.

Millerton Wastewater Preliminary Engineering Report

#### **Adjacent Systems**

All occupied parcels in the Village contain groundwater disposal systems or holding tanks. In addition, there are subsurface drainage returns in various areas of the Village. Consideration should be given in siting any new subsurface disposal systems so that adjacent systems are not impacted.

#### **Conveyance Distance**

The cost of installing a collection system from the site to the treatment area is directly related to the length of sewer lines required. Sites which require longer conveyance distances are less favorable then potential sites closer to the center of the service area as long as those sites are not in conflict with the items discussed above. The Mill Street Site would require approximately 1,500 more feet of force main compared to the Town Garage Site.

#### 4.5.3 Return to Groundwater System Potential

Soils suitable for groundwater return systems must be sufficiently permeable to allow effluent to be returned to groundwater. The commonly used empirical measure is the percolation test that measures the rate of water drop in minutes per inch in a small percolation test hole.

For return to groundwater systems, soils must have a percolation rate of less than 120 minutes/inch and preferably less than 60 minutes per inch; especially for larger systems. DEC standards tabulate the allowable application for subsurface return in gallons per day per square foot for a range of percolation rates. The required system size and cost therefore is proportional to the percolation rate. Soils with a percolation rate of over 60 minutes per inch need to be 6 times larger than systems with a soil percolation rate of 1 minute per inch. Very coarse sands and gravels may have percolation rates of less than 1 minute per inch. In this case, DEC standards require additional treatment (beyond septic tanks) because the effluent moves too rapidly through the soil to be treated.

On-site investigations at the Mill Street Site were completed on October 26<sup>th</sup>, 2018. The detailed results of the on-site investigation can be found in Appendix H. A total of six deep tests and three percolation tests were completed in the cleared area at the Mill Street Site (see map included in Appendix H). In general, the soils were found to be silty loam to a depth of approximately 90 inches. The percolation rates ranged from 6 minutes to 11 minutes with an average percolation rate of approximately 8 minutes per inch. No percolation tests have been completed at the vacant parcel.

Based upon the percolation rate and NYSDEC Design Standards, an application rate of 0.9 gallons/day/square foot is appropriate for the Mill Street Site (8-10 mpi). However, as discussed in Section 4.4.2, NYSDOH may allow a 33% increase in application rate for treatment systems that are owned by a responsible management entity provided that secondary treatment is supplied prior to recovered water return to groundwater. Therefore, an application rate of 1.2 gallons/day/square foot has been used to estimate the return potential for the Mill Street Site.

The following list provides the assumptions/constraints that were made regarding the preliminary calculation of the maximum potential water return capacity at the Mill Street Site:

- 1. The vacant parcel will be obtained and can be utilized for groundwater return
- 2. The vacant parcel has similar percolation rates as the Mill Street Site (8 mpi)
- 3. Secondary treatment will be provided prior to disposal
- 4. The Village is considered a responsible management entity
- 5. The allowable application rate will be 1.2 gpd/square foot (includes 33% increase)
- 6. Approximately 6 acres of the site is suitable for absorption fields (excluding the area for the treatment system and accounting for approximate setback requirements)
- 7. Trench dimensions are in accordance with NYSDEC design standards

Table 4.7 provides the approximate maximum wastewater disposal capacity of the Mill Street Site with the assumptions stated above and with a conventional trench absorption system, with a drip dispersal system, and with a GGSF absorption system.

**TABLE 4.7** – Estimated Return to Groundwater Capacity at the Mill Street Site

Disposal System	Available Trench Length (ft)	Trench Sizing Criteria (ft²/ft)	Available Absorption Area (ft²)	Application Rate (gpd/ft²)	Potential Disposal Capacity (gpd)
Conventional Trench	33,500	2.0	67,000	1.2	80,000
Drip Dispersal	-	-	67,000	1.2	80,000
GGSF	25,300	6.0	151,800	1.2	182,000

As shown in Table 4.7, the total potential capacity of the Mill Street Site varies based on the type of system used. The GGSF system provides a significant advantage over the conventional trench system regarding disposal capacity at the site. Using the GGSF, the approximate maximum potential disposal capacity at the Mill Street Site is 182,000 gpd (including the vacant parcel). However, if the vacant parcel was not obtained by the Village, the total potential disposal capacity of the site using the GGSF system would only be about 60,000 gpd. It should be noted that this calculation assumes that the 33% increase in application rate would be granted by the NYS Department of Health and that the vacant parcel has the same percolation rates as the Mill Street Site.

If the increased application rate was not allowed by the NYS Department of Health, the total potential disposal capacity of the Mill Street Site and vacant parcel would be reduced to 137,000 gpd and 45,000 gpd if the vacant parcel was not acquired (0.9 gpd/square foot application rate) using a GGSF disposal system. Therefore, it is critical that the Village acquire the vacant parcel, or portions thereof in order to consider subsurface disposal. Additional percolation tests should be conducted at the vacant parcel prior to the Village acquiring the property.

#### 4.5.4 Return to Surface Water Locations\*

In general, recovered water return to surface water is the less desirable option as the SPDES permit discharge levels are much more significant compared to a subsurface disposal system. In addition, return to surface water does not have the benefits of local aquifer recharge as recovered water immediately leaves the watershed.

If a surface return system was used at either of the two sites, both would utilize the Webatuck Creek. Based upon the NYSDEC classification of Webatuck Creek, it is anticipated that recovered water parameters would be held to the levels discussed in Section 3.4.3. A submerged discharge within the Webatuck Creek is preferred to a free discharge due to the visual and environmental impacts of a free discharge. Actual type and components of the surface return will be determined during final design.\*

An acceptable return for a treatment system at the Town Garage Site would likely be towards the south side of the site near the confluence of Kelsey Brook and upstream of the Mill Street Bridge (Location No. 1). The return would be across from a neighboring property which is likely to be seen negatively by the residents. Although there is one residential property adjacent to the return location, the stream then continues approximately 1,500 feet before passing the next residence.

Surface water return at the Mill Street Site would also returned to Webatuck Creek. The treatment system water return at the Mill Street Site would need to be piped down the hill and return in Webatuck Creek downstream of the Mill Street Bridge (Location No. 2). This return location is not directly adjacent to any residents and the closest downstream resident is approximately 1,100 feet. Therefore, the Mill Street Site is the preferred site for surface disposal due to its isolation from nearby residences as compared to the Town Garage Site. Figure 4.18 shows the potential surface return locations.



FIGURE 4.18\*
Potential Surface Return Locations



# Section 5 Alternative Analysis

## 5.1 Proposed District & Alternative Development

Preliminary findings based on the wastewater needs analysis, estimated flows, and disposal options were discussed with the Village of Millerton and the Town of North East in 2020 and 2021 following the first revisions of this Preliminary Engineering Report. The Village of Millerton and Town of North East solicited feedback from residents and business owners in the study area in 2021 and 2022 regarding the proposed sewer district. This Report and this Section have been updated based on the recent feedback provided by the Village and the Town.

Based on the community feedback, it was determined that the proposed service area should incorporate parts of each sub-area with the primary focus on serving the Village General Business District, commercial areas along Route 22, and the Town of North East Boulevard District along Route 44. The anticipated sewer district is shown in Figure A.9.

Table 5.1 summarizes the average day design flow for the anticipated sewer district shown in Figure A.9. The anticipated flow contribution from each municipality is shown in Table 5.1. The base flow for the Village and the Town is based on the EDU methodology with one EDU equivalent to 215 gpd as discussed in Section 3.4.1. A Village future flow contribution of 25% of the base flow and a Town future flow contribution of 75% of the base flow has been added to the average day design flow to account for potential future flow contributions in each municipality. The future flow contributions are approximate based on the vacant land and potential build-out/expansion in each area.

**TABLE 5.1** – Millerton Anticipated Sewer District Design Flow Summary

Contribution	No. of Res EDUs	No. of Com. EDUs	Total No. of EDUs	Total Flow (GPD)
Village Base Flow <sup>1</sup>	86	128	214	46,100
Village Future Flow <sup>2</sup>	-	-	-	11,500
Town Base Flow <sup>1</sup>	1	32	33	7,100
Town Future Flow <sup>3</sup>	-	-	-	5,300
	Average Day Design Flow			70,000

<sup>&</sup>lt;sup>1</sup>Based on 1 EDU equivalent to 215 gpd

A summary of the developed alternatives for wastewater collection, treatment, and disposal are discussed in the following Sections. The alternatives and costs comparisons presented in this report are based on the anticipated sewer district shown in Figure A.9 and the estimated average day design flow of 70,000 gpd as shown in Table 5.1. Expansion of the sewer district and/or future increases in average day flows greater than those presented above will increase the size and cost of the collection and treatment system.

<sup>&</sup>lt;sup>2</sup>Future flow for Village calculated as 25% of the Village base flow

<sup>&</sup>lt;sup>3</sup>Future flow for Town calculated as 75% of the Town base flow

#### **5.1.1 Individual Onsite Wastewater Treatment Systems**


The use of individual, alternative, onsite wastewater treatment systems was dismissed since upgrades to individual septic systems alone were not expected to be sufficient for the parcels in the anticipated sewer district. Alternative onsite, decentralized wastewater treatment systems also require mechanical equipment that have high up-front costs as well as associated operation and maintenance costs. Additionally, most of the proposed district has small lot sizes which have limited area for onsite alternative treatment systems. Therefore, alternative onsite wastewater treatment system improvements were not considered for the proposed sewer district. Use of conventional septic systems and leachfields for those parcels not included in the district will are appropriate and will continue.

#### 5.1.2 Wastewater Collection Systems\*

Two types of collection systems were discussed in Section 4.2 including conventional gravity/pumped systems and alternative septic tank effluent systems. An alternative collection system where sludge is addressed at individual septic tanks is recommended for the proposed service area. An alternative collection system will not only reduce the construction costs compared to a conventional collection system but, will also reduce the O&M costs associated with the water resource recovery system since solids handling is addressed by individual septic tanks.

As previously discussed, there are two acceptable collection system methodologies for septic tank effluent systems; gravity and pumped (STEG and STEP). Gravity systems require appropriate topography. A low spot between South Center Street and Route 22 would prohibit gravity flow for approximately eleven parcels along Railroad Plaza back to the intersection of Main Street and South Center Street (refer to Figure 5.1). However, a gravity line for the parcels along Railroad Plaza could be routed along the rail trail and back out onto South Center Street to meet the required slopes. Alternatively, the eleven parcels could use a STEP system to pump the flow along Main Street up to the intersection with South Center Street.

A high spot running north/south across Main Street would require excavation in excess of 20 feet to allow for a continuous slope from North Maple Avenue along Main Street towards South Center Street. To avoid the extensive excavations, sewer mains would be routed along South Maple Avenue across Fish Street to the intersection of South Center Street. However, this requires a bridge crossing on Fish Street.



Village of Millerton Topography Impacting Gravity Flow

Most of the wastewater from the service area could flow by gravity, however, certain lots will require a STEP system based on local topography, the details of which have not been thoroughly reviewed during this evaluation. Areas where effluent pumps are anticipated are shown in Figure 5.1 (note that these areas are outside of the proposed district). However, more areas requiring STEP systems would likely be identified during a detailed collection system evaluation and design.

If a STEG system is used, a central pump station located near the intersection of South Center Street and Fish Street (the Garage Site) will be required to pump the wastewater up to the Mill Street Site. A central pump station adds maintenance, nuisances, and significant costs. In addition, STEG systems require manholes at junction points which also add construction costs and additional maintenance. For these reasons, a comprehensive STEP type collection system is the recommended collection system approach for the Village of Millerton.

Figure A.10 provides a preliminary collection system layout for the proposed service area. The northern section of the collection system begins at the Millerton Recreation Park from which the service lateral crosses Rte. 22/N Elm Ave and ties into the STEP sewer on the northeast side of the road. The STEP sewer then proceeds southerly along Rte. 22 to parcel #5924 where an easement will cross the Webatuck Creek, Railroad Plaza, and Harlem Valley Rail Trail to connect to John St., then east on Century Blvd. to parcel #97 Main St.

where the sewer crosses Rte. 44 and combines with the eastern section of the collection system. The eastern section begins at the NY/CT border and conveys flows along the south side of Rte. 44 to parcel #108 Rte. 44 where it combines with the northern section of the collection system. Flow from parcels on the north side of Rte. 44 is collected in two separate pipe segments that cross Rte. 44 to combine with the sewer on the south side of the road. The combined northern and eastern sections of sewer then parallel Main St. through easements and crosses Central Ave. and Park Ave. to reach S Center St., which the sewer then runs south along to Mill St. where the sewer continues cross-country to the proposed Mill Street Site for treatment.\*

Septic tanks will be located on each parcel connected to the system, except for the Main St./S Center St. area where due to the building density multiple parcels flow will be combined in a few septic tanks where space is available. As much as possible, existing septic tanks in good condition and of appropriate size will be reused. On parcels that require new septic tanks, those tanks will be located as close as feasible to existing tank locations to reduce new piping needed to connect to buildings. Each septic tank will include a redundant effluent pump system on the parcel. No additional pump stations will be required in the collection system to convey flow to the treatment site.\*

#### **5.1.3 Wastewater Treatment Systems**

Of the treatment systems reviewed in Section 4.3, a conventional wastewater treatment system was not recommended due to the size of the Village and the associated costs and staffing requirements of a conventional WWTP. Therefore, two water resource recovery treatment technologies were discussed; a membrane bioreactor treatment system (Ovivo microBLOX), and a biofiltration treatment system (Orenco's AdvanTex). The Orenco treatment system varies slightly based on the return type and therefore it is discussed relevant to both surface and groundwater resource recovery.

Both water resource recovery systems meet the minimum treatment system criteria:

- Ability to reach effluent limits, and;
- NYSDEC Region 3 familiarity with the system and past approval for community systems.

To evaluate the systems, the following items have been considered:

- Ease of Operation
- Operation and Maintenance Considerations
- Footprint

#### **Ease of Operation**

Each of the systems require a different degree of operation. Generally speaking, the Ovivo MBR system is more complicated than the Orenco AdvanTex system. Both systems use a similar biological process for treatment and use similar components including pumps, media filters, and blowers. However, the Ovivo system has more pumps and controllers in comparison to the Orenco System. Both systems have automated controls which can be viewed remotely to check on the status of the systems. Additional tankage, pumps, and equipment will be required for the Orenco treatment system for surface return compared to the same system for groundwater return.

The Ovivo System is primarily a single treatment tank, versus multiple units in the Orenco System. However, by having multiple treatment tanks, the Orenco system could easily have one unit out of service, while still treating wastewater flow. Since the Ovivo MBR system has only one unit, there is no ability to maintain flow, although there should be sufficient storage in preceding tankage to hold flow while short-term maintenance activities occur, given a certain time period.

Each system has similar maintenance requirements regarding textile/membrane replacement, and periodic textile filter cleaning or replacement. Maintenance of the Orenco system will be less labor intensive for cleaning and/or replacement of the textile media in comparison with the Ovivo system which requires a building crane to remove and install the membranes. The Ovivo membranes require regular backwashing which is an automated process. The Ovivo MBR system will also generate significantly more sludge than the Orenco AdvanTex system which will result in more frequent sludge removal.

#### **Operation & Maintenance Considerations**

Although both systems use similar technologies, the degree of anticipated operation and maintenance activities for each system is different. The Orenco system for groundwater return can, for the most part, be left alone, however, it is anticipated that approximately 3 hours per week will be required for checking and monitoring the system compared to 10 hours per week for the Ovivo system and 7 hours a week for the Orenco system with surface return. Sludge generation for the Ovivo system is significantly more and is estimated that sludge will need to be hauled off site twice a month. The Orenco tanks will only need to be emptied every couple of years or as needed based on regular monitoring of the sludge levels.

#### **Footprint**

It is anticipated that the AdvanTex treatment units and primary tankage for groundwater and surface water return would take up approximately 10,000 square feet and 14,000 square feet, respectively. The Ovivo tanks are approximately 9'W x 45'L X 12'H and would require approximately a 4,500 square foot building to house the units. A comparison of the two treatment systems is tabulated in Table 5.2.

Fase of Operation  AdvanTex Packed Bed Biofiltration Multiple Treatment Units No building required  Operation & Maintenance  AdvanTex  Less sludge build-up Less frequent media maintenance Remote control available  AdvanTex  AdvanTex  AdvanTex  Single Treatment Unit Building required  Considerations  Ovivo  Greater sludge removal More difficult media maintenance Remote control available  Footprint  AdvanTex  AdvanTex  Ovivo  Smaller Footprint (4.5k sq ft) Shallow installation  Requires concrete slab and building		<b>TABLE 5.2</b> – Treatment System Comparison				
<ul> <li>Packed Bed Biofiltration</li> <li>Multiple Treatment Units</li> <li>No building required</li> <li>Deration &amp; Maintenance Considerations</li> <li>AdvanTex</li> <li>Less sludge build-up</li> <li>Less frequent media maintenance</li> <li>Remote control available</li> <li>AdvanTex</li> <li>More difficult media maintenance</li> <li>Remote control available</li> <li>Footprint</li> <li>AdvanTex</li> <li>Larger footprint (10k -14k sq ft)</li> <li>Smaller Footprint (4.5k sq ft)</li> </ul>						
- Multiple Treatment Units - No building required  Operation & Maintenance Considerations  AdvanTex - Less sludge build-up - Less frequent media maintenance - Remote control available  Footprint  AdvanTex  AdvanTex  - Larger footprint (10k -14k sq ft)  - Single Treatment Unit  Building required  Ovivo  Greater sludge removal - More difficult media maintenance - Remote control available  Footprint  Ovivo  Smaller Footprint (4.5k sq ft)		<u>AdvanTex</u>		<u>Ovivo</u>		
- No building required  Operation & Maintenance Considerations  AdvanTex - Less sludge build-up - Less frequent media maintenance - Remote control available  Footprint  AdvanTex  AdvanTex - Larger footprint (10k -14k sq ft)  - Building required  Ovivo  Greater sludge removal - More difficult media maintenance - Remote control available  Footprint  Ovivo  Smaller Footprint (4.5k sq ft)	-	Packed Bed Biofiltration	-	Membrane Bioreactor		
Operation & Maintenance Considerations  AdvanTex  Less sludge build-up  Less frequent media maintenance Remote control available  Footprint  AdvanTex  AdvanTex  Larger footprint (10k -14k sq ft)  Smaller Footprint (4.5k sq ft)	-	Multiple Treatment Units	-	Single Treatment Unit		
AdvanTex  - Less sludge build-up - Less frequent media maintenance - Remote control available  Footprint  AdvanTex  - Larger footprint (10k -14k sq ft)  - Smaller Footprint (4.5k sq ft)	-	No building required	-	Building required		
<ul> <li>Less sludge build-up</li> <li>Less frequent media maintenance</li> <li>Remote control available</li> <li>Footprint</li> <li>AdvanTex</li> <li>Larger footprint (10k -14k sq ft)</li> <li>Greater sludge removal</li> <li>More difficult media maintenance</li> <li>Remote control available</li> <li>Ovivo</li> <li>Smaller Footprint (4.5k sq ft)</li> </ul>	Operation & Maintenance Considerations					
<ul> <li>Less frequent media maintenance</li> <li>Remote control available</li> <li>Footprint</li> <li>AdvanTex</li> <li>Larger footprint (10k -14k sq ft)</li> <li>More difficult media maintenance</li> <li>Remote control available</li> <li>Ovivo</li> <li>Smaller Footprint (4.5k sq ft)</li> </ul>		<u>AdvanTex</u>		<u>Ovivo</u>		
- Remote control available Footprint  AdvanTex - Larger footprint (10k -14k sq ft) - Smaller Footprint (4.5k sq ft)	-	Less sludge build-up	-	Greater sludge removal		
Footprint  AdvanTex  - Larger footprint (10k -14k sq ft)  - Smaller Footprint (4.5k sq ft)	-	Less frequent media maintenance	-	More difficult media maintenance		
AdvanTex  - Larger footprint (10k -14k sq ft)  - Smaller Footprint (4.5k sq ft)	-	Remote control available	-	Remote control available		
- Larger footprint (10k -14k sq ft) - Smaller Footprint (4.5k sq ft)	Footprint					
		<u>AdvanTex</u>		<u>Ovivo</u>		
	_	Larger footprint (10k -14k sq ft)	_	Smaller Footprint (4.5k sq ft)		
		,	-			

From a review of both technologies, it appears that either is well suited to address the Village's needs. As discussed in Section 4.3.4, multiple communities in New York State have successfully utilized the Orenco AdvanTex technology including continued effluent quality exceeding the NYSDEC SPDES permit limits. MBR systems have also been used successfully for small communities, and Ovivo has over 200 microBLOX MBR systems in operation across the country, many of which are in New England and New York. Since both technologies appear to be applicable for meeting the needs of the Village, both treatment technologies will be considered in the alternative analysis.

#### **5.1.4 Recovered Water Return Systems**

Two alternatives exist for return of recovered water; return to a surface water body, or return to the groundwater. As mentioned in Section 4.4, surface return will have more stringent SPDES permit limits than groundwater return, thus requiring a larger, more costly recovery system, higher operation and maintenance skill and expense, and the potential for negative public perception. However, the total footprint will be much smaller, allowing for a much larger treatment flow rate per square foot.

Surface return is the only disposal option for the Town Garage Site. The Mill Street site can return of up to 182,000 gpd to the subsurface with a GGSF system if the adjacent vacant parcel is acquired which would be more than large enough to support the estimated flows for the proposed sewer district.

Table 5.3 compares both disposal methods.

**TABLE 5.3** – Recovered Water Return Comparison

TABLE 5.5 - Recovered	water Return Companson			
Surface Return	Subsurface Return			
Water Quality				
<ul> <li>Stream Water Quality</li> <li>Dissolved oxygen level essential for maintaining fish populations impacted by BOD, nitrogen and phosphorus</li> </ul>	<ul> <li>Groundwater Quality</li> <li>Nitrates untreated by soil and accumulate in groundwater, potentially lowering aquifer water quality</li> </ul>			
<ul> <li>Potential route for public exposure to treated effluent</li> </ul>	- No direct public exposure route			
Public P	erception			
<ul> <li>Negative public perception in regard to public impacts and environmental health concerns</li> </ul>	<ul> <li>Less controversial method, no observable return location, generally more positive public perception regarding public health impacts</li> </ul>			
Foot	tprint			
- Small return area	- Large return area			
Permitting				
- Higher level of treatment required	- Lower level of treatment required			
Expandability				
- Greater potential for expansion	- Lower potential for expansion			
Operation & Maintenance				
<ul> <li>Minimal amount of operation and maintenance for return piping</li> <li>Will require regular sampling</li> </ul>	<ul> <li>Greater operation and maintenance depending on subsurface technology used</li> <li>Periodic groundwater monitoring</li> </ul>			

As shown in Table 5.3, each return method has advantages and disadvantages. Fortunately, both options are feasible for the Village of Millerton and therefore both methods of recovered water return are considered in the alternative analysis.

#### **5.1.5 Water Resource Recovery System Sites**

As discussed in Section 4.5, the Mill Street site is the only site available at this time that is suitable for groundwater return. The Town Garage site has inadequate area available for groundwater return and is also within the 100-year flood zone. There would be enough room for consideration of an MBR system at the Garage Site with surface return. However, due to its proximity to residential neighbors and its location within the 100-year flood zone, this treatment site has not been considered. Therefore, the Mill Street site is the recommended site for construction of a water resource recovery and/or return system.

#### 5.1.6 Definition of Alternatives

Based upon the results of the evaluation and the recommendations discussed above, four alternatives have been considered regarding implementation of a water resource recovery collection, treatment, and return system for the Village of Millerton. The alternatives include:

- Alternative No. 1 No-Action
- Alternative No. 2 STEP Collection System with Biofiltration Resource Recovery System and Groundwater Return at the Mill Street Site
- Alternative No. 3 STEP Collection System with Membrane Bioreactor Resource Recovery System and Surface Return to Webatuck Creek at the Mill Street Site
- Alternative No. 4 STEP Collection System with Biofiltration Resource Recovery System and Surface Return to Webatuck Creek at the Mill Street Site

#### 5.2 Alternative No. 1: No-Action

The no-action alternative means that no centralized wastewater collection, treatment, or return system would be implemented in the Village of Millerton. In this scenario, the existing individual wastewater treatment systems and storage tanks would remain in use. This option does not address the isolated wastewater return issues and leaves the responsibility of fixing these issues on the homeowners. Faulty septic systems and leachfields may remain in place due to homeowners lack of maintenance or financial inability to repair their own system. Faulty septic systems may also adversely affect the quality of local water ways and nearby residential water supplies.

Additionally, the no-action alternative does not address locations where local conditions such as high bedrock, high groundwater, poor soils, parcel density, or inadequate space limit the effectiveness of traditional septic systems. Another disadvantage of the no-action alternative is that certain high demand facilities such as restaurants may be unable to expand due to limited wastewater capacity. The no-action alternative does not address the desire of the 40% of wastewater survey respondents who felt that a centralized wastewater treatment system is required for the Village.

An advantage of the no-action alternative is that there is no large construction cost; all septic tank pumping costs, maintenance costs, and repair costs will remain the responsibility of the property owners. This will prevent a potential tax burden for those Village residents who would not be serviced by the wastewater treatment system yet may still see an increase in their contribution for funding of the construction and maintenance.

Another advantage of the no-action alternative is that there will be no direct surface water return and no disruption of traffic which is likely to occur during construction of a new sewage collection system.

## 5.3 Alternative No. 2: Biofiltration with Absorption Field

Alternative No. 2 consists of the following:

- Construction of a STEP collection system for the proposed service area;
- 2. Installation of the Orenco AdvanTex biofiltration system for secondary treatment of the septic tank effluent at the Mill Street Site sized to treat an average daily flow of 75,000 gpd for the proposed service area, and;
- 3. Construction of a subsurface return system at the Mill Street Site sized for an average daily flow of 75,000 gpd for the service area.

A preliminary layout of the water resource recovery system and absorption fields for Alternative No. 2 is shown in Figure 5.2. Note that Figure 5.2 assumes that the vacant parcel would be acquired by the Village and used for the recovery and return system.



**FIGURE 5.2** Preliminary Layout of Alternative No. 2

If a biofiltration resource recovery system with subsurface return at the Mill Street Site was pursued, then the system components will consist of:

- Influent Flow Meter
- Pre-Anoxic/EQ Tanks
- Orenco AdvanTex AX-Max Biofiltration Treatment Modules
- Treated Wastewater Effluent Tank
- Effluent Flow Meter
- Control Building
- GGSF Absorption Fields
- Groundwater Monitoring Wells

Site work for Alternative No. 2 would include construction of an access road from Sharon Road, brush hogging and clearing, excavation and grading for the absorption fields, excavation for the buried piping, tanks, and treatment units, and security fencing around the treatment units. After the absorption fields are installed the area would be seeded and mulched and would be mowed at least a few times a year for maintenance. There would be minimal visual impact once construction is complete for the nearby residences as almost all equipment would be below grade.

#### 5.4 Alternative No. 3: MBR with Surface Return

Alternative No. 3 consists of the following:

- 1. Construction of a STEP collection system for the proposed service area;
- 2. Installation of the Ovivo microBLOX MBR system for secondary treatment of septic tank effluent at the Mill Street Site sized to treat an average daily flow of 75,000 gpd for the service area;
- 3. Construction of a building for the MBR treatment system, and;
- 4. Installation of surface return piping to Webatuck Creek.

A preliminary layout of the treatment system and return location for Alternative No. 3 is shown in Figure 5.3. If an MBR system with surface return at the Mill Street Site was pursued, then the system components will consist of:

- Metal Building for the MBR System
- Influent Flow Meter (in building)
- Ovivo microBLOX Tank split for EQ and WAS Storage
- Ovivo microBLOX Treatment Unit with UV Treatment
- Ovivo microBLOX Supplementary Oxygen Unit
- Effluent Flow Meter
- Surface Return to Webatuck Creek



**FIGURE 5.3** Preliminary Layout of Alternative No. 3

Site work for Alternative No. 3 would include clearing and construction of an access road from the Corner of Mill Street and South Center Street to the treatment system building at the Mill Street Site and/or the secondary access road through the right-of-way off Sharon Road. The forcemain would be installed up the hill to the metal building that would house the MBR system. The MBR system will require excavation and grading for a concrete slab for the building. The building will be approximately 4,500 square feet and will require 18' of height for proper clearances above the MBR treatment units.

The MBR system will require a 208V, 3 phase electric service for the pumps and blowers. Minimal site clearing will be required for this alternative. The return piping would be routed back down along the primary access road to Webatuck Creek. The return would discharge downstream of the South Center Street Bridge as shown in Figure 5.3.

This alternative does not require acquisition of the vacant parcel because there is enough room for the MBR system on the parcels that the Village currently owns including the required property line setbacks. However, the Village may need to consider purchasing a portion of the vacant parcel if a right-of-way or lot-line adjustment is infeasible for the secondary access road.

### 5.5 Alternative No. 4: Biofiltration with Surface Return

Alternative No. 4 consists of the following:

- Construction of a STEP collection system for the proposed service area;
- 2. Installation of the Orenco AdvanTex biofiltration system for secondary treatment of the septic tank effluent at the Mill Street Site sized to treat an average daily flow of 75,000 gpd for the proposed service area;
- 3. Installation of UV disinfection system and effluent flow monitoring, and;
- 4. Installation of surface return piping and return to Webatuck Creek.

A preliminary layout of the water resource recovery system and return location for Alternative No. 4 is shown in Figure 5.4.




FIGURE 5.4\*
Preliminary Layout of Alternative No. 4

If a biofiltration treatment system with surface return at the Mill Street Site was pursued, then the system components will consist of:

Influent Flow Meter

- Pre-Anoxic/EQ Tanks
- Orenco AdvanTex AX-Max Stage 1 Treatment Modules
- Orenco AdvanTex AX-Max Stage 2 Treatment Modules
- Post Anoxic Tank with Carbon Addition
- Disinfection
- Effluent Flow Meter
- Control Building
- Surface return to Webatuck Creek
- Aeration within surface return piping\*

Site work for Alternative No. 4 would include clearing and construction of an access road from the Corner of Mill Street and South Center Street to the treatment system location at the Mill Street Site and/or the secondary access road through the right-of-way off Sharon Road. The forcemain would be installed up the hill to the treatment system. The Orenco treatment system will require excavation and for installation of the buried tanks. A small control building would be located adjacent to the treatment system.

Minimal site clearing will be required for this alternative. The surface return piping would be routed back down along the primary access road to Webatuck Creek. The return piping would return downstream of the South Center Street Bridge as shown in Figure 5.4. If during final design it is determined that effluent aeration is required for DO levels, the surface return piping has several drops which will be designed to address aeration, such that additional aeration systems will not be needed.

This alternative does not require acquisition of the vacant parcel because there is enough room for the treatment system on the parcels that the Village currently owns including the required property line setbacks. However, the Village may need to consider purchasing a portion of the vacant parcel if a right-of-way or lot-line adjustment is infeasible for the secondary access road.

The Orenco AdvanTex Systems are installed in over 75 residential applications and in several municipal locations with surface discharges in New York including the communities of:

- Hyde Park 120 Service Connections 60,000 gpd Surface Return
- East Schodack 23 Service Connections 7,500 gpd Surface Return
- Schodack Landing 75 Service Connections 20,000 gpd Surface Return
- Bethlehem 23 Service Connections 7,500 gpd Surface Return
- Kensington Woods 84 Service Connections 35,500 gpd Surface Return

# **5.6 Alternative Cost Comparison**

#### **5.6.1** Cost Estimate Approach\*

Conceptual construction cost estimates have been prepared for each of the three construction alternatives and include the following components:

Millerton Wastewater Preliminary Engineering Report

- 1. Construction Cost: The budgetary cost estimates are based on Class 3 level construction cost estimates, as defined by the Association for the Advancement of Cost Engineering (AACE) International Recommended Practices and Standards. According to AACE International Recommended Practices and Standards, the estimate class designators are labeled Class 1, 2, 3, 4, and 5, where a Class 5 estimate is based on the lowest level of project definition and a Class 1 estimate is closest to full project definition and maturity. The end usage for a Class 3 estimate is budget authorization, appropriation, and initial cost control. The expected accuracy range of a Class 3 estimate is between +30% and -20%. The level of project definition for a Class 3 estimate is between 10% and 40%. The costs include overhead and profit, equipment costs, demolition/removal of existing equipment, temporary provisions (if applicable), facilities and bypasses (if necessary, to complete the work), and costs regarding installation and start-up of improvements. This cost also includes a contractor general conditions cost factor of 15% of the construction subtotal. The costs are based upon recently completed project bid forms, quotes from equipment manufacturers/vendors, and data contained in R.S. Means Construction Cost Data.
- **2. Engineering (20%):** A 20% cost factor has been applied for engineering fees. The 20% for engineering fees can be broken down further as: Engineering Design (8%) and Construction Administration (12%).
- **3. Contingency (20%):** A 20% contingency has been applied to the estimated total project costscosts. For a Class 3 estimate, AACE International Recommended Practices and Standards recommends a contingency of 20%.\*
- **4. Total Project Costs:** The total project costs are the sum of the construction costs, property acquisition (if applicable), engineering, and the contingency costs.

#### 5.6.2 Alternative Cost Estimates\*

#### **Capital Costs**

The capital cost to the Village for the no-action alternative is \$0. However, as described previously, if an individual system fails, cost to replace with an engineered system is estimated to be up to \$40,000 per parcel.

Tables 5.4, 5.5 and 5.6 present the summarized construction cost estimates for Alternative No. 2, Alternative No. 3, and Alternative No. 4, respectively. These cost estimates include the cost for the collection, treatment, and disposal systems. The detailed construction cost estimates for each alternative are provided in Appendix I.

**TABLE 5.4** - Alternative No. 2 Preliminary Cost Estimate\*

Component	<b>Estimated Cost</b>
STEP Collection System	\$4,739,000
Site Work	\$36,000
Electrical Service	\$21,000
Biofiltration Resource Recovery System	\$2,719,000
GGSF Absorption Field	\$1,140,000
Construction Subtotal	\$8,655,000
Property Acquisition	\$283,000
Contingency (20%)	\$1,788,000
<b>Total Estimated Construction Cost</b>	\$10,726,000

**TABLE 5.5** - Alternative No. 3 Preliminary Cost Estimate\*

Component	<b>Estimated Cost</b>
STEP Collection System	\$4,739,000
Site Work	\$83,000
Electrical Service	\$21,000
MBR Resource Recovery System	\$3,441,000
Surface Return	\$56,000
Construction Subtotal	\$8,340,000
Property Acquisition	\$0
Contingency (20%)	\$1,668,000
<b>Total Estimated Construction Cost</b>	\$10,008,000

**TABLE 5.6** - Alternative No. 4 Preliminary Cost Estimate\*

Component	Estimated Cost
STEP Collection System	\$4,739,000
Site Work	\$83,000
Electrical Service	\$21,000
Biofiltration Resource Recovery System	\$3,773,000
Surface Return	\$56,000
Construction Subtotal	\$8,672,000
Property Acquisition	\$0
Contingency (20%)	\$1,734,000
<b>Total Estimated Construction Cost</b>	\$10,406,000

As shown in Tables 5.4, 5.5, and 5.6, Alternative No. 3 is anticipated to have the lowest capital construction cost.

#### **Operation and Maintenance Costs**

If the No Action Alternative is selected, costs for maintenance and repairs of existing septic systems will remain the cost of the individual property owners including costs for repair or replacement of failing systems. Tables 5.7, 5.8, and 5.9 present the summarized annual operation and maintenance (O&M) cost estimates for Alternative No. 2, Alternative No. 3, and Alternative No. 4, respectively. These cost estimates include the annual operation and maintenance costs for the collection, treatment, and disposal systems as well as administrative costs, short-term assets, and a 20% contingency. The detailed O&M cost estimates for each alternative are provided in Appendix I.

**TABLE 5.7** - Alternative No. 2 Annual O&M Cost Estimate

Component	<b>Estimated Cost</b>
STEP Collection System	\$46,700
Biofiltration Resource Recovery System	\$35,700
GGSF Absorption Field	\$1,900
Annual O&M Subtotal	\$84,300
Contingency (20%)	\$16,900
Administration, Billing, & Accounting	\$15,000
Total Estimated Annual O&M Cost	\$116,200

**TABLE 5.8** - Alternative No. 3 Annual O&M Cost Estimate

Component	<b>Estimated Cost</b>
STEP Collection System	\$46,700
MBR Resource Recovery System	\$106,900
Surface Return	\$1,000
Annual O&M Subtotal	\$154,600
Contingency (20%)	\$31,000
Administration, Billing, & Accounting	\$15,000
<b>Total Estimated Annual O&amp;M Cost</b>	\$201,000

**TABLE 5.9** - Alternative No. 4 Annual O&M Cost Estimate

Component	<b>Estimated Cost</b>
STEP Collection System	\$46,700
Biofiltration Resource Recovery System	\$61,400
Surface Return	\$1,000
Annual O&M Subtotal	\$109,100
Contingency (20%)	\$21,900
Administration, Billing, & Accounting	\$15,000
Total Estimated Annual O&M Cost	\$146,000

As shown in Tables 5.7, 5.8, and 5.9, Alternative No. 2 is anticipated to have the lowest annual operation and maintenance costs.

#### 5.6.3 Life Cycle Cost Analysis\*

A life cycle cost analysis was utilized to better compare the alternatives to determine the most cost-effective alternative, rather than just the alternative with the lowest capital cost. The net present value was calculated for each alternative as the capital cost (which includes construction and non-construction costs such as land acquisition and engineering) plus the present worth of the uniform series of annual O&M, minus the present worth of the salvage value of the system. This was calculated for a planning period of 20 years with a 2.3% inflation rate and a 0.3% discount rate taken from Appendix C of OMB Circular A-94. The net present value for each alternative is presented in Table 5.10.

**TABLE 5.10 -** Life Cycle Cost Analysis Summary\*

		- / /	
	Alt. No. 2	Alt. No. 3	Alt. No. 4
Capital Costs	\$10,726,000	\$10,008,000	\$10,406,000
Annual O&M Costs	\$116,200	\$201,000	\$146,000
Present Worth of O&M Costs	\$2,820,000	\$4,880,000	\$3,550,000
Present Worth of Salvage Value	\$1,150,000	\$890,000	\$1,080,000
Net Present Value	\$14,812,000	\$15,979,000	\$15,182,000
		Planning Period	20 years
		Inflation Rate	2.30%
		Discount Rate	0.30%

Although the capital costs for Alternative No. 3 and Alternative No. 4 are less, the lower O&M costs for Alternative No. 2 ultimately results in a lower life cycle cost for Alternative No. 2 as shown in Table 5.10.

# 5.7 Non-Monetary Considerations

Non-monetary factors such as environmental impacts, land requirements, constructability concerns, sustainability considerations, potential for service interruption, availability for future expansion, public perception, operation and maintenance requirements, and regulator familiarity should also be considered for each alternative. Each of these items are briefly discussed in this Section.

#### **Environmental Impacts**

As discussed, the surface return options presented in Alternative No. 3 and Alternative No. 4 have the most direct impact on the water quality of Webatuck Creek. In comparison, the groundwater system recommended for Alternative No. 2 would have no direct environmental impact on Webatuck Creek. The no-action alternative is very likely to have environmental impacts if existing systems are to remain and are not functioning properly. There are no other anticipated environmental impacts.

#### **Land Requirements**

Alternative No. 2 requires the procurement of the vacant parcel adjacent to the Town owned parcel. However, Alternative No. 3 and Alternative No. 4 do not require land procurement since both treatment systems can fit within the existing Town owned property.

Procurement of a right-of-way or a lot line adjustment will be required for Alternative No. 3 and No. 4 for the secondary access road. Easements will also be required for the collection system and access easements will be required for the Village to access each parcel's STEG/STEP tank for operation and maintenance purposes.

#### **Constructability Concerns**

Each of the alternatives has their own unique constructability challenges. Alternative No. 2 has a constructability challenge for installation of the absorption field trenches parallel to the site contours. Alternative No. 3 and No. 4 have constructability challenges

associated with the site clearing and construction of an access roadway along a relatively steep slope.

#### **Sustainability Considerations**

Sustainable utility management practices are important to consider when creating a new sewer district. Each alternative is utilizing a STEP collection system which is a closed system and thus there is much less chance for inflow and infiltration compared to a conventional collection system. Alternatives No. 2 with subsurface discharge are generally expected to be more energy efficient than Alterative No. 3 and Alternative No. 4 with the surface discharge. This is because the treatment system has less components, and thus there are less pumps, blowers, and there is no UV system which consumes a large amount of electricity. The operational simplicity of Alternative No. 2 compared to Alternative No. 3 and 4 in turn reduces the amount of operator visits, time and fuel driving back and forth, sending samples to the lab, etc. which, although minimal, helps to reduce the carbon footprint of the system.

There is minimal installation of non-porous surfaces for each alternative and thus stormwater management should be easily obtained. Green infrastructure can be incorporated where practical during the final design of the selected system.

#### **Potential for Service Interruption**

Each alternative has the potential for service interruption. However, the design of each treatment system would include an emergency back-up generator to ensure continuous operation even during a power failure event. However, power failure events for parcels with STEP systems (all alternatives) will mean temporary service interruptions for those parcels until electrical service is restored.

#### **Availability for Future Expansion**

Having area available for expansion of the sewer system is a very important consideration. Each of the alternatives has a STEP collection system which can be easily expanded.

One of the most important non-monetary considerations is the ability for the treatment system to expand for future wastewater flows. Alternative No. 2 is somewhat restricted in this manner as the subsurface is only capable of returning a fixed amount of flow based on the available area at the site (up to 182,000 gpd, see Section 4.5.3).

The MBR system and surface return alternative could be expanded in the future to meet average day flows of up to 125,000 gpd by adding a supplemental oxygen system and additional membranes. However, if flows are in excess of 125,000 gpd, an additional treatment unit will need to be added which will require an expansion of the metal building or construction of a second building to house the additional treatment units. This is an important consideration if the Village desires to expand the service area in the future.

The Orenco biofiltration system (Alternative No. 4) can also be expanded to meet future flows if needed. The Orenco system is modular and therefore additional tanks can be added to the system to allow for treatment of additional flow.

#### **Public Perception**

Nuisances such as odors and noise are commonly associated with wastewater treatment systems. While none of the proposed alternatives are expected to cause significant noise Millerton Wastewater Preliminary Engineering Report 5-18

or odor pollution, the MBR alternative is likely to be louder due to a greater number of pumps and blowers associated with the system. However, the building should significantly reduce the amount of noise emanating from the MBR system. No noise or odor concerns are expected with the AdvanTex biofiltration systems.

Public perception of the surface water return to Webatuck Creek will be seen negatively by members of the community. Residents have previously voiced concern to a surface water return. In addition, the MBR system will require a building which may be considered aesthetically unappealing for the neighbors within sight distance of the facility. This can be reduced with strategic placement and landscaping if required.

The components for Alternative No. 2 and Alternative No. 4 are primarily below grade and therefore are not expected to cause any negative public perceptions. However, Alternative No. 2 does require installation of an access road between two residences off Sharon Road and will require weekly inspection of the site by operators.

#### **Operation and Maintenance Requirements**

Each of the alternatives require a different degree of operation and maintenance. For the STEP system, maintenance primarily includes pumping out the tanks every 3-5 years (same as typical septic tanks). At a minimum, a yearly check on each of the septic tanks is also good practice to make sure there are no obvious issues. Effluent filters should be cleaned/replaced on a regular basis and STEP tank pumps will need to be replaced after approximately 20 years. It is anticipated that emergency maintenance for STEP tanks will periodically be required.

The Orenco AdvanTex treatment systems for Alternative No. 2 and Alternative No. 4 have similar operation and maintenance requirements. However, the Orenco treatment system for Alternative No. 4 will require more frequent operation and maintenance since there are additional tanks and components associated with the surface return treatment system. This means more pumps and blowers to maintain and eventually more media that will need to be replaced. Alternative No. 4 will require more frequent operational check-ins including daily compliance sampling as compared to Alternative No. 2. Generally, the MBR system (Alternative No. 3) requires a more operation and maintenance than the Orenco AdvanTex treatment system.

Besides maintenance for the effluent dosing pumps, there is practically no maintenance associated with the GGSF disposal system (Alternative No. 2). Maintenance of the surface return (Alternative No. 3 and 4) will consist of regular inspections of the surface return and periodic cleaning.

#### **Regulator Familiarity**

Regulator familiarity with the treatment system will help expedite regulatory review of the project. Treatment system technologies that have not been previously approved by the NYSDEC Region 3 for a community application will have a much longer review period and have a significant chance of delaying project schedule. The Orenco treatment systems have been installed for several community applications including a 30,000 gpd system in Hyde Park and a 35,000 gpd system in Hillsdale (Alternative No. 2 and 4). NYSDEC Region 3 is also familiar with the MBR systems (Alternative No. 3).

A summary of the non-monetary considerations for each alternative is shown in Table 5.11.

**TABLE 5.11** – Non-Monetary Considerations

		<ul> <li>Non-Monetary Con</li> </ul>		
Item	Alt No. 1	Alt. No. 2	Alt. No. 3	Alt. No. 4
Environmental Impacts	- Failing or unmaintained leachfields remain	<ul> <li>Secondary treatment provided</li> <li>Minimal groundwater impacts</li> </ul>	- Direct Return to Webatuck Creek	- Return to Webatuck Creek
Land Requirements	- None	<ul> <li>Need to acquire vacant parcel</li> </ul>	- None	- None
Constructability Concerns	- None	- GGSF system install on sloped site	- Secondary access road	- Secondary access road
Sustainability Considerations	- None	- More energy efficient	- Least energy efficient	- Less energy efficient
Potential for Service Interruption	- Potential for septic systems to fail	- Service interruption for STEP Tanks	- Service interruptio n for STEP Tanks	- Service interruptio n for STEP Tanks
Availability for Future Expansion	- Limited expansion available on small parcels	<ul> <li>Limited future expansion for disposal system</li> </ul>	- Potential for expansion	- Most easily expandable - modular system
Public Perception	- Negative	- Subsurface return, positive	- Surface return, negative	- Surface return, negative

Operation and Maintenance Requirements	O&M remains the responsibility - of property owners	Least O&M -	Most O&M -	Less O&M
Regulator Familiarity	Familiar -	Familiar -	Familiar -	Familiar
- Village Goals	Limits the amount of flow from businesses	Increases expandability of businesses	Increases expandabi lity of businesse s	Increases expandabili ty of businesses
- Existing Issues	Does not address existing WW issues	Addresses existing WW issues	Addresses existing WW issues	Addresses existing WW issues



# Section 6 Recommended Alternative

Due to the reported wastewater problems in the Village, the public's desire to install a centralized wastewater treatment system, the goals of the comprehensive plan, and the site constraints in the Village which limit the performance of traditional septic systems, the Village is encouraged to consider Alternative No. 2, Alternative No. 3, or Alternative No. 4.

# **6.1 Summary of Recommended Alternative**

Based on the results of the alternatives analysis and the non-monetary considerations discussed in Section 5, Alternative No. 2 is the apparent best alternative and was recommended in previous revisions of this report. However, although preliminary conversations with the owner of the vacant parcel suggested that a suitable path may exist for Village ownership of the vacant parcel, further conversations between the Village and the parcel owner in late 2021 concluded that the Village will not be able to acquire the vacant parcel at this time. Therefore, Alternative No. 2 is no longer feasible since there is insufficient area for a groundwater return system on the Mill Street property alone.

Since Alternative No. 2 is no longer feasible, Alternative No. 4 is the recommended alternative. The basis for selection of Alternative No. 4 is as follows:

- Alternative No. 2 is not feasible (vacant parcel cannot be acquired)
- Second lowest life cycle costs
- Reduced operation and maintenance complexity and frequency compared to MBR
- Minimal visual impacts
- Greater public perception (tanks are mostly buried)
- Ease of future expansion
- Meets Village goals
- Will allow growth of businesses within the Village

Implementation of Alternative No. 4 will consist of the following:

- 1. Construction of a STEP collection system for the proposed sewer district. The proposed sewer district primarily covers the Village General Business District, the commercial areas along Route 22, and the Town of North East Boulevard District along Route 44 (see Figure A.9 for a map of the proposed sewer district);
- 2. Installation of the Orenco AdvanTex biofiltration system for secondary treatment of the septic tank effluent wastewater at the Mill Street Site sized to treat an average daily flow of 70,000 gpd for the service area, and;
- 3. Construction of surface return piping to Webatuck Creek for the treated effluent.

# **6.2 Project Costs\***

There are several financial grant or low-interest loan programs available which may assist the Village with funding this project such as the Clean Water State Revolving Fund (CWSRF) or the USDA Rural Development program. This engineering report has been prepared in anticipation of pursuit of a low-interest loan or grant. Table 6.1 below provides the conceptual opinion of probable cost for implementation of Alternative No. 4 in a format that is consistent with USDA Rural Development requirements.

**TABLE 6.1 - Recommended Project Costs\*** 

TABLE 6:1 Recommended Project Costs	
Item	Cost <sup>1</sup>
1. Construction Costs	\$9,476,000
2. Engineering Costs	
a. Design	\$736,000
b. Construction	\$1,137,000
3. Other Expenses	
a. Local Counsel	\$71,000
b. Bond Counsel	\$118,000
c. Work Force	\$0
d. Financial Services	\$0
e. Miscellaneous	\$0
4. Equipment	\$0
5. Land Acquisition	\$0
6. Project Contingency (20%)	\$2,292,000
7. Total Project Costs	\$13,830,000
8. Less Other Sources of Financing	
a. Dutchess County MIG	-\$200,000
b. CPF Grant	-\$959,752
c. IMG Grant	-\$5,082,099
9. Project Costs to be Financed	\$7,588,149

<sup>&</sup>lt;sup>1</sup>Costs presented are in 2025 dollars

# 6.3 Annual Operating Budget

#### 6.3.1 Income

There is no existing income for sewer services since there is no existing municipal sewer system. Sewer use fees for the proposed system will fund construction and annual O&M costs. Refer to Section 6.3.3 for debt repayments.

#### 6.3.2 Annual O&M Costs

As discussed in Section 5.6.2, the estimated annual O&M cost for the proposed system is \$146,000 (see Table 5.9). The annual O&M cost estimate includes the annual operation and maintenance costs for the collection, treatment, and disposal systems as well as administrative costs, short-term assets, and a 20% contingency. The detailed O&M cost estimate for Alternative No. 4 can be found in Appendix I.

#### 6.3.3 Dept Repayment & User Fees\*

Sewer Use costs have been developed using a Benefit Unit approach presented in Appendix L.

#### 6.3.4 Reserves

It is anticipated that debt service reserves will be accounted for in future Village and Town budgets. Short lived assets are tabulated in Table 6.2, below.

TABLE 6.2 - Short Lived Assets

Description Cost		
1-5 Years		
STEP Tank Float Switches		¢11 700
STEP Tank Fildat Switches STEP Tank Effluent Filters		\$11,700
		\$19,500
Biofiltration System Pump Float Switches		\$1,050
UV Bulbs and Sleeves		\$9,600
5-10 Years		
Office Computer		\$2,000
Biofiltration System Spray Nozzles		\$9,000
UV Bulbs and Sleeves		\$9,600
10-15 Years		
Influent Flow Meter		\$5,500
Effluent Flow Meter		\$5,500
UV Bulbs and Sleeves		\$9,600
Fans		\$12,000
Control Building Lights		\$500
Control Building HVAC		\$7,500
Sewer District Truck		\$70,000
	Total	\$173,050

# 6.4 Project Implementation & Schedule\*

The following are the next steps for project implementation of the recommended alternative:

1. <u>Secure Additional Project Funding</u> - As indicated in this report, the cost of the proposed system is substantial. It is recommended that this report is used to apply for financial assistance for funding the design and construction of the recommended alternative. This report has been modified for the USDA Rural Development application. The Village plans to continue pursuing WQIP in 2025.

#### 2. Engineering & Design:


- a. Preliminary Engineering A \$200,000 Municipal Innovation Grant has been secured to fund a portion of preliminary design. The QBS process has been utilized to select an engineer and an engineering contract has been executed. The Preliminary Design is now mostly complete and included:
  - i. Site Survey A topographic and boundary survey of the treatment and disposal site conducted by the engineering consultant.

- ii. Collection System Survey A survey of the collection system to locate existing utilities and prevent conflicts with the utilities during construction of the new collection system.
- iii. Soil Testing Geotechnical information collected at the treatment system site and in the collection system and will be used for final design of the collection and treatment system components.
- iv. Parcel Investigations A parcel by parcel survey completed to determine the type and location of the existing wastewater treatment systems in order to determine the appropriate connection points and locations for the new STEP tanks.
- b. Final Engineering As noted above a wastewater design engineer has been selected through the QBS process, final engineering will include design and construction administration and observation for construction of the collection, water resource recovery, and return systems. The Village recently received a \$959,752 Congressionally Directed Spending Community Project Funding Grant which will be used to fund the final design phase.
  - i. Service Area Flow Confirmation Following the completion of the water meter replacement project, the measured flows for the proposed sewer district should be compared to the estimated flows. As discussed in Section 3.4.1, it is anticipated that actual flows will be less than the estimated flows based on the water production data available.
  - ii. Permitting the engineering consultant will assist the Village with obtaining a SPDES permit for the system. Permits will be required for construction of the sewer mains where the sewer mains cross state roads. A Protections of Water Permit will be required for stream crossings and the outfall through NYSDEC. A permit for the outfall will also be required through the Army Corp of Engineers. A SWPPP for Construction Phase activities will also be developed.
  - iii. Design Phases- Design of the collection, treatment, and disposal system will advance in stages including 30%, 60%, and 100% (permit set) design phases. The engineering consultant will have discussions with regulators during the design including the NYSDEC and the Dutchess County Department of Behavioral and Community Health. Design modifications may be required depending on discussions with regulators.
  - iv. Contract Documents Contract documents appropriate for permitting and construction will be developed and will consist of drawings and specifications for each phase of the design process.
  - v. Regulatory Review It is anticipated that the NYSDEC and the Dutchess County Department of Behavioral and Community Health will need to review and approve the 100% design prior to bidding.
  - vi. Bidding The project will go out to public bid after receiving approval.

- vii. Construction Administration & Observation The engineering consultant will provide construction administration and observation services.
- 3. Construction Construction will be awarded and commence following receipt of reasonable bids. It is anticipated that the construction project will be split into two prime contracts: general construction and electrical construction per Wick's Law. The sequence of construction would likely start with installation of the water resource recovery and return systems, installation of the sewer mains, and then making the service connections to each user.
- 4. Testing and Start-up Testing and start-up will begin as construction nears completion and service connections are made.

The anticipated project schedule is attached as Appendix M.

**APPENDIX A** 





Ortho provided by dhses.ny.gov (2016).
 Parcel lines are approximate.
 Resource data provided by NYSGIS clearinghouse (gis.ny.gov)


400 Feet


1 in = 800 ft


# **Study Area Boundary**


Village of Millerton Wastewater Feasibility Evaluation


March 2020











Ortho provided by dhses.ny.gov (2016).
 Parcel lines are approximate.
 Resource data provided by NYSGIS clearinghouse (gis.ny.gov)
 Flood zone delineation provided by FEMA.
 NWI wetlands provided by U.S. Fish & Wildlife Service.


1 in = 800 ft400 800 Feet


Village of Millerton Wastewater Feasibility Evaluation

March 2020

Engineers | Environmental Specialists

PROVIDED IN NEW YORK BY T&B ENGINEERING, P.C.





Engineers | Environmental Specialists

PROVIDED IN NEW YORK BY T&B ENGINEERING, P.C.

Ortho provided by dhses.ny.gov (2016).
 Parcel lines are approximate.
 Resource data provided by NYSGIS clearinghouse (gis.ny.gov).


Wastewater Feasibility Evaluation

March 2020

400

Feet

800






Ortho provided by dhses.ny.gov (2016).
 Parcel lines are approximate.
 Wastewater survey results provided by the Village of Millerton.

400 800 Feet

1 in = 800 ft

Village of Millerton Wastewater Feasibility Evaluation

March 2020






Ortho provided by dhses.ny.gov (2016).
 Parcel lines are approximate.
 Resource data provided by NYS GIS clearinghouse (gis.ny.gov).


400 800 Feet

1 in = 800 ft

Village of Millerton Wastewater Feasibility Evaluation

March 2020





**APPENDIX B** 



**NRCS** 

Natural Resources Conservation Service A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

# Custom Soil Resource Report for Dutchess County, New York



# **Preface**

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2 053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# **Contents**

Preface	2
How Soil Surveys Are Made	
Soil Map	
Soil Map	
Legend	10
Map Unit Legend	11
Map Unit Descriptions	
Dutchess County, New York	
Cc—Catden muck, 0 to 2 percent slopes	
CuA—Copake gravelly silt loam, nearly level	15
CuB—Copake gravelly silt loam, undulating	
CuC—Copake gravelly silt loam, rolling	
CuD—Copake gravelly silt loam, hilly	
CwA—Copake channery silt loam, fan, 0 to 3 percent slopes	
CxB—Copake-Urban land complex, undulating	22
DwC—Dutchess-Cardigan complex, rolling, rocky	23
DwD—Dutchess-Cardigan complex, hilly, rocky	25
Ff—Fluvaquents-Udifluvents complex, frequently flooded	27
GfB—Galway-Farmington complex, undulating, rocky	29
GsA—Georgia silt loam, 0 to 3 percent slopes	31
GsB—Georgia silt loam, 3 to 8 percent slopes	33
Ha—Halsey mucky silt loam	34
MnA—Massena silt loam, 0 to 3 percent slopes	
NwD—Nassau-Cardigan complex, hilly, very rocky	
NxE—Nassau-Rock outcrop complex, steep	
Pg—Pawling silt loam	
SkB—Stockbridge silt loam, 3 to 8 percent slopes	
SkC—Stockbridge silt loam, 8 to 15 percent slopes	
SkD—Stockbridge silt loam, 15 to 25 percent slopes	
SmC—Stockbridge-Farmington complex, rolling, rocky	
Su—Sun silt loam	
Ue—Udorthents, wet substratum	
Ur—Urban land	
W—Water	
Wy—Wayland silt loam	
Soil Information for All Uses	
Soil Properties and Qualities	
Soil Qualities and Features	
Depth to Any Soil Restrictive Layer (Depth to Water Table)	
Water Features	
Depth to Water Table (Depth to Water Table)	
References	65

# **How Soil Surveys Are Made**

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.


Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



#### MAP LEGEND

å

Ŷ

Δ

**Water Features** 

Transportation

---

 $\sim$ 

Background

Spoil Area

Stony Spot

Wet Spot

Other

Rails

**US Routes** 

Major Roads

Local Roads

Very Stony Spot

Special Line Features

Streams and Canals

Interstate Highways

Aerial Photography

#### Area of Interest (AOI)

Area of Interest (AOI)

#### Soils

Soil Map Unit Polygons

Soil Map Unit Lines

Soil Map Unit Points

#### **Special Point Features**

Blowout

Borrow Pit

Clay Spot

Closed Depression

Gravel Pit

Gravelly Spot

Landfill

A Lava Flow

Marsh or swamp

Mine or Quarry

Miscellaneous Water

Perennial Water

Rock Outcrop

sandy Spot

Severely Eroded Spot

Sinkhole

Slide or Slip

Sodic Spot

# MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Dutchess County, New York Survey Area Data: Version 14, Oct 8, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 2, 2015—Oct 5, 2016

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# 10

# **Map Unit Legend**

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
Сс	Catden muck, 0 to 2 percent slopes	14.2	1.8%
CuA	Copake gravelly silt loam, nearly level	41.0	5.2%
CuB	Copake gravelly silt loam, undulating	113.8	14.5%
CuC	Copake gravelly silt loam, rolling	23.9	3.0%
CuD	Copake gravelly silt loam, hilly	3.8	0.5%
CwA	Copake channery silt loam, fan, 0 to 3 percent slopes	28.3	3.6%
СхВ	Copake-Urban land complex, undulating	12.6	1.6%
DwC	Dutchess-Cardigan complex, rolling, rocky	5.7	0.7%
DwD	Dutchess-Cardigan complex, hilly, rocky	11.6	1.5%
Ff	Fluvaquents-Udifluvents complex, frequently flooded	0.2	0.0%
GfB	Galway-Farmington complex, undulating, rocky	0.1	0.0%
GsA	Georgia silt loam, 0 to 3 percent slopes	1.8	0.2%
GsB	Georgia silt loam, 3 to 8 percent slopes	16.1	2.0%
На	Halsey mucky silt loam	5.6	0.7%
MnA	Massena silt loam, 0 to 3 percent slopes	19.6	2.5%
NwD	Nassau-Cardigan complex, hilly, very rocky	14.4	1.8%
NxE	Nassau-Rock outcrop complex, steep	18.5	2.3%
Pg	Pawling silt loam	4.5	0.6%
SkB	Stockbridge silt loam, 3 to 8 percent slopes	192.0	24.4%
SkC	Stockbridge silt loam, 8 to 15 percent slopes	172.3	21.9%
SkD	Stockbridge silt loam, 15 to 25 percent slopes	20.6	2.6%
SmC	Stockbridge-Farmington complex, rolling, rocky	14.1	1.8%
Su	Sun silt loam	6.8	0.9%
Ue	Udorthents, wet substratum	3.2	0.4%

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI	
Ur	Urban land	7.6	1.0%	
W	Water	0.3	0.0%	
Wy	Wayland silt loam	34.4	4.4%	
Totals for Area of Interest		786.9	100.0%	

# **Map Unit Descriptions**

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

# **Dutchess County, New York**

# Cc—Catden muck, 0 to 2 percent slopes

# **Map Unit Setting**

National map unit symbol: 2t2qk

Elevation: 0 to 1,430 feet

Mean annual precipitation: 36 to 71 inches Mean annual air temperature: 39 to 55 degrees F

Frost-free period: 140 to 240 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Catden and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Catden**

# Setting

Landform: Fens, kettles, marshes, swamps, bogs, depressions, depressions,

depressions

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Base slope, tread

Down-slope shape: Concave Across-slope shape: Concave

Parent material: Highly decomposed herbaceous organic material and/or highly

decomposed woody organic material

# **Typical profile**

Oa1 - 0 to 2 inches: muck Oa2 - 2 to 79 inches: muck

#### **Properties and qualities**

Slope: 0 to 1 percent

Percent of area covered with surface fragments: 0.0 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Very poorly drained

Runoff class: Negligible

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high

(0.14 to 14.17 in/hr)

Depth to water table: About 0 to 6 inches

Frequency of flooding: None Frequency of ponding: Frequent

Available water storage in profile: Very high (about 26.9 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: B/D Hydric soil rating: Yes

# **Minor Components**

#### Canandaigua

Percent of map unit: 5 percent

Landform: Depressions

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Base slope, tread

Down-slope shape: Concave Across-slope shape: Concave

Hydric soil rating: Yes

# Natchaug

Percent of map unit: 5 percent Landform: Depressions, depressions

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Base slope, tread

Down-slope shape: Concave Across-slope shape: Concave

Hydric soil rating: Yes

#### Alden

Percent of map unit: 5 percent

Landform: Depressions

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Base slope, tread

Down-slope shape: Concave Across-slope shape: Concave

Hydric soil rating: Yes

#### **Timakwa**

Percent of map unit: 5 percent

Landform: Swamps

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Base slope, tread

Down-slope shape: Linear, concave Across-slope shape: Linear, concave

Hydric soil rating: Yes

# CuA—Copake gravelly silt loam, nearly level

#### Map Unit Setting

National map unit symbol: 9rf9

Mean annual precipitation: 41 to 47 inches
Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

# **Map Unit Composition**

Copake and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

## **Description of Copake**

# Setting

Landform: Outwash plains, terraces, deltas Landform position (two-dimensional): Summit Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy over calcareous sandy and gravelly glaciofluvial deposits

# **Typical profile**

H1 - 0 to 6 inches: gravelly silt loam H2 - 6 to 36 inches: gravelly loam

H3 - 36 to 80 inches: stratified very gravelly coarse sand to gravelly loamy fine

sand

# Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.3 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 1

Hydrologic Soil Group: A Hydric soil rating: No

# **Minor Components**

# Hoosic

Percent of map unit: 10 percent

Hydric soil rating: No

#### Halsey

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# Fredon

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# CuB—Copake gravelly silt loam, undulating

# **Map Unit Setting**

National map unit symbol: 9rfb

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

# **Map Unit Composition**

Copake and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Copake**

## Setting

Landform: Terraces, deltas, outwash plains Landform position (two-dimensional): Summit Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy over calcareous sandy and gravelly glaciofluvial deposits

#### Typical profile

H1 - 0 to 6 inches: gravelly silt loam H2 - 6 to 36 inches: gravelly loam

H3 - 36 to 80 inches: stratified very gravelly coarse sand to gravelly loamy fine sand

# Properties and qualities

Slope: 3 to 8 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.3 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: A Hydric soil rating: No

# **Minor Components**

#### Hoosic

Percent of map unit: 10 percent

Hydric soil rating: No

#### Fredon

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

#### Halsey

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# CuC—Copake gravelly silt loam, rolling

# **Map Unit Setting**

National map unit symbol: 9rfc

Mean annual precipitation: 41 to 47 inches

Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Farmland of statewide importance

#### **Map Unit Composition**

Copake and similar soils: 85 percent Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Copake**

# **Setting**

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy over calcareous sandy and gravelly glaciofluvial deposits

# Typical profile

H1 - 0 to 6 inches: gravelly silt loam H2 - 6 to 36 inches: gravelly loam

H3 - 36 to 80 inches: stratified very gravelly coarse sand to gravelly loamy fine sand

# Properties and qualities

Slope: 5 to 16 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.3 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: A Hydric soil rating: No

# **Minor Components**

#### Hoosic

Percent of map unit: 10 percent

Hydric soil rating: No

#### Fredon

Percent of map unit: 3 percent Landform: Depressions Hydric soil rating: Yes

## Halsey

Percent of map unit: 2 percent Landform: Depressions Hydric soil rating: Yes

# CuD—Copake gravelly silt loam, hilly

# **Map Unit Setting**

National map unit symbol: 9rfd

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

# Map Unit Composition

Copake and similar soils: 85 percent Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Copake**

#### Setting

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Backslope Landform position (three-dimensional): Riser

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Loamy over calcareous sandy and gravelly glaciofluvial deposits

## Typical profile

H1 - 0 to 6 inches: gravelly silt loam H2 - 6 to 36 inches: gravelly loam

H3 - 36 to 80 inches: stratified very gravelly coarse sand to gravelly loamy fine

sand

# Properties and qualities

Slope: 15 to 30 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.3 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: A Hydric soil rating: No

# **Minor Components**

# Hoosic

Percent of map unit: 10 percent

NIO.

Hydric soil rating: No

#### Fredon

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# CwA—Copake channery silt loam, fan, 0 to 3 percent slopes

# **Map Unit Setting**

National map unit symbol: 9rfg Elevation: 300 to 850 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

# Map Unit Composition

Copake, fan, and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# Description of Copake, Fan

#### Setting

Landform: Terraces, deltas, outwash plains Landform position (two-dimensional): Summit Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy over calcareous sandy and gravelly glaciofluvial deposits

# **Typical profile**

H1 - 0 to 6 inches: channery silt loam H2 - 6 to 36 inches: channery loam

H3 - 36 to 80 inches: stratified very gravelly coarse sand to gravelly loamy fine

sand

# Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: About 36 to 72 inches

Frequency of flooding: Rare Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.3 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 1

Hydrologic Soil Group: A Hydric soil rating: No

# **Minor Components**

#### Hoosic

Percent of map unit: 10 percent

Hydric soil rating: No

#### Fredon

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# Halsey

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# CxB—Copake-Urban land complex, undulating

# **Map Unit Setting**

National map unit symbol: 9rfj

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Copake and similar soils: 40 percent

Urban land: 35 percent

Minor components: 25 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

## **Description of Copake**

# Setting

Landform: Deltas, outwash plains, terraces Landform position (two-dimensional): Summit Landform position (three-dimensional): Tread

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy over calcareous sandy and gravelly glaciofluvial deposits

#### Typical profile

H1 - 0 to 6 inches: gravelly silt loam H2 - 6 to 36 inches: gravelly loam

H3 - 36 to 80 inches: stratified very gravelly coarse sand to gravelly loamy fine sand

# Properties and qualities

Slope: 1 to 6 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.3 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: A Hydric soil rating: No

## **Description of Urban Land**

# Typical profile

H1 - 0 to 6 inches: variable

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8s

Hydric soil rating: Unranked

#### **Minor Components**

#### **Udorthents**

Percent of map unit: 10 percent

Hydric soil rating: No

#### Fredon

Percent of map unit: 5 percent

Landform: Depressions Hydric soil rating: Yes

#### Hoosic

Percent of map unit: 5 percent

Hydric soil rating: No

#### Halsey

Percent of map unit: 5 percent

Landform: Depressions Hydric soil rating: Yes

# DwC—Dutchess-Cardigan complex, rolling, rocky

#### **Map Unit Setting**

National map unit symbol: 9rfp Elevation: 50 to 1,000 feet

Mean annual precipitation: 41 to 47 inches

Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Farmland of statewide importance

# **Map Unit Composition**

Dutchess and similar soils: 40 percent Cardigan and similar soils: 30 percent

Minor components: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Dutchess**

#### Setting

Landform: Ridges, hills

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till derived mainly from phyllite, slate, schist, and shale

# **Typical profile**

H1 - 0 to 8 inches: silt loam H2 - 8 to 28 inches: silt loam

H3 - 28 to 86 inches: channery silt loam

# Properties and qualities

Slope: 5 to 16 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 1.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: High (about 9.6 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: B Hydric soil rating: No

# **Description of Cardigan**

# Setting

Landform: Hills, ridges

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till or colluvium derived from phyllite, slate, shale, and

schist

# **Typical profile**

H1 - 0 to 8 inches: channery silt loam
H2 - 8 to 20 inches: channery loam
H3 - 20 to 30 inches: channery silt loam
H4 - 30 to 34 inches: unweathered bedrock

#### Properties and qualities

Slope: 5 to 16 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low

(0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.1 inches)

## Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C Hydric soil rating: No

# **Minor Components**

# Georgia

Percent of map unit: 10 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 9 percent

Hydric soil rating: No

#### Nassau

Percent of map unit: 9 percent

Hydric soil rating: No

#### **Rock outcrop**

Percent of map unit: 1 percent Hydric soil rating: Unranked

#### Sun

Percent of map unit: 1 percent Landform: Depressions Hydric soil rating: Yes

# DwD—Dutchess-Cardigan complex, hilly, rocky

# **Map Unit Setting**

National map unit symbol: 9rfq Elevation: 50 to 1,000 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Dutchess and similar soils: 40 percent Cardigan and similar soils: 30 percent

Minor components: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Dutchess**

# Setting

Landform: Ridges, hills

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till derived mainly from phyllite, slate, schist, and shale

# **Typical profile**

H1 - 0 to 8 inches: silt loam H2 - 8 to 28 inches: silt loam

H3 - 28 to 86 inches: channery silt loam

## Properties and qualities

Slope: 15 to 30 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 1.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: High (about 9.6 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: B Hydric soil rating: No

# **Description of Cardigan**

## Setting

Landform: Ridges, hills

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till or colluvium derived from phyllite, slate, shale, and

schist

# Typical profile

H1 - 0 to 8 inches: channery silt loam
H2 - 8 to 20 inches: channery loam
H3 - 20 to 30 inches: channery silt loam
H4 - 30 to 34 inches: unweathered bedrock

#### Properties and qualities

Slope: 15 to 30 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low

(0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.1 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: C Hydric soil rating: No

#### **Minor Components**

# Sun

Percent of map unit: 10 percent Landform: Depressions

Hydric soil rating: Yes

#### Nassau

Percent of map unit: 9 percent

Hydric soil rating: No

# Georgia

Percent of map unit: 5 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 5 percent

Hydric soil rating: No

## Rock outcrop

Percent of map unit: 1 percent Hydric soil rating: Unranked

# Ff—Fluvaquents-Udifluvents complex, frequently flooded

## Map Unit Setting

National map unit symbol: 9rfy Elevation: 100 to 3,000 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Fluvaquents and similar soils: 50 percent Udifluvents and similar soils: 40 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Fluvaquents**

#### Setting

Landform: Flood plains

Landform position (two-dimensional): Toeslope Landform position (three-dimensional): Dip

Down-slope shape: Concave Across-slope shape: Concave

Parent material: Alluvium with highly variable texture

## Typical profile

H1 - 0 to 5 inches: gravelly silt loam H2 - 5 to 70 inches: very gravelly silt loam

# **Properties and qualities**

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to very

high (0.06 to 19.98 in/hr)

Depth to water table: About 0 inches Frequency of flooding: Frequent Frequency of ponding: Frequent

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.1 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: A/D Hydric soil rating: Yes

# **Description of Udifluvents**

## Setting

Landform: Flood plains

Landform position (two-dimensional): Summit Landform position (three-dimensional): Talf

Down-slope shape: Concave Across-slope shape: Convex

Parent material: Alluvium with a wide range of texture

#### Typical profile

H1 - 0 to 4 inches: gravelly loam H2 - 4 to 70 inches: very gravelly loam

#### **Properties and qualities**

Slope: 0 to 5 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to very

high (0.06 to 19.98 in/hr)

Depth to water table: About 24 to 72 inches

Frequency of flooding: Frequent Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent Available water storage in profile: Low (about 5.9 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: A Hydric soil rating: No

## **Minor Components**

# Linlithgo

Percent of map unit: 2 percent Landform: Depressions Hydric soil rating: No

#### Wayland

Percent of map unit: 2 percent Landform: Flood plains Hydric soil rating: Yes

## Wappinger

Percent of map unit: 1 percent Landform: Depressions Hydric soil rating: No

# **Pawling**

Percent of map unit: 1 percent Landform: Depressions Hydric soil rating: No

#### Carlisle

Percent of map unit: 1 percent Landform: Marshes, swamps Hydric soil rating: Yes

#### Palms

Percent of map unit: 1 percent Landform: Marshes, swamps Hydric soil rating: Yes

## Hoosic, fan

Percent of map unit: 1 percent Hydric soil rating: No

# Copake, fan

Percent of map unit: 1 percent Hydric soil rating: No

# GfB—Galway-Farmington complex, undulating, rocky

# **Map Unit Setting**

National map unit symbol: 9rg0 Elevation: 100 to 1,000 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

# **Map Unit Composition**

Galway and similar soils: 40 percent Farmington and similar soils: 30 percent

Minor components: 30 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

## **Description of Galway**

## Setting

Landform: Benches, ridges, till plains

Landform position (two-dimensional): Summit Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Calcareous loamy till

# **Typical profile**

H1 - 0 to 6 inches: gravelly loam H2 - 6 to 30 inches: gravelly loam H3 - 30 to 31 inches: gravelly loam

H4 - 31 to 35 inches: unweathered bedrock

# Properties and qualities

Slope: 1 to 6 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 25 percent Available water storage in profile: Low (about 4.2 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C Hydric soil rating: No

# **Description of Farmington**

#### Setting

Landform: Till plains, benches, ridges

Landform position (two-dimensional): Summit Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till or congeliturbate derived from limestone, dolomite, shale, and sandstone, and in many places mixed with wind and water deposits

#### Typical profile

H1 - 0 to 7 inches: loam

H2 - 7 to 15 inches: very fine sandy loam H3 - 15 to 19 inches: unweathered bedrock

## **Properties and qualities**

Slope: 1 to 6 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 5 percent

Available water storage in profile: Very low (about 2.1 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3s

Hydrologic Soil Group: D Hydric soil rating: No

# **Minor Components**

# Georgia

Percent of map unit: 10 percent

Hydric soil rating: No

# Stockbridge

Percent of map unit: 10 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 8 percent

Hydric soil rating: No

#### Rock outcrop

Percent of map unit: 1 percent Hydric soil rating: Unranked

# Sun

Percent of map unit: 1 percent Landform: Depressions Hydric soil rating: Yes

# GsA—Georgia silt loam, 0 to 3 percent slopes

# **Map Unit Setting**

National map unit symbol: 9rg5 Elevation: 90 to 1,000 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

## **Map Unit Composition**

Georgia and similar soils: 80 percent *Minor components*: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Georgia**

# Setting

Landform: Hills, till plains, drumlinoid ridges Landform position (two-dimensional): Summit Landform position (three-dimensional): Crest

Down-slope shape: Concave Across-slope shape: Convex

Parent material: Loamy till derived mainly from limestone, shale, or slate

## Typical profile

H1 - 0 to 8 inches: silt loam H2 - 8 to 27 inches: loam

H3 - 27 to 80 inches: gravelly fine sandy loam

# Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 18 to 36 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Moderate (about 8.6 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2w

Hydrologic Soil Group: C Hydric soil rating: No

## **Minor Components**

#### Massena

Percent of map unit: 5 percent

Hydric soil rating: No

#### Stockbridge

Percent of map unit: 5 percent

Hydric soil rating: No

# Charlton

Percent of map unit: 3 percent

Hydric soil rating: No

#### **Dutchess**

Percent of map unit: 3 percent

Hydric soil rating: No

# Sun

Percent of map unit: 2 percent Landform: Depressions

Hydric soil rating: Yes

#### **Punsit**

Percent of map unit: 2 percent

Hydric soil rating: No

# GsB—Georgia silt loam, 3 to 8 percent slopes

# **Map Unit Setting**

National map unit symbol: 9rg6 Elevation: 90 to 1,000 feet

Mean annual precipitation: 41 to 47 inches
Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

# **Map Unit Composition**

Georgia and similar soils: 80 percent *Minor components:* 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Georgia**

# Setting

Landform: Drumlinoid ridges, hills, till plains Landform position (two-dimensional): Summit Landform position (three-dimensional): Crest

Down-slope shape: Concave Across-slope shape: Convex

Parent material: Loamy till derived mainly from limestone, shale, or slate

# Typical profile

H1 - 0 to 8 inches: silt loam H2 - 8 to 27 inches: loam

H3 - 27 to 80 inches: gravelly fine sandy loam

#### **Properties and qualities**

Slope: 3 to 8 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 18 to 36 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Moderate (about 8.6 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C

Hydric soil rating: No

# **Minor Components**

#### Charlton

Percent of map unit: 5 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 5 percent

Hydric soil rating: No

# Stockbridge

Percent of map unit: 5 percent

Hydric soil rating: No

#### **Dutchess**

Percent of map unit: 3 percent

Hydric soil rating: No

#### **Pittstown**

Percent of map unit: 2 percent

Hydric soil rating: No

# Ha—Halsey mucky silt loam

#### Map Unit Setting

National map unit symbol: 9rg8

Mean annual precipitation: 41 to 47 inches

Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Halsey and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Halsey**

# Setting

Landform: Depressions

Landform position (two-dimensional): Toeslope Landform position (three-dimensional): Tread

Down-slope shape: Concave Across-slope shape: Concave

Parent material: Loamy glaciofluvial deposits over sandy and gravelly glaciofluvial

deposits

# Typical profile

H1 - 0 to 9 inches: mucky silt loam H2 - 9 to 33 inches: gravelly loam

H3 - 33 to 60 inches: stratified very gravelly loamy sand

# Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Very poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 1.98 in/hr)

Depth to water table: About 0 to 6 inches

Frequency of flooding: Rare Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 7.2 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: B/D Hydric soil rating: Yes

# **Minor Components**

#### **Fredon**

Percent of map unit: 10 percent

Landform: Depressions Hydric soil rating: No

#### Palms

Percent of map unit: 5 percent Landform: Marshes, swamps

Hydric soil rating: Yes

#### Carlisle

Percent of map unit: 5 percent Landform: Marshes, swamps

Hydric soil rating: Yes

# MnA—Massena silt loam, 0 to 3 percent slopes

# **Map Unit Setting**

National map unit symbol: 9rh9 Elevation: 100 to 1,000 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Prime farmland if drained

# **Map Unit Composition**

Massena and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

## **Description of Massena**

# Setting

Landform: Hills, till plains, drumlinoid ridges

Landform position (two-dimensional): Footslope, summit Landform position (three-dimensional): Base slope

Down-slope shape: Concave Across-slope shape: Linear

Parent material: Loamy till dominated by siliceous rocks with varying proportions

of limestone

## Typical profile

H1 - 0 to 7 inches: silt loam H2 - 7 to 33 inches: loam

H3 - 33 to 72 inches: fine sandy loam

## **Properties and qualities**

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Somewhat poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: About 12 to 18 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 10 percent

Available water storage in profile: Moderate (about 7.0 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3w

Hydrologic Soil Group: C/D Hydric soil rating: No

# **Minor Components**

# Sun

Percent of map unit: 10 percent

Landform: Depressions Hydric soil rating: Yes

#### Georgia

Percent of map unit: 5 percent

Hydric soil rating: No

# Punsit

Percent of map unit: 5 percent

Hydric soil rating: No

# NwD—Nassau-Cardigan complex, hilly, very rocky

# **Map Unit Setting**

National map unit symbol: 9rhf Elevation: 600 to 1,800 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

## **Map Unit Composition**

Nassau and similar soils: 45 percent Cardigan and similar soils: 30 percent Minor components: 25 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Nassau**

# Setting

Landform: Benches, ridges, till plains

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Channery loamy till derived mainly from local slate or shale

# Typical profile

H1 - 0 to 5 inches: channery silt loam H2 - 5 to 16 inches: very channery silt loam H3 - 16 to 20 inches: unweathered bedrock

# Properties and qualities

Slope: 15 to 30 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low

(0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Very low (about 1.7 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D Hydric soil rating: No

## **Description of Cardigan**

#### Setting

Landform: Hills, ridges

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till or colluvium derived from phyllite, slate, shale, and

schist

# **Typical profile**

H1 - 0 to 8 inches: channery silt loam
H2 - 8 to 20 inches: channery loam
H3 - 20 to 30 inches: channery silt loam
H4 - 30 to 34 inches: unweathered bedrock

# **Properties and qualities**

Slope: 15 to 30 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low

(0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Low (about 4.1 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C Hydric soil rating: No

# **Minor Components**

# **Dutchess**

Percent of map unit: 10 percent

Hydric soil rating: No

#### Sun

Percent of map unit: 10 percent

Landform: Depressions Hydric soil rating: Yes

# **Rock outcrop**

Percent of map unit: 5 percent Hydric soil rating: Unranked

# NxE—Nassau-Rock outcrop complex, steep

## **Map Unit Setting**

National map unit symbol: 9rhg Elevation: 600 to 1,800 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Nassau and similar soils: 45 percent

Rock outcrop: 30 percent Minor components: 25 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Nassau**

# Setting

Landform: Benches, ridges, till plains

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Channery loamy till derived mainly from local slate or shale

# **Typical profile**

H1 - 0 to 5 inches: channery silt loam H2 - 5 to 16 inches: very channery silt loam H3 - 16 to 20 inches: unweathered bedrock

#### **Properties and qualities**

Slope: 25 to 45 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Low to moderately low

(0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water storage in profile: Very low (about 1.7 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D Hydric soil rating: No

## **Description of Rock Outcrop**

#### Typical profile

H1 - 0 to 60 inches: unweathered bedrock

# Properties and qualities

Slope: 25 to 45 percent

Depth to restrictive feature: 0 inches to lithic bedrock

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately

low (0.00 to 0.06 in/hr)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydric soil rating: Unranked

## **Minor Components**

# Cardigan

Percent of map unit: 10 percent

Hydric soil rating: No

#### **Dutchess**

Percent of map unit: 10 percent

Hydric soil rating: No

#### Sun

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

# Pg—Pawling silt loam

#### **Map Unit Setting**

National map unit symbol: 9rhk

Elevation: 50 to 500 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

# **Map Unit Composition**

Pawling and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Pawling**

#### Setting

Landform: Flood plains

Landform position (two-dimensional): Summit Landform position (three-dimensional): Talf

Down-slope shape: Concave Across-slope shape: Convex

Parent material: Loamy over sandy and gravelly alluvium

# **Typical profile**

H1 - 0 to 8 inches: silt loam H2 - 8 to 33 inches: silt loam

H3 - 33 to 72 inches: very gravelly sand

# **Properties and qualities**

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to

high (0.57 to 1.98 in/hr)

Depth to water table: About 18 to 24 inches

Frequency of flooding: Occasional Frequency of ponding: None

Calcium carbonate, maximum in profile: 2 percent

Available water storage in profile: Moderate (about 6.6 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: B/D Hydric soil rating: No

# **Minor Components**

# Linlithgo

Percent of map unit: 10 percent

Hydric soil rating: No

#### Wayland

Percent of map unit: 5 percent Landform: Flood plains Hydric soil rating: Yes

# Wappinger

Percent of map unit: 5 percent

Hydric soil rating: No

# SkB—Stockbridge silt loam, 3 to 8 percent slopes

#### Map Unit Setting

National map unit symbol: 9rhv

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: All areas are prime farmland

#### **Map Unit Composition**

Stockbridge and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Stockbridge**

#### Setting

Landform: Till plains, drumlinoid ridges, hills Landform position (two-dimensional): Summit Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Calcareous loamy till

#### **Typical profile**

H1 - 0 to 6 inches: silt loam H2 - 6 to 23 inches: silt loam H3 - 23 to 80 inches: silt loam

#### **Properties and qualities**

Slope: 3 to 8 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 8.4 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C Hydric soil rating: No

#### **Minor Components**

#### Georgia

Percent of map unit: 5 percent

Hydric soil rating: No

#### Galway

Percent of map unit: 4 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 4 percent

Hydric soil rating: No

#### Charlton

Percent of map unit: 3 percent

Hydric soil rating: No

#### Bernardston

Percent of map unit: 2 percent

Hydric soil rating: No

#### **Farmington**

Percent of map unit: 1 percent

Hydric soil rating: No

#### Sun

Percent of map unit: 1 percent Landform: Depressions Hydric soil rating: Yes

#### SkC—Stockbridge silt loam, 8 to 15 percent slopes

#### **Map Unit Setting**

National map unit symbol: 9rhw

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Farmland of statewide importance

#### **Map Unit Composition**

Stockbridge and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Stockbridge**

#### Setting

Landform: Hills, till plains, drumlinoid ridges Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Calcareous loamy till

#### Typical profile

H1 - 0 to 6 inches: silt loam H2 - 6 to 23 inches: silt loam H3 - 23 to 80 inches: silt loam

#### **Properties and qualities**

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 8.4 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C Hydric soil rating: No

#### **Minor Components**

#### Georgia

Percent of map unit: 5 percent

Hydric soil rating: No

#### Galway

Percent of map unit: 4 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 4 percent

Hydric soil rating: No

#### Charlton

Percent of map unit: 3 percent

Hydric soil rating: No

#### **Bernardston**

Percent of map unit: 2 percent

Hydric soil rating: No

#### **Farmington**

Percent of map unit: 1 percent

Hydric soil rating: No

#### Sun

Percent of map unit: 1 percent

Landform: Depressions Hydric soil rating: Yes

#### SkD—Stockbridge silt loam, 15 to 25 percent slopes

#### **Map Unit Setting**

National map unit symbol: 9rhx

Mean annual precipitation: 41 to 47 inches
Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

#### **Map Unit Composition**

Stockbridge and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Stockbridge**

#### Setting

Landform: Hills, till plains, drumlinoid ridges Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Calcareous loamy till

#### **Typical profile**

H1 - 0 to 6 inches: silt loam H2 - 6 to 23 inches: silt loam H3 - 23 to 80 inches: silt loam

#### Properties and qualities

Slope: 15 to 25 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 8.4 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: C Hydric soil rating: No

#### **Minor Components**

#### **Bernardston**

Percent of map unit: 5 percent

Hydric soil rating: No

#### Charlton

Percent of map unit: 5 percent

Hydric soil rating: No

#### Galway

Percent of map unit: 4 percent

Hydric soil rating: No

#### Georgia

Percent of map unit: 4 percent

Hydric soil rating: No

#### Farmington

Percent of map unit: 1 percent

Hydric soil rating: No

#### Sun

Percent of map unit: 1 percent Landform: Depressions

Hydric soil rating: Yes

#### SmC—Stockbridge-Farmington complex, rolling, rocky

#### Map Unit Setting

National map unit symbol: 9rj0 Elevation: 100 to 900 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Farmland of statewide importance

#### **Map Unit Composition**

Stockbridge and similar soils: 50 percent Farmington and similar soils: 30 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Stockbridge**

#### Setting

Landform: Drumlinoid ridges, hills, till plains Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Calcareous loamy till

#### Typical profile

H1 - 0 to 6 inches: silt loam H2 - 6 to 23 inches: silt loam H3 - 23 to 80 inches: silt loam

#### **Properties and qualities**

Slope: 5 to 16 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 8.4 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C Hydric soil rating: No

#### **Description of Farmington**

#### Setting

Landform: Benches, ridges, till plains

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Loamy till or congeliturbate derived from limestone, dolomite, shale, and sandstone, and in many places mixed with wind and water deposits

#### **Typical profile**

H1 - 0 to 7 inches: loam

H2 - 7 to 15 inches: very fine sandy loam H3 - 15 to 19 inches: unweathered bedrock

#### **Properties and qualities**

Slope: 5 to 16 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 5 percent

Available water storage in profile: Very low (about 2.1 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: D Hydric soil rating: No

#### **Minor Components**

#### Galway

Percent of map unit: 10 percent

Hydric soil rating: No

#### Georgia

Percent of map unit: 5 percent

Hydric soil rating: No

#### Massena

Percent of map unit: 3 percent

Hydric soil rating: No

#### **Rock outcrop**

Percent of map unit: 1 percent Hydric soil rating: Unranked

#### Sun

Percent of map unit: 1 percent Landform: Depressions Hydric soil rating: Yes

#### Su-Sun silt loam

#### **Map Unit Setting**

National map unit symbol: 9rj3 Elevation: 600 to 1,800 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Farmland of statewide importance

#### Map Unit Composition

Sun and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Sun**

#### Setting

Landform: Depressions

Landform position (two-dimensional): Toeslope Landform position (three-dimensional): Base slope

Down-slope shape: Concave Across-slope shape: Concave

Parent material: Loamy till derived primarily from limestone and sandstone, with a

component of schist, shale, or granitic rocks in some areas

#### **Typical profile**

H1 - 0 to 4 inches: silt loam H2 - 4 to 22 inches: loam

H3 - 22 to 80 inches: gravelly loam

#### Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr) Depth to water table: About 0 inches

Frequency of flooding: None Frequency of ponding: Occasional

Calcium carbonate, maximum in profile: 15 percent

Available water storage in profile: Moderate (about 6.2 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4w

Hydrologic Soil Group: C/D Hydric soil rating: Yes

#### **Minor Components**

#### Canandaigua

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

#### Massena

Percent of map unit: 5 percent

Hydric soil rating: No

#### **Palms**

Percent of map unit: 5 percent Landform: Marshes, swamps Hydric soil rating: Yes

#### Sun, stony

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: Yes

#### **Ue—Udorthents**, wet substratum

#### **Map Unit Setting**

National map unit symbol: 9rj8 Elevation: 50 to 2.400 feet

Mean annual precipitation: 41 to 47 inches
Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

#### **Map Unit Composition**

Udorthents, wet substratum, and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Udorthents, Wet Substratum**

#### **Typical profile**

H1 - 0 to 4 inches: gravelly loam H2 - 4 to 72 inches: very gravelly loam

#### **Properties and qualities**

Slope: 0 to 5 percent

Depth to restrictive feature: More than 80 inches Natural drainage class: Somewhat poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high

(0.06 to 5.95 in/hr)

Depth to water table: About 12 to 36 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent Available water storage in profile: Low (about 5.5 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: B Hydric soil rating: No

#### **Minor Components**

#### Udorthents, smoothed

Percent of map unit: 10 percent

Hydric soil rating: No

#### **Urban land**

Percent of map unit: 5 percent Hydric soil rating: Unranked

#### Unnamed soils, undisturbed

Percent of map unit: 4 percent Hydric soil rating: Unranked

#### Rock outcrop

Percent of map unit: 1 percent Hydric soil rating: Unranked

#### Ur-Urban land

#### **Map Unit Setting**

National map unit symbol: 9rjb

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

#### **Map Unit Composition**

Urban land: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Urban Land**

#### Typical profile

H1 - 0 to 6 inches: variable

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8s

Hydric soil rating: Unranked

#### **Minor Components**

#### Udorthents, smoothed

Percent of map unit: 5 percent

Hydric soil rating: No

#### Udorthents, wet substratum

Percent of map unit: 3 percent

Hydric soil rating: No

#### Unnamed soils, undisturbed

Percent of map unit: 1 percent Hydric soil rating: Unranked

#### **Rock outcrop**

Percent of map unit: 1 percent Hydric soil rating: Unranked

#### W-Water

#### **Map Unit Setting**

National map unit symbol: 9rjc

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

#### **Map Unit Composition**

Water: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### Wy—Wayland silt loam

#### **Map Unit Setting**

National map unit symbol: 9rjf Elevation: 200 to 1,500 feet

Mean annual precipitation: 41 to 47 inches Mean annual air temperature: 45 to 50 degrees F

Frost-free period: 115 to 195 days

Farmland classification: Not prime farmland

#### **Map Unit Composition**

Wayland and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

#### **Description of Wayland**

#### Setting

Landform: Flood plains

Landform position (two-dimensional): Toeslope Landform position (three-dimensional): Dip

Down-slope shape: Concave Across-slope shape: Concave

Parent material: Silty and clayey alluvium washed from uplands that contain some

calcareous drift

#### Typical profile

H1 - 0 to 9 inches: silt loam H2 - 9 to 80 inches: silt loam

#### Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 0 inches

Frequency of flooding: Frequent

Frequency of ponding: Frequent

Calcium carbonate, maximum in profile: 1 percent

Available water storage in profile: High (about 11.0 inches)

#### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: C/D Hydric soil rating: Yes

#### **Minor Components**

#### **Pawling**

Percent of map unit: 5 percent Landform: Depressions Hydric soil rating: No

#### Linlithgo

Percent of map unit: 5 percent

Hydric soil rating: No

#### **Fluvaquents**

Percent of map unit: 3 percent Landform: Flood plains Hydric soil rating: Yes

#### **Palms**

Percent of map unit: 3 percent Landform: Marshes, swamps Hydric soil rating: Yes

#### Carlisle

Percent of map unit: 2 percent Landform: Marshes, swamps

Hydric soil rating: Yes

### Udifluvents

Percent of map unit: 2 percent Hydric soil rating: No

# Soil Information for All Uses

# **Soil Properties and Qualities**

The Soil Properties and Qualities section includes various soil properties and qualities displayed as thematic maps with a summary table for the soil map units in the selected area of interest. A single value or rating for each map unit is generated by aggregating the interpretive ratings of individual map unit components. This aggregation process is defined for each property or quality.

### Soil Qualities and Features


Soil qualities are behavior and performance attributes that are not directly measured, but are inferred from observations of dynamic conditions and from soil properties. Example soil qualities include natural drainage, and frost action. Soil features are attributes that are not directly part of the soil. Example soil features include slope and depth to restrictive layer. These features can greatly impact the use and management of the soil.

# Depth to Any Soil Restrictive Layer (Depth to Water Table)

A "restrictive layer" is a nearly continuous layer that has one or more physical, chemical, or thermal properties that significantly impede the movement of water and air through the soil or that restrict roots or otherwise provide an unfavorable root environment. Examples are bedrock, cemented layers, dense layers, and frozen layers.

This theme presents the depth to any type of restrictive layer that is described for each map unit. If more than one type of restrictive layer is described for an individual soil type, the depth to the shallowest one is presented. If no restrictive layer is described in a map unit, it is represented by the "> 200" depth class.

This attribute is actually recorded as three separate values in the database. A low value and a high value indicate the range of this attribute for the soil component. A "representative" value indicates the expected value of this attribute for the component. For this soil property, only the representative value is used.



Not rated or not available

Streams and Canals

Interstate Highways

Aerial Photography

#### MAP LEGEND

**Water Features** 

Transportation

+++

Background

Rails

**US Routes** 

Major Roads

Local Roads

#### Area of Interest (AOI)

Area of Interest (AOI)

#### Soils

#### Soil Rating Polygons

- 0 25 25 - 50
- 50 100
- 100 150
- 150 200
- > 200
- Not rated or not available

#### Soil Rating Lines

- **....** 0 25
- 25 50
- 50 100
- 100 150
- 150 200
- > 200
- Not rated or not available

#### **Soil Rating Points**

- 0 25
- 25 50
- 50 100
- 100 150
- 150 200
- > 200

#### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Dutchess County, New York Survey Area Data: Version 14, Oct 8, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 2, 2015—Oct 5, 2016

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# Table—Depth to Any Soil Restrictive Layer (Depth to Water Table)

Map unit symbol	Map unit name	Rating (centimeters)	Acres in AOI	Percent of AOI
Сс	Catden muck, 0 to 2 percent slopes	>200	14.2	1.8%
CuA	Copake gravelly silt loam, nearly level	>200	41.0	5.2%
CuB	Copake gravelly silt loam, undulating	>200	113.8	14.5%
CuC	Copake gravelly silt loam, rolling	>200	23.9	3.0%
CuD	Copake gravelly silt loam, hilly	>200	3.8	0.5%
CwA	Copake channery silt loam, fan, 0 to 3 percent slopes	>200	28.3	3.6%
СхВ	Copake-Urban land complex, undulating	>200	12.6	1.6%
DwC	Dutchess-Cardigan complex, rolling, rocky	>200	5.7	0.7%
DwD	Dutchess-Cardigan complex, hilly, rocky	>200	11.6	1.5%
Ff	Fluvaquents-Udifluvents complex, frequently flooded	>200	0.2	0.0%
GfB	Galway-Farmington complex, undulating, rocky	79	0.1	0.0%
GsA	Georgia silt loam, 0 to 3 percent slopes	>200	1.8	0.2%
GsB	Georgia silt loam, 3 to 8 percent slopes	>200	16.1	2.0%
На	Halsey mucky silt loam	>200	5.6	0.7%
MnA	Massena silt loam, 0 to 3 percent slopes	>200	19.6	2.5%
NwD	Nassau-Cardigan complex, hilly, very rocky	41	14.4	1.8%
NxE	Nassau-Rock outcrop complex, steep	41	18.5	2.3%
Pg	Pawling silt loam	>200	4.5	0.6%
SkB	Stockbridge silt loam, 3 to 8 percent slopes	>200	192.0	24.4%
SkC	Stockbridge silt loam, 8 to 15 percent slopes	>200	172.3	21.9%
SkD	Stockbridge silt loam, 15 to 25 percent slopes	>200	20.6	2.6%

Map unit symbol	Map unit name	Rating (centimeters)	Acres in AOI	Percent of AOI
SmC	Stockbridge-Farmington complex, rolling, rocky	>200	14.1	1.8%
Su	Sun silt loam	>200	6.8	0.9%
Ue	Udorthents, wet substratum	>200	3.2	0.4%
Ur	Urban land	>200	7.6	1.0%
W	Water	>200	0.3	0.0%
Wy	Wayland silt loam	>200	34.4	4.4%
Totals for Area of Interest			786.9	100.0%

# Rating Options—Depth to Any Soil Restrictive Layer (Depth to Water Table)

Units of Measure: centimeters

Aggregation Method: Dominant Component Component Percent Cutoff: None Specified

Tie-break Rule: Lower Interpret Nulls as Zero: No


#### **Water Features**

Water Features include ponding frequency, flooding frequency, and depth to water table.

## **Depth to Water Table (Depth to Water Table)**

"Water table" refers to a saturated zone in the soil. It occurs during specified months. Estimates of the upper limit are based mainly on observations of the water table at selected sites and on evidence of a saturated zone, namely grayish colors (redoximorphic features) in the soil. A saturated zone that lasts for less than a month is not considered a water table.

This attribute is actually recorded as three separate values in the database. A low value and a high value indicate the range of this attribute for the soil component. A "representative" value indicates the expected value of this attribute for the component. For this soil property, only the representative value is used.



#### MAP LEGEND

#### Area of Interest (AOI)

Area of Interest (AOI)

#### Soils

#### Soil Rating Polygons

0 - 25

25 - 50

50 - 100

100 - 150

150 - 200

> 200

Not rated or not available

#### Not rated or not available

#### **Water Features**

Streams and Canals

#### Transportation

+++ Rails

Interstate Highways

US Routes

Major Roads

Local Roads

#### Background

Aerial Photography

#### Soil Rating Lines

**0 - 25** 

25 - 50

**5**0 - 100

100 - 150

150 - 200

> 200

Not rated or not available

#### **Soil Rating Points**

0 - 25

25 - 50

50 - 100

100 - 150

150 - 200

> 200

#### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Dutchess County, New York Survey Area Data: Version 14, Oct 8, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 2, 2015—Oct 5, 2016

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# Table—Depth to Water Table (Depth to Water Table)

Map unit symbol	Map unit name	Rating (centimeters)	Acres in AOI	Percent of AOI
Сс	Catden muck, 0 to 2 percent slopes	0	14.2	1.8%
CuA	Copake gravelly silt loam, nearly level	>200	41.0	5.2%
CuB	Copake gravelly silt loam, undulating	>200	113.8	14.5%
CuC	Copake gravelly silt loam, rolling	>200	23.9	3.0%
CuD	Copake gravelly silt loam, hilly	>200	3.8	0.5%
CwA	Copake channery silt loam, fan, 0 to 3 percent slopes	137	28.3	3.6%
СхВ	Copake-Urban land complex, undulating	>200	12.6	1.6%
DwC	Dutchess-Cardigan complex, rolling, rocky	>200	5.7	0.7%
DwD	Dutchess-Cardigan complex, hilly, rocky	>200	11.6	1.5%
Ff	Fluvaquents-Udifluvents complex, frequently flooded	0	0.2	0.0%
GfB	Galway-Farmington complex, undulating, rocky	>200	0.1	0.0%
GsA	Georgia silt loam, 0 to 3 percent slopes	69	1.8	0.2%
GsB	Georgia silt loam, 3 to 8 percent slopes	69	16.1	2.0%
На	Halsey mucky silt loam	8	5.6	0.7%
MnA	Massena silt loam, 0 to 3 percent slopes	38	19.6	2.5%
NwD	Nassau-Cardigan complex, hilly, very rocky	>200	14.4	1.8%
NxE	Nassau-Rock outcrop complex, steep	>200	18.5	2.3%
Pg	Pawling silt loam	54	4.5	0.6%
SkB	Stockbridge silt loam, 3 to 8 percent slopes	>200	192.0	24.4%
SkC	Stockbridge silt loam, 8 to 15 percent slopes	>200	172.3	21.9%
SkD	Stockbridge silt loam, 15 to 25 percent slopes	>200	20.6	2.6%
SmC	Stockbridge-Farmington complex, rolling, rocky	>200	14.1	1.8%

Map unit symbol	Map unit name	Rating (centimeters)	Acres in AOI	Percent of AOI
Su	Sun silt loam	0	6.8	0.9%
Ue	Udorthents, wet substratum	61	3.2	0.4%
Ur	Urban land	>200	7.6	1.0%
W	Water	>200	0.3	0.0%
Wy	Wayland silt loam	0	34.4	4.4%
Totals for Area of Interest			786.9	100.0%

# Rating Options—Depth to Water Table (Depth to Water Table)

Units of Measure: centimeters

Aggregation Method: Dominant Component Component Percent Cutoff: None Specified

Tie-break Rule: Lower Interpret Nulls as Zero: No Beginning Month: January

Ending Month: December

# References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2 053374


United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE\_DOCUMENTS/nrcs142p2\_052290.pdf

# **APPENDIX C**



**APPENDIX D** 

#### **Village of Millerton Wastewater Survey**

#### **Dear Village Resident:**

The Village of Millerton is collecting data to evaluate the wastewater conditions within the Village.

#### Why is the Village collecting data?

While most Village residents have municipal drinking water (treated drinking water is provided to a parcel through underground piping) wastewater is disposed of by individual on-site systems that use biology in the soil to treat wastewater before it reaches the groundwater aquifer. While some of these systems are working well, others have needed costly repairs and upgrades. The intent of this data collection is to:

- 1) Understand where residents have experienced problems with their systems
- 2) Understand where other conditions exist (such as high groundwater) which may impact wastewater conditions

#### What will this data be used for?

The Village has received an Engineering Planning Grant through the New York State Department of Environmental Conservation Environmental Facilities Corporation. This grant will be used to prepare a study that will:

- 1) Determine the need for wastewater improvements within the Village
- 2) Recommend needed improvements and suggest alternatives for achieving those recommendations
- 3) Provide estimated costs to implement improvements

To accomplish this we need your help in providing some important information about your wastewater conditions. Please fill out the attached form and return to the Village by:

1. Mail: Village of Millerton

PO Box 528

Millerton, NY 12546

2. Email: clerk@villageofmillerton.com

3. Drop off: Millerton Village Hall, 21 Dutchess Avenue Mon. – Fri., 9am – 4pm

If you have any questions about this survey, or need assistance filling out the forms, please contact Stephany Eisermann, Village of Millerton Clerk, (518) 789-4489.

#### Thank you for your help.

File: J:\M\M1784 Millerton\004 - Wastewater Evaluation\Documents\Survey\survey cover letter.doc

# Village of Millerton Wastewater Disposal Survey

Property Owner/Commercial Name:
Property Address:
Property is:
☐ Residential ☐ Commercial ☐ Vacant Lot - No building - No Wastewater System
Do you have any problems with your wastewater disposal system (generally septic tank and leachfield)?
□ Yes □ No
If your answer was yes, please indicate the type of problem:
☐ Must pump septic tank frequently times per year
□ Toilet/sink back-ups
☐ Leachfield failing, ponding on the surface
Other:
Do you feel there is a need for a wastewater treatment system somewhere in the Village?
□ Yes □ No
If your answer was yes, please indicate where:
Do you have any problems with water in your basement?
☐ Yes ☐ No
If your answer was yes, please indicate how often:
□ Every day
□ Whenever it rains
☐ Only in spring
Other:
Do you have a sump pump in your basement?
□ Yes □ No
If your answer was yes, please indicate how often it runs:
□ Every day
□ Whenever it rains
☐ Only in spring
Other:
Other Comments:

**APPENDIX E** 

#### PROPOSED MILLERTON SEWER DISTRICT

# BENEFIT ASSESSMENT METHODOLOGY (BU) EQUIVALENT DWELLING UNIT METHODOLOGY (EDU)

### 1 BU = 25 GPD 10 BU = 1 EDU = 1x SINGLE FAMILY RESIDENCE

## **DEVELOPED LAND** (Use the higher of either <u>LAND USE/WATER USE</u> or <u>ACREAGE</u>)

LAND USE/WATER USE	BU/EDU
RESIDENTIAL	
FIRST DWELLING UNIT	10/1
EACH ADDITIONAL DWELLING UNIT	8/1
COMMERCIAL/INSTITUTIONAL:	
FIRST 250 GPD WATER USAGE	10/1
EACH ADDITIONAL 100 GPD	4/0.4
ADDITIONAL APARTMENT DWELLING:	
FIRST 125 GPD WATER USAGE	5/0.5
EACH ADDITIONAL 125 GPD	5/0.5
ACREAGE	
FIRST 2 ACRES	10/0
EACH ADDITIONAL WHOLE ACRE	2/0
UNDEVELOPED LAND	
FIRST 2 ACRES	8/0
EACH ADDITIONAL WHOLE ACRE	2/0

Adapted from *Preliminary Engineering Report for Millerton Central Sewer District Village of Millerton and Town of North East,* by C.T. Male Associates, P.C., 2009.

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-14-304308-0000	1	0	1
7271-14-353308-0000	1	0	1
7271-14-343309-0000	3	0	3
7271-14-336299-0000	0	3	3
7271-14-352290-0000	0	3	3
7271-14-353282-0000	0	1	1
7271-14-388335-0000	1	0	1
7271-14-364304-0000	0	2	2
7271-14-413332-0000	1	0	1
7271-14-353292-0000	0	1	1
7271-14-458315-0000	1	0	1
7271-14-380297-0000	0	2	2
7271-14-403334-0000	1	0	1
7271-14-438320-0000	1	0	1
7271-14-311291-0000	0	1	1
7271-14-374300-0000	0	1	1
7271-14-386330-0000	3	2	5
7271-14-449317-0000	1	0	1
7271-14-341303-0000	0	1	1
7271-14-425324-0000	0	1	1
7271-14-348289-0000	0	2	2
7271-14-355284-0000	0	1	1
7271-14-444319-0000	1	0	1
7271-14-401327-0000	0	1	1
7271-14-389340-0000	0	1	1
7271-14-381305-0000	0	1	1
7271-14-332290-0000	0	1	1
7271-14-360287-0000	0	3	3
7271-14-410324-0000	0	1	1
7271-14-381260-0000	4	0	4
7271-14-352267-0000	0	3	3
7271-14-364277-0000	0	2	2
7271-14-487305-0000	0	1	1
7271-14-323272-0000	0	2	2
7271-14-340276-0000	0	1	1
7271-14-357260-0000	0	1	1
7271-14-351260-0000	0	2	2
7271-14-479308-0000	0	1	1
7271-14-391272-0000	1	0	1
7271-14-360274-0000	0	1	1
7271-14-327266-0000	0	2	2
7271-14-382253-0000	1	0	1
7271-14-402267-0000	0	3	3

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-14-385274-0000	0	3	3
7271-14-382277-0000	0	2	2
7271-14-364272-0000	1	1	2
7271-14-409265-0000	0	2	2
7271-14-387273-0000	0	1	1
7271-14-317278-0000	0	2	2
7271-14-346284-0000	0	2	2
7271-14-375264-0000	0	1	1
7271-14-419263-0000	1	0	1
7271-14-364326-0000	0	2	2
7271-14-498306-0000	0	1	1
7271-14-378278-0000	1	1	2
7271-14-370276-0000	0	2	2
7271-14-495298-0000	0	1	1
7271-15-504270-0000	0	1	1
7271-14-367268-0000	0	1	1
7271-14-470316-0000	1	0	1
7271-14-362253-0000	2	1	3
7271-14-483274-0000	0	1	1
7271-14-459275-0000	0	1	1
7271-14-462287-0000	0	1	1
7271-14-431301-0000	0	1	1
7271-14-408296-0000	0	1	1
7271-14-451293-0000	0	1	1
7271-14-374279-0000	0	2	2
7271-14-379254-0000	2	0	2
7271-14-437286-0000	0	2	2
7271-14-396269-0000	1	0	1
7271-18-365247-0000	0	2	2
7271-14-420293-0000	1	0	1
7271-14-448280-0000	4	2	6
7271-14-428288-0000	1	1	2
7271-14-392291-0000	0	0	0
7271-14-472278-0000	1	0	1
7271-14-395303-0000	0	2	2
7271-14-333251-0000	0	1	1
7271-14-339254-0000	0	1	1
7271-18-342244-0000	1	0	1
7271-18-351232-0000	2	0	2
7271-00-612237-0000	0	1	1
7271-00-715245-0000	0	2	2
7271-00-646248-0000	1	0	1
7271-00-622253-0000	0	1	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-00-610232-0000	0	2	2
7271-00-632250-0000	0	1	1
7271-00-682247-0000	0	2	2
7271-00-658247-0000	0	1	1
7271-00-596259-0000	0	1	1
7271-00-564263-0000	0	0	0
7271-00-578242-0000	0	1	1
7271-00-701220-0000	0	2	2
7271-00-715223-0000	0	2	2
7271-00-664222-0000	0	0	0
7271-00-623228-0000	0	1	1
7271-00-739225-0000	0	2	2
7271-00-552232-0000	0	0	0
7271-00-585220-0000	0	3	3
7271-00-534237-0000	0	4	4
7271-00-524328-0000	0	4	4
7271-19-509241-0000	0	1	1
7271-15-518268-0000	0	1	1
7271-14-397393-0000	1	0	1
7271-14-382386-0000	0	2	2
7271-14-362429-0000	2	1	3
7271-14-383402-0000	0	2	2
7271-14-361373-0000	0	3	3
7271-14-346435-0000	0	2	2
7271-14-329378-0000	0	2	2
7271-14-344380-0000	3	0	3
7271-14-337380-0000	0	3	3
7271-14-388408-0000	1	0	1
7271-14-353376-0000	1	0	1
7271-14-403400-0000	1	0	1
7271-14-328311-0000	0	2	2
7271-14-357363-0000	0	1	1
7271-14-447343-0000	2	0	2
7271-14-378338-0000	1	1	2
7271-14-471342-0000	1	0	1
7271-15-506328-0000	0	1	1
7271-14-485337-0000	0	1	1
7271-14-317310-0000	0	2	2
7271-14-407347-0000	1	2	3
7271-14-381357-0000	0	1	1
7271-14-318328-0000	0	2	2
7271-14-409354-0000	0	2	2
7271-14-335328-0000	0	1	1

Parcel No.	Residential EDUs	Commercial EDUs	<b>Total EDUs</b>
7271-14-393364-0000	0	0	0
7271-14-352366-0000	0	3	3
7271-14-411360-0000	0	1	1
7271-14-476334-0000	1	0	1
7271-14-468332-0000	1	0	1
7271-14-364367-0000	0	2	2
7271-14-331356-0000	0	2	2
7271-14-330364-0000	0	2	2
7271-14-441351-0000	1	0	1
7271-14-420347-0000	1	0	1
7271-14-390354-0000	0	1	1
7271-14-491330-0000	0	1	1
7271-14-369341-0000	0	1	1
7271-14-422357-0000	1	0	1
7271-14-431347-0000	0	1	1
7271-14-438341-0000	1	0	1
7271-14-319337-0000	2	0	2
7271-14-383367-0000	0	2	2
7271-14-319323-0000	2	0	2
7271-14-482327-0000	0	1	1
7271-14-331371-0000	0	2	2
7271-14-323346-0000	0	2	2
7271-14-355346-0000	0	1	1
7271-14-343367-0000	3	0	3
7271-14-369365-0000	0	1	1
7271-14-454341-0000	0	1	1
7271-14-361343-0000	0	3	3
7271-14-376363-0000	0	1	1
7271-14-359391-0000	0	1	1
7271-14-333435-0000	0	1	1
7271-14-347403-0000	0	2	2
7271-14-353401-0000	1	0	1
7271-14-364402-0000	0	2	2
7271-14-338427-0000	0	3	3
7271-14-366391-0000	0	2	2
7271-14-338418-0000	0	3	3
7271-14-374425-0000	0	1	1
7271-14-329384-0000	0	2	2
7271-14-364415-0000	0	2	2
7271-14-430429-0000	1	1	2
7271-14-438426-0000	1	0	1
7271-15-503336-0000	0	1	1
7271-14-495410-0000	0	1	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-14-498325-0000	0	1	1
7271-14-457421-0000	0	1	1
7271-15-505321-0000	0	1	1
7271-14-397381-0000	1	0	1
7271-14-398415-0000	1	0	1
7271-14-465420-0000	1	0	1
7271-14-462338-0000	0	1	1
7271-14-481415-0000	0	1	1
7271-14-447424-0000	2	0	2
7271-14-314426-0000	0	1	1
7271-14-466392-0000	1	0	1
7271-14-274440-0000	1	2	3
7271-14-416379-0000	1	0	1
7271-14-496385-0000	0	1	1
7271-14-443376-0000	1	0	1
7271-14-302430-0000	1	0	1
7271-14-278425-0000	1	2	3
7271-14-431407-0000	0	1	1
7271-14-425376-0000	0	1	1
7271-14-452373-0000	0	1	1
7271-14-261411-0000	0	1	1
7271-14-472390-0000	1	0	1
7271-14-452396-0000	0	1	1
7271-14-296396-0000	1	0	1
7271-14-311437-0000	0	1	1
7271-14-298380-0000	1	0	1
7271-14-301372-0000	1	0	1
7271-14-285422-0000	0	7	7
7271-14-293406-0000	0	1	1
7271-14-460371-0000	0	1	1
7271-15-500360-0000	0	1	1
7271-14-428398-0000	1	1	2
7271-14-290440-0000	0	7	7
7271-14-444398-0000	1	0	1
7271-15-507374-0000	0	1	1
7271-14-288415-0000	0	7	7
7271-14-308401-0000	1	0	1
7271-15-511380-0000	0	1	1
7271-14-478389-0000	2	0	2
7271-14-487386-0000	0	1	1
7271-14-318436-0000	0	2	2
7271-14-424390-0000	1	0	1
7271-14-471367-0000	1	0	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-14-459395-0000	0	1	1
7271-14-316374-0000	0	2	2
7271-14-312393-0000	0	1	1
7271-00-515404-0000	1	0	1
7271-00-408450-0000	1	0	1
7271-14-279466-0000	1	2	3
7271-14-299463-0000	1	0	1
7271-14-288465-0000	0	7	7
7271-14-307460-0000	1	0	1
7271-14-335457-0000	0	1	1
7271-14-320456-0000	2	0	2
7271-14-350452-0000	0	2	2
7271-14-370446-0000	0	2	2
7271-14-386442-0000	3	2	5
7271-18-461244-0000	2	0	2
7271-18-384204-0000	2	2	4
7271-14-445261-0000	2	0	2
7271-18-455219-0000	1	0	1
7271-18-390191-0000	1	0	1
7271-14-451260-0000	0	1	1
7271-14-433256-0000	1	0	1
7271-18-429240-0000	2	0	2
7271-18-448220-0000	1	0	1
7271-18-486224-0000	1	0	1
7271-18-493239-0000	1	0	1
7271-18-450209-0000	1	0	1
7271-18-445197-0000	1	0	1
7271-18-491233-0000	1	0	1
7271-18-441236-0000	1	0	1
7271-18-473241-0000	1	0	1
7271-18-495245-0000	0	1	1
7271-14-477253-0000	2	0	2
7271-14-436264-0000	2	2	4
7271-18-374232-0000	1	0	1
7271-18-458236-0000	1	0	1
7271-18-475246-0000	1	0	1
7271-18-472235-0000	1	0	1
7271-18-467222-0000	1	0	1
7271-14-464254-0000	1	0	1
7271-18-465209-0000	1	0	1
7271-18-451196-0000	1	0	1
7271-14-498253-0000	0	1	1
7271-18-409244-0000	1	0	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-18-434223-0000	4	0	4
7271-18-432199-0000	1	0	1
7271-14-446252-0000	2	0	2
7271-18-405219-0000	2	0	2
7271-18-441218-0000	3	0	3
7271-18-390238-0000	1	0	1
7271-18-439197-0000	1	0	1
7271-18-380216-0000	0	1	1
7271-18-414175-0000	1	0	1
7271-18-431248-0000	1	0	1
7271-18-418227-0000	3	0	3
7271-18-419157-0000	1	0	1
7271-18-425223-0000	1	0	1
7271-18-398164-0000	0	2	2
7271-18-423176-0000	1	0	1
7271-18-409198-0000	1	0	1
7271-18-407207-0000	1	0	1
7271-18-394229-0000	4	0	4
7271-18-421199-0000	3	0	3
7271-18-410189-0000	1	0	1
7271-18-388247-0000	2	2	4
7271-18-442176-0000	1	0	1
7271-14-406252-0000	1	2	3
7271-18-444244-0000	1	0	1
7271-18-407237-0000	2	0	2
7271-18-432176-0000	2	0	2
7271-18-433215-0000	0	0	0
7271-18-461173-0000	1	0	1
7271-18-470194-0000	1	0	1
7271-14-311262-0000	0	1	1
7271-18-311229-0000	1	0	1
7271-18-309235-0000	1	0	1
7271-14-319267-0000	2	0	2
7271-18-308219-0000	1	0	1
7271-14-315265-0000	0	2	2
7271-18-277227-0000	0	0	0
7271-14-297252-0000	1	0	1
7271-18-279173-0000	0	3	3
7271-18-328242-0000	0	1	1
7271-18-339222-0000	1	0	1
7271-18-336229-0000	2	0	2
7271-13-217424-0000	0	2	2
7271-14-296285-0000	1	0	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-14-253364-0000	0	2	2
7271-14-290303-0000	0	7	7
7271-14-285318-0000	0	7	7
7271-14-263351-0000	0	1	1
7271-14-293292-0000	0	1	1
7271-14-305275-0000	1	0	1
7271-13-245381-0000	0	2	2
7271-14-300280-0000	1	0	1
7271-13-228407-0000	0	2	2
7271-14-268277-0000	1	0	1
7271-14-277327-0000	1	2	3
7271-14-255290-0000	0	3	3
7271-14-273269-0000	1	2	3
7271-14-277259-0000	1	2	3
7271-14-258306-0000	0	1	1
7271-14-273334-0000	1	2	3
7271-13-199451-0000	0	2	2
7271-13-234295-0000	1	0	1
7271-13-177277-0000	1	0	1
7271-13-118283-0000	1	0	1
7271-13-135268-0000	1	0	1
7271-13-167277-0000	1	0	1
7271-13-122295-0000	1	0	1
7271-13-145286-0000	1	0	1
7271-13-153272-0000	1	0	1
7271-17-121238-0000	1	0	1
7271-13-164304-0000	2	0	2
7271-13-129310-0000	1	0	1
7271-13-210316-0000	0	2	2
7271-13-157422-0000	0	2	2
7271-13-239337-0000	2	0	2
7271-13-173354-0000	0	2	2
7271-13-230350-0000	1	0	1
7271-18-317180-0000	1	0	1
7271-18-316188-0000	1	0	1
7271-18-309122-0000	4	0	4
7271-18-335101-0000	1	0	1
7271-18-329194-0000	1	0	1
7271-18-295122-0000	1	0	1
7271-18-322116-0000	1	0	1
7271-18-305076-0000	1	0	1
7271-18-314168-0000	2	0	2
7271-18-295093-0000	1	0	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-18-352136-0000	1	0	1
7271-18-313147-0000	2	0	2
7271-18-324090-0000	1	0	1
7271-18-301099-0000	1	0	1
7271-18-317100-0000	0	1	1
7271-18-308088-0000	4	0	4
7271-18-312137-0000	3	0	3
7271-18-307099-0000	4	0	4
7271-18-319116-0000	1	0	1
7271-18-294074-0000	3	0	3
7271-18-315157-0000	2	0	2
7271-18-312199-0000	1	0	1
7271-18-349116-0000	0	1	1
7271-18-325126-0000	1	0	1
7271-18-283128-0000	3	0	3
7271-18-300054-0000	1	0	1
7271-18-350214-0000	2	0	2
7271-18-357179-0000	1	0	1
7271-18-353206-0000	1	0	1
7271-18-357185-0000	3	0	3
7271-18-353148-0000	1	0	1
7271-18-356172-0000	1	0	1
7271-18-355160-0000	1	0	1
7271-18-356197-0000	1	0	1
7271-18-344218-0000	1	0	1
7271-18-353141-0000	1	0	1
7271-18-356166-0000	1	0	1
7271-18-356191-0000	1	0	1
7271-00-688294-0000	0	2	2
7271-00-642269-0000	0	1	1
7271-00-599270-0000	0	1	1
7271-00-569274-0000	0	1	1
7271-00-590270-0000	0	3	3
7271-00-679269-0000	0	1	1
7271-00-548287-0000	0	4	4
7271-00-626267-0000	0	1	1
7271-00-580273-0000	0	1	1
7271-00-648272-0000	1	0	1
7271-00-612268-0000	0	1	1
7271-00-663270-0000	0	1	1
7271-15-656344-0000	1	0	1
7271-15-612306-0000	1	0	1
7271-15-635339-0000	1	0	1

Parcel No.	Residential EDUs	Commercial EDUs	Total EDUs
7271-15-622362-0000	1	0	1
7271-15-544338-0000	1	0	1
7271-15-574318-0000	1	0	1
7271-15-524324-0000	1	0	1
7271-15-632317-0000	1	0	1
7271-15-616328-0000	1	0	1
7271-15-597331-0000	1	0	1
7271-15-521312-0000	1	0	1
7271-15-593314-0000	1	0	1
7271-15-584316-0000	1	0	1
7271-15-637360-0000	1	0	1
7271-15-614317-0000	1	0	1
7271-15-533364-0000	1	0	1
7271-15-631302-0000	1	0	1
7271-15-618339-0000	1	0	1
7271-15-620350-0000	1	0	1
7271-15-563337-0000	1	0	1
7271-15-588332-0000	1	0	1
7271-15-554340-0000	1	0	1
7271-15-578335-0000	1	0	1
7271-15-600356-0000	1	0	1
7271-15-529342-0000	1	0	1
7271-15-655330-0000	1	0	1
7271-15-554364-0000	1	0	1
7271-15-547304-0000	1	0	1
7271-15-582288-0000	1	0	1
7271-15-655305-0000	1	0	1
7271-15-577360-0000	1	0	1
7271-15-673301-0000	1	0	1
7271-15-612284-0000	1	0	1
7271-15-651283-0000	1	0	1
7271-15-549314-0000	1	0	1
7271-15-572294-0000	1	0	1
7271-15-552323-0000	1	0	1
7271-15-592287-0000	1	0	1
7271-15-535374-0000	1	0	1
7271-15-518292-0000	1	0	1
7271-15-627282-0000	1	0	1
7271-15-643283-0000	1	0	1
7271-15-602285-0000	1	0	1
7271-15-639380-0000	1	0	1
7271-15-626384-0000	1	0	1
7271-15-606390-0000	1	0	1

Parcel No.	Residential EDUs	sidential EDUs Commercial EDUs		
7271-15-603371-0000	1	0	1	
7271-15-618388-0000	1	0	1	
7271-18-498217-0000	0	2	2	
7271-18-363242-0000	0	0	0	

**APPENDIX F** 

## Ovivo microBLOX Membrane Bioreactor Treatment System



### $microBLOX^{TM}$


#### RTO (Ready-to-Operate) Enviroquip® MBR Systems

#### **Key Features & Benefits**

- Complete, Ready-to-Operate MBR System
- High solids operation
- Gravity filtration
- Simple, single-stage process
- Few moving parts
- Small footprint
- Easily located, deployable

#### How we create value

- Guaranteed to meet most stringent nutrient limits
- 25 % 50 % lower total installed cost
- > 5x less waste solids hauling
- 12 week delivery (2 weeks for submittals)
- Highest reuse quality effluent
- All replacement parts in stock (72hr delivery)
- Comprehensive service plans available



#### microBLOX™

microBLOX<sup>™</sup> Membrane Bioreactor (MBR) Systems are fully functional solutions to wastewater treatment problems and are ideally suited for a wide range of applications, including, but not limited to: housing developments, state parks, rest areas, isolated communities, military camps, shopping malls, golf courses, resorts, casinos, sewer mining (scalping), some industrial and more.

microBLOX™ technology was designed and engineered to be extremely simple to operate and optimize. This single-stage process uses one set of blowers to provide mixing, air scouring and process oxygen. For higher strength waste, concentrated oxygen can be efficiently added to the process on an as needed basis. Each System can be guaranteed to meet the most stringent nutrient limits and online monitoring is available for ammonia, nitrates and phosphorus in the effluent.

Backed by one of the largest water companies in the world, Ovivo, microBLOX™ Systems are built on the experience of Enviroquip® MBR Systems and our over 130 operating plants in the US and 330 plants worldwide.



62,500 GPD microBLOX plant is easily installed and ready-to-operate

#### Why microBLOX™?

- Lowest Total Cost of Ownership
   Total installed and operating costs can be lower than all other comparable technologies.
- The Most Space Efficient
   At higher flow and/or pollutant loading, microBLOX™ can treat more waste than any other technology in a given footprint (maximum unit capacity up to 62,500 gpd).
- Most Reliable
   Considered Best Available Technology
   (BAT), microBLOX™ Systems are
   guaranteed to meet the most stringent
   nutrient limits and to produce the highest,
   reuse quality effluent over a broad range
   of operating conditions.
- Single Source Responsibility

  There is only one number to call for technical support, parts or service (with parts delivery in 72 hrs).
- Built for Operators by Operators
   All components are accessible; no electrical components are located in mixed liquor. Full remote monitoring capabilities using easily configurable phone application.

#### microBLOX™ Range

#### **Standard Systems**

Each microBLOX™ comes equipped as a fully functioning, ready-to-operate MBR system, including:


- Fine screening (1)
- Integrated, tested process tankage (2)
- Equalization Zone (3)
- WAS Zone (4)
- Submerged membrane units by KUBOTA®(5)
- Pre-wired, factory tested equipment (6)
- Remote monitoring controls

#### **Options**

Several options are available to tailor the capabilities of each microBLOX™ System to meet specific project needs including:

- Online nutrient monitoring
- Winterization packages
- Chemical dosing (add. carbon, pH, coagulants)
- Permeate pumping (7)

Treated Effluent Quality					
Parameters	Typical Values	Achievable			
		Values			
BOD <sub>5</sub>	< 2.0 mg/l	Non Detectable			
Total Nitrogen (TN)	< 10.0 mg/l	< 3.0 mg/l			
Ammonia (NH3)	< 1.0 mg/l	< 0.3 mg/l			
Phosphorus (TP)	< 1.0 mg/l	< 0.03 mg/l			
Fecal Coliform	< 2.2 CFU/100 ml	Non Detectable			
TSS	< 2.0 mg/l	Non Detectable			




#### The Process


A microBLOX™ System can be configured to run in flow-through or batch modes depending on site conditions and treatment goals. As shown above, influent (raw wastewater) is screened before filling a dedicated Equalization Zone. Equalized wastewater is then pumped into a single-stage MBR process designed to operate over a range of dissolved oxygen conditions to achieve nutrient removal targets. For smaller, municipal applications, process oxygen is delivered exclusively by membrane aeration. Biologically treated wastewater is then gravity filtered (or pumped) using KUBOTA membranes to produce reuse quality effluent with only one tank; there is no recycle, no mechanical mixing and no fine bubble diffusers.

For higher strength wastes (e.g. light industrial or commercial), or to increase hydraulic throughput, options are available using various oxygen concentrator technologies. Oxygen makeup and delivery systems are completely skid mounted and easy to setup requiring only a few field connections. The onboard controls system is equipped with programming necessary for seamless integration.

Unlike other MBR Systems, a microBLOX™ System integrates solids thickening into the biological process to keep waste solids handling costs down and to improve overall reliability. As necessary, partially digested, thickened solids are wasted to an integral Waste Activated Sludge (WAS) Storage Zone. WAS can be stored at 2% - 3% solids, which can reduce hauling frequencies by more than 5 times that of conventional (package) technologies using sedimentation for solid/liquid separation.







PART NUMBER TOTAL WEIGHT

45365.975

821.434

929.319

55.645

283.310

481.337

SALES M-V3 65K GPD-0

SEE BOM SEE BOM

48785.8 lbmass

SHEET REV

V3 65K GPD-1-300


234-688

234-659

234-660

BY OTHERS

234-521




NOT FOR CONSTRUCTION
\*FINAL DESIGN MAY VARY\*

THIS DRAWING CONTAINS CONFIDENTIAL PROPRIETARY INFORMATION OF OVIVO, AND ITS
AFFLIATES, AND IS NOT TO BE DISCLOSED NOR TO BE USED EXCEPT FOR EVALUATING
PROPOSALS OF OVIVO OR INSTALLING, OPERATING OR ANANTAINING OVIVO EQUIPMENT.
UNLESS OTHERWISE AUTHORIZED IN WRITING BY OVIVO. UNCONTROLLED COPY IF PRINTED

DO NOT SCALE PRINTS
WORKMANSHIP STANDAMO ESSOOL APPLIES
NO.

SALES M-V3 65K
GPD-01



<u>VIEW A-A</u> (GRATING TURNED OFF FOR CLARITY)

\*FINAL DESIGN MAY VARY\*

THIS DRAWING CONTAINS CONFIDENTIAL PROPRIETARY INFORMATION OF OVIVO, AND ITS AFFILIATES, AND IS NOT TO BE DISCLOSED NOR TO BE USED EXCEPT FOR EVALUATING PROPOSALS OF OVIVOUR OB INSTALING, OPERATING DAMINATIANING OVIVOUR OBJURNENT, UNLESS OTHERWISE AUTHORIZED IN WRITING BY OVIVOU UNCONTROLLED COPY IF PRINTED

DO NOT SCALE PRINTS


DO NOT SCALE PRINTS


WORKMANDED STANDAND ESDOOL APPLIES

NO.

GPD-01

3 OF 6






VIEW B-B

VIEW C-C

NOT FOR CONSTRUCTION
\*FINAL DESIGN MAY VARY\*

AFFILIATES, AND IS NOT TO BE DI PROPOSALS OF OVIVO OR INSTAL	SCLOSED NOR TO B LING, OPERATING (	ARY INFORMATION OF OVIVO, AND ITS IE USED EXCEPT FOR EVALUATING OR MAINTAINING OVIVO EQUIPMENT. VIVO. UNCONTROLLED COPY IF PRINTED		OVIVO Worldwide Experts in Water Th	eatment	
D	<b>a</b> —	DO NOT SCALE PRINTS	DWG.	SALES M-V3 65K	SHEET	R
© 2018 OVIVO. ALL RIGHTS RESERVED.		WORKMANSHIP STANDARD ES0001 APPLIES	NO.	GPD-01	4 OF 6	1




NOT FOR CONSTRUCTION
\*FINAL DESIGN MAY VARY\*

THIS DRAWING CONTAINS CONFIDENTIAL PROPRIETARY INFORMATION OF OVIVO, AND ITS
AFFILIATES, AND IS NOT TO BE DISCLOSED NOR TO BE USED EXCEPT FOR EVALUATING
PROPOSALS OF DVIVO OR INSTALLING, OPERATING OR MAINTAINING OVIVO CUJUMENT.
UNLESS OTHERWISE AUTHORIZED IN WRITING BY OVIVO. UNCONTROLLED COPY IF PRINTED

DO NOT SCALE PRINTS
WORMMASHIP STANDARD ESCOOL APPLIES
NO.

SALES M-V3 65K
GPD-01

SHEET REV



#### **Orenco AdvanTex System - Example Installations in New York**

- Hyde Park 120 Service Connections 30,000 gpd Surface Return
- Hillsdale 73 Service Connections 50,000 gpd Subsurface Return
- East Schodack 23 Service Connections 7,500 gpd Surface Return
- Schodack Landing 75 Service Connections 20,000 gpd Surface Return
- Bethlehem 23 Service Connections 7,500 gpd Surface Return
- Kensington Woods 160 Service Connections 35,500 gpd Surface Return

## Orenco AdvanTex AX-Max Biofiltration Treatment System

## AdvanTex® Treatment Systems

# AX-Max

Manufactured by Orenco Systems®, Inc.



## **Decentralized Wastewater Treatment for Commercial Properties and Communities**



814 Airway Avenue, Sutherlin, Oregon, USA 97479 Toll-Free: 800-348-9843 • +1-541-459-4449 • www.orenco.com

#### **Applications:**

- Municipal systems
- Subdivisions, apartments
- Golf course developments, resorts
- Manufactured home parks
- Parks, RV parks, campgrounds
- Schools, churches, businesses
- Rest areas, truck stops

## AdvanTex® AX-Max™ Treatment System

#### Reliable, Energy-Efficient Wastewater Treatment



The Yakama Nations Housing Authority in Washington state added five AdvanTex® AX-Max units (background) to its ten AdvanTex AX-100 units, increasing the capacity of its wastewater system by 50%. Photo courtesy of Fextex Systems, Inc.

## **Everywhere!**


For more than 15 years, Orenco's AdvanTex® Treatment Systems have been providing reliable, energy-efficient wastewater treatment inside and outside the urban core. AdvanTex textile filter technology has been winning awards and coming out on top in field trials and demo projects, all over the world.

Orenco's newest product in the AdvanTex line is the AX-Max™: a completely-integrated, fully-plumbed, and compact wastewater treatment plant that's ideal for commercial properties and communities. It's also ideal for projects with strict discharge limits, limited budgets, and part-time operators.

#### A Sustainable Solution for Wastewater Treatment



## AdvanTex® AX-Max™ Treatment System



The AX-Max is pre-plumbed and easy to install, so AX-Max projects can meet the tightest deadlines. The entire system — including treatment, recirculation, and discharge — is built inside an insulated fiberglass tank that ranges from 14-42 feet (4.3-12.8 m) in length. AX-Max units can be installed above-ground — for maximum versatility in temporary or variable-flow situations — or in-ground. They can also be installed individually or in multi-tank arrays, treating up to 1 MGD 73-800 m<sup>3</sup>/day).

## For Every Climate and Condition

AX-Max systems provide excellent treatment anywhere, and they have been installed all over the world. For example, AX-Max systems have been installed at Malibu's famous beach parks and New Zealand's Glendhu Bay campground. Several more were installed in Soyo, Africa, to serve a new hospital and school. Other AX-Max systems have been installed on top of Alaska's frozen tundra and St. Lucia's volcanic rock. Still more have been installed in mining camps from Alberta to Texas and, in the Midwest, at a U.S. Department of Defense demo site.



#### **Benefits**

- Containerized, fully-plumbed
- Capable of meeting stringent permit limits
  - ~ Reuse-quality effluent
  - ~ Significant reductions in ammonia, total nitrogen
- Compact and versatile
- Above-ground or in-ground installation
- Easy to set
- Simple to operate
- Low energy usage: <2 kWh per 1000 treated gal. (<2 kWh per 3.785 m³)\*</li>
  - \* When treating domestic waste



#### **Textile Treatment Media**

The treatment medium is a uniform, engineered textile. AdvanTex textile is easy to clean and allows loading rates as high as 50 gpd/ft² (2000 L/day/m²) with primary-treated influent.



#### **Effluent Distribution**

High-quality, low-horsepower pumps micro-dose the treatment media at regular intervals, and proprietary spin nozzles efficiently distribute the effluent, optimizing treatment.



#### **Telemetry Controls**

Orenco's telemetry-enabled control panels use a dedicated phone line or ethernet connection, ensuring 24/7 monitoring and real-time remote control

## **AdvanTex® AX-Max™** Treatment System

### **Carefully Engineered**by Orenco

Orenco Systems has been researching, designing, manufacturing, and selling leading-edge products for small-scale wastewater treatment systems since 1981. The company has grown to become an industry leader, with about 300 employees and 300 points of distribution in North America, Australasia, Europe, Africa, and Southwest Asia. Our systems have been installed in more than 70 countries around the world.

Orenco maintains an environmental lab and employs dozens of civil, electrical, mechanical, and manufacturing engineers, as well as wastewater treatment system operators. Orenco's technologies are based on sound scientific principles of chemistry, biology, mechanical structure, and hydraulics. As a result, our research appears in numerous publications and our engineers are regularly asked to give workshops and trainings.





814 Airway Avenue Sutherlin, OR 97479 USA

T: 800-348-9843

T: 541-459-4449

F: 541-459-2884

www.orenco.com

ABR-ATX-MAX-1 Rev. 1.5, © 03/17 Orenco Systems®, Inc.

## **Project Summary**



#### Point Dume State Beach and Preserve, Southern California

In spring, 2011, Los Angeles County needed to quickly upgrade restrooms at Malibu's Point Dume State Beach in time for the long — and busy — Memorial Day weekend.

The county's engineer specified three AX-Max units, one for each restroom, and all three were installed in a matter of days. The small footprint of this configuration saved the county valuable space for visitor parking. After disinfection, the treated effluent is dispersed right into the sand. Point Dume is part of a large-scale upgrade of L.A. County beach parks, virtually all of which include AdvanTex Treatment Systems of various sizes and configurations.



#### **Fully Supported by Orenco**

AdvanTex Treatment Systems are part of a comprehensive program that includes ...

- · Designer, installer, and operator training
- Design assistance, technical specifications, and plan reviews
- Installation and operation manuals
- · Lifetime technical support

Distributed by:

## **AdvanTex® AX-Max Treatment Systems**

#### **Applications**

Orenco's AdvanTex® AX-Max is a complete, fully-plumbed, AdvanTex Wastewater Treatment Plant for residential, commercial, municipal, and mobile applications with medium-to-large-flows and permits requiring secondary treatment or better. It can be used as a stand-alone unit or in multi-unit arrays under adverse conditions in a wide range of environments. The AX-Max is ideal for:

- · Small sites and poor soils
- At-grade or above-grade installations
- Mobile and temporary installations
- Disaster response sanitation
- Remote locations
- · Extreme hot or cold climates

#### General


The AX-Max is a modular system that can be preceded by primary treatment or configured to incorporate primary, secondary, and tertiary wastewater treatment before reuse or dispersal.


The heart of the AX-Max system is the AdvanTex Recirculating Treatment Tank, a sturdy, watertight, corrosion-proof fiberglass tank that includes the same dependable, textile treatment media found in all AdvanTex products.

#### **Standard Models**


AX-MAX100-14, AX-MAX150-21, AX-MAX200-28, AX-MAX250-35, AX-MAX300-42 (Standard models without pump systems.)


AX-MAX075-14, AX-MAX125-21, AX-MAX175-28, AX-MAX225-35, AX-MAX275-42 (Standard models with pump systems.)





AdvanTex AX-MAX275-42, side view





AdvanTex AX-MAX, end view (all models)

### **Specifications**

Nominal Dimensions*					
Model	AX-MAX100-14	AX-MAX150-21	AX-MAX200-28	AX-MAX250-35	AX-MAX300-42
A, ft (m)	variable	variable	variable	variable	variable
B, ft (m)	14.0 (4.2)	21.0 (6.4)	28.0 (8.5)	35.0 (10.7)	42.0 (12.8)
C, ft (m)	7.6 (2.3)	7.6 (2.3)	7.6 (2.3)	7.6 (2.3)	7.6 (2.3)
D, ft (m)	7.5 (2.3)	7.5 (2.3)	7.5 (2.3)	7.5 (2.3)	7.5 (2.3)
Footprint, ft <sup>2</sup> (m <sup>2</sup> )	112.0 (10.4)	168.0 (15.6)	224.0 (20.8)	280.0 (26.0)	336.0 (31.2)
Model	AX-MAX075-14	AX-MAX125-21	AX-MAX175-28	AX-MAX225-35	AX-MAX275-42
A, ft (m)	5.7 (1.7)	5.7 (1.7)	5.7 (1.7)	5.7 (1.7)	5.7 (1.7)
B, ft (m)	14.0 (4.2)	21.0 (6.4)	28.0 (8.5)	35.0 (10.7)	42.0 (12.8)
C, ft (m)	7.6 (2.3)	7.6 (2.3)	7.6 (2.3)	7.6 (2.3)	7.6 (2.3)
D, ft (m)	7.5 (2.3)	7.5 (2.3)	7.5 (2.3)	7.5 (2.3)	7.5 (2.3)
Footprint, ft <sup>2</sup> (m <sup>2</sup> )	112.0 (10.4)	168.0 (15.6)	224.0 (20.8)	280.0 (26.0)	336.0 (31.2)

<sup>\*</sup>See AdvanTex® AX-Max Treatment System drawings for exact dimensions and specific treatment configurations.

**APPENDIX G** 

#### NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where Base Flood Elevati To obtain more detailed information in areas where Base Flood Elevations (BFEs) allot floodways have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood insurance Study (FIS) report that accompanies its FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These DFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood slevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of Coastal Base Flood Elevations shown on this map apply only landward of 00° North American Vertical Datum of 1988 (AND 88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stitheater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stitheater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the relevations shown on this FIRM.

Soundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on indigation considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance

Certain areas not in Special Flood Hazard Areas may be protected by flood control structures. Refer to Section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this

The projection used in the preparation of this map was Universal Transverse Memoster (UTM) core i.8. The horizontal datum was NAD 33, GR580 spheroid. Offenemens in datum, spheroid, projections of UTM zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the

Flood elevations on this map are referenced to the North American Vertical Datum of 1988. These flood elevations must be compared to structure and ground elevations referenced to the same vertical datum. For information regarding conversion between the National Geodetic Vertical Datum of 1989, with the National Geodetic Survey.

NGS Information Services NDAA, NJNGS12 National Geordein Survey SSMC-3, #0202 1315 East-West Highway Giver Spring, Maryland 20910-3182 (301) 713-3242

To obtain current elevation, description, and/or location information for bench marks shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242, or visit its website at http://www.ngs.noaa.gov.

Base map information shown on this FIRM was derived from digital orthophotography provided by the New York State Office of Cyber Security & Crical Infrastructure Coordination. This information was produced as one-foot and two-foot resolution natural color ortholmagery from photography dated April 2000.

Based on updated topographic information, this map refeats more detailed and up-to-date stream channel configurations and floodplain delineations than those shown on the previous PRM for this jurisdiction. As a result, the Flood Profiles and Floodway Data tables in the Flood insurance Study Report (which confars authoristive hydradic data) may reflect stream channel distances that differ from what is shown on this map. Also, the road to floodplain relationships for unrevised streams may differ from what is shown on previous maps.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed Map Index for an overview map of the county showing the layout of map panels; community map repository addresses and a Listing of Communities table containing National Flood insurance Program dates for each community as well as a listing of the panels on which each

For information on available products associated with this FIRM, visit the Map Service Center (MSC) website at <a href="http://msc.ferna.gov">http://msc.ferna.gov</a>. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the MSC website


If you have questions about this map, how to order products or the National Flood Insurance Program in general, please call the FEMA Map Information exchange (FMIX) at 1.877-FEMA MAP (1.877-336-2527) or visit the FEMA website at <a href="https://www.fema.gov/business/nfig">https://www.fema.gov/business/nfig</a>.







This digital FIRM was produced through a unique cooperative partnership bet New York Date Department of Environmental Conservation (NYSDEC) and FEMA. As particle of the effort, NYSDEC has joined in a Cooperative Technical Partnership agreement is produce and maintain FEMA's digital FIRM.



#### LEGEND

11/11

ZONE X

SPECIAL FLOOD HAZARD AREAS SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

The 1% annual flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equated or exceeded in any given year. The Special Rocal Issuard Area is thus area subject to Roching by the 1½ annual chance flood. Have of Special Flood Hazer of Loude Rocal Flood Hazer of Louder Flood Hazer of Special Flood Hazer flood.

Zones A. ME. All. ADL RR. ASP, V. and VE. The Base Flood Elevation is the water-surface elevation of the Normal Internet flood.

ZONE A No Base Flood Elevations determined.

ZONE AE Base Flood Elevations determined.

Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood

Special Flood Hazard Area formerly protected from the 1% annual chance flood by a flood control system that was subsequently decertified. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual relative or greater flood.

ZONE A99 Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations

Coastal flood zone with velocity hazard (wive action); no base Flood Elevations determined.

Coastal flood zone with velocity hazard (wave action); Base Flood

The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases

OTHER FLOOD AREAS Areas of 0.2% annual chance flood; areas of 1% annual chance flood with

Areas determined to be outside the 0.2% annual chance floodplain.

Areas in which flood hazants are undetermined, but possible. COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS

OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

1% annual chance floodplain boundary 0.2% annual chance floodplain boundary

\_\_\_\_\_ Zone D boundary CBRS and OPA boundary

Base Flood Elevation line and value; elevation in feet\*

Base Flood Elevation value where uniform within zone; dievation in feet\*

(A)—(A) Cross section line

Limited detail cross section line ®-----®

600000 FT

• M1.6

87"07'45", 32"22'30" Geographic coordinates referenced to the North American Datum of 1983 (NAD 83), Western Hemisphere

1000-meter Universal Transverse Mercator grid values, Jone 18

5000-foot grid values: New York State Plane coordinate system, East zone (FIPSZONE 3101), Transverse Mercator


DX5510 ... Bench mark (see explanation in Notes to Users section of this FIRM panel)

Siver Mile

For community map revision history prior to countywide mapping, refer to the Community Map History table located in the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your Insurance agent or call the National Flood Insurance Program at 1-800-638-6520.







#### PANEL 0209E FIRM

#### FLOOD INSURANCE RATE MAP

for DUTCHESS COUNTY, NEW YORK (ALL JURISDICTIONS)

CONTAINS: COMMUNITY

NUMBER MILLERTON, VILLAGE 360220

NORTHEAST, TOWN OF 361340

#### PANEL 209 OF 602 MAP SUFFIX: E



MAP NUMBER 36027C0209E EFFECTIVE DATE MAY 2, 2012

Federal Emergency Management Agency

**APPENDIX H** 



#### M1784-004 Wastwater Evlauation Mill Road

Test Pit No. Page No. File No. Checked By:

Millerton, New York 12546

&B Rep.	. R. Morrison	Contractor	Village of Mi	llerton DPW		Date		10/1	2/18
		Operator	Cole Lawren	ce		Ground Ele	ev.	Unk	own
Veather		Make		Model		Time Start	ed	9:00	MA C
		Capacity		Reach	ft.	Time Com	pleted	2:0	O PM
Depth		Soil Descrip	otion		Sample	PID		Boulder	
					No.	Reading	Excav.	Count/	Note
_ 0						(ppm)	Effort	Class	No.
_ 0	0" - 2" Organic Debris				N/A		М		
	2" - 94" Silt Loam, Brown-Grey	color, Gravel 10	-15%, Cobble	s 5%			IVI		
1'	Roots to a depth of 37"						N 4		
							M		
2'					1				

2" - 94" Silt Loam, Brown-Grey color, Gravel 10-15%, Cobbles 5%			
Roots to a depth of 37		M	
2'			
3' —			
4'—			
5'—			
6'—			
7'—			
8'—			
9'—			
10'			
11'			
12'			
13'-			
14'—			
15'—			
16'			
Notes:			

- 1. Inconsistent lenses of redox features found typically around cobles. Redox features were as high as 38" but very sparatic in formation
- 2. Purple maganese marks found in soil matrix
- 3. Bedrock not encountered
- 4. No topsoil noted.
- 5. Water weeping in test pit while digging and was left open to see how high ground water would stabilize at.

Test Pit Plan	Boulder Class Letter Size Range	Proportions Used		Abbreviations	GROUNDWATER ( X ) Encountered ( ) Not Encountered		
	Designation Classification A 6" - 17"	TRACE (TR.)	0 - 10%	F = Fine M = Medium C = Coarse			
	B 18" - 36" C 36" +	LITTLE (LI.)	10 - 20%	V = Very F/M = Fine to medium	Elapsed Time to	Depth to Ground-	
	Excavation Effort EEasy	SOME (SO.)	20 - 35%	F/C = Fine to coarse GR = Gray BN = Brown	Reading (Hours)	water	
Volume =cu. yd.	MModerate DDifficult	AND	35 - 50%	YEL = Yellow	4	47"	



#### M1784-004 Wastwater Evlauation Mill Road Millerton, New York 12546

Test Pit No.	TP-2
Page No.	2 of 6
File No.	
Checked By:	

( X ) Encountered

T&B Rep. R. Morrison  Weather		Son Contractor Village Operator Cole Make		illerton DPW nce Model		Date Ground Ele Time Starte	Unl	10/12/18 Unkown 9:00 AM		
		Capacity		Reach	ft.	Time Completed			2:00 PM	
Depth		Soil Descrip	otion		Sample No.	Reading	Excav		Note	
0	0" - 1" Organic Del	orio.			N/A	(ppm)	Effort	t Class	No.	
	1" - 95" Silt Loam, Roots to a depth of	Brown-Grey color, Gravel 5-1	10%, Cobbles	5 5%	IN/A		M			
2'	·						M			
— 3'—										
4'										
5'										
— 6' — — 7' —										
— 8' —										
<u> </u>										
10'										
11'										
— 12' —										
13'										
— 14' — — 15' —										
— 16' —										
<ol> <li>Purple r</li> <li>Bedrock</li> <li>No tops</li> </ol>	maganese marks foun k not encountered oil layer noted.	features found typically around co d in soil matrixs as not left open to equalize.	obles. Redox fea	atures were as high	as 20" bu	t very sparatic	in forma	ntion.		
	Test Pit Plan	<u>Boulder Class</u> Letter Size Range		ortions Used	F = Fine	Abbreviations		GROUNDWATER X ) Encountere	d	

Boulder Class
Size Range
on Classification F = FineDesignation M = Medium ( ) Not Encountered TRACE (TR.) M = Medium
C = Coarse
V = Very
F/M = Fine to medium
F/C = Fine to coarse
GR = Gray
BN = Brown
VEL = Vellow 6" - 17" 18" - 36" 36" + 0 - 10% A B C Elapsed Depth LITTLE (LI.) 10 - 20% Time to Reading Ground-Excavation Effort SOME (SO.) 20 - 35% (Hours) water E----Easy M-----Moderate YEL = YellowVolume = cu. yd. AND 35 - 50% 51" D-----Difficult

J:\M\M1784 Millerton\004 - Wastewater Evaluation\Data\Soils\Testing\[2018-10-12 Deep Test Log.xls]TP-2



#### M1784-004 Wastwater Evlauation Mill Road Millerton, New York 12546

Test Pit No.
Page No.
File No.
Checked By:

Time Completed

ft.

TP-3

3 of 6

2:00 PM

T&B Rep.	R. Morrison	Contractor	Village of Millerton DPW	Date	10/12/18
		Operator	Cole Lawrence	Ground Elev.	Unkown
Weather		Make	Model	Time Started	9:00 AM

Reach

Capacity

Dank	Call Decembring	Comercia	DID.		I Davidale :: I	
Depth	Soil Description	Sample	PID	F	Boulder	N1 4 -
		No.	Reading	Excav.	Count/	Note
0			(ppm)	Effort	Class	No.
	0" - 2" Organic Debris	N/A		M		
	2" - 96" Silt Loam, Brown-Grey color, Gravel 10-15%, Cobbles 5%			IVI		
1'	Roots to a depth of 20"					
				M		
— 2' —						
<b>—</b> 3' <b>—</b>	4					
L 1' -						
<b>-</b>						
— 5' —						
6'						
<del></del>						
— 8' —						
<u> </u>						
10'						
11'						
— 12' —						
— 13' —	4					
— 14' —						
17						
151						
— 15' —						
16'	1					
I						

#### Notes:

- 1. Inconsistent lenses of redox features found typically around cobles. Redox features were as high as 51" but very sparatic in formation.
- 2. Bedrock not encountered
- 3. No topsoil layer noted.
- 4. No groundwater encountered.

Test Pit Plan		Boulde	er Class	Proportions	ı	Abbreviations	GROUNDWA	TER	
		Letter Size Range Designation Classification A 6" - 17" TRAC		Ûsed TRACE (TR.)	0 - 10%	F = Fine M = Medium	( X ) Encountered ( ) Not Encountered		
	B C	B C	6 - 17 18" - 36" 36" +	LITTLE (LI.)	10 - 20%	C = Coarse V = Very F/M = Fine to medium	Elapsed Time to Reading	Depth to Ground-	
			tion Effort Easy	SOME (SO.)	20 - 35%	F/C = Fine to coarse GR = Gray BN = Brown	(Hours)	water	
Volume =cu.	. yd.		Moderate Difficult	AND	35 - 50%	YEL = Yellow	N/A	N/A	
		D	Dimcuit						



#### M1784-004 Wastwater Evlauation Mill Road Millerton, New York 12546

Test Pit No.	TP-4
Page No.	4 of 6
File No.	
Checked By:	

T&B Rep. R. Morrison Weather		Operator Make		del		Date Ground Ele Time Starte	ed		10/12 Unko 9:00	own AM
		Capacity		ach	ft.	Time Comp	leted		2:00	PM
Depth		Soil Descrip	tion		Sample No.	PID Reading (ppm)	Excav. Effort		ınt/	Note No.
		n Loam, Gravel 0-5% , Brown-Grey color, Gravel 5-	100/ Cabbles E		N/A	(66)	M	0.0		
- <sub>1'</sub>	16 - 60 SIII LOAIII	i, brown-Grey color, Graver 5-	10%, Cobbles 5:	<b>/</b> 0			M		$\overline{}$	
2'-									$\dashv$	
3'-									$\dashv$	
— 4' —									$\dashv$	
5'										
- 6'-										
8'—										
9'—										
10'									$\dashv$	
— <sub>11'</sub> —									$\dashv$	
— 12' —									+	
— 13' —									$\dashv$	
— 14' —									$\dashv$	
— 15' —									$\dashv$	
<del></del>									$\perp$	
<ol> <li>Bedrock</li> <li>No topso</li> </ol>	tent lenses of redox f not encountered oil layer noted. ndwater encountered	eatures found typically around col	oles. Redox feature	s were as high	as 23" but	very sparatio	: in format	tion		
Т	est Pit Plan	<u>Boulder Class</u> Letter Size Range	Proportions Used	1	A F = Fine	bbreviations		ROUNDWA		
Г		Designation Classification  A 6" - 17"  B 18" - 36"  C 36" +	TRACE (TR.)	0 - 10%	M = Med C = Coar	se	(	) Not End	counter	ed Depth
L			LITTLE (LI.)	10 - 20%	F/C = Fir	ne to medium ne to coarse		e to ding	te G	o Ground-
Volume =	cu. yd.	<u>Excavation Effort</u> EEasy MModerate	SOME (SO.) AND	20 - 35% 35 - 50%	GR = Gra BN = Bro YEL = Ye	wn	-	urs) N/A	T *	vater N/A
	ca. ya.	DDifficult	, , , ,	35 - 3070					二	



#### M1784-004 Wastwater Evlauation Mill Road Millerton, New York 12546

Test Pit No.	TP-5
Page No.	5 of 6
File No.	
Checked By:	

T&B Rep. R. Morrison  Weather		Operator Make		odel	<u></u>	Date Ground Ele Time Starte	ed		10/12/18 Unkown 9:00 AM		
		Capacity	Re	each	ft.	Time Comp	oleted		2:00	PM	
Depth		Soil Descrip	tion		Sample No.	PID Reading	Excav. Effort		ınt/	Note No.	
		n Loam, Gravel 0-5%			N/A	(ppm)	M	Cla	55	INO.	
	25" - 92" Silt Loam Root Depth noted a	ı, Brown-Grey color, Gravel 5- at 24"	10%, Cobbles 5	%			M		+		
_ 2' <del></del>							IVI		+		
— 3'—									+		
— 4'—									$\dashv$		
5'									$\perp$		
— <sub>6'</sub> —											
_ 7'											
, 											
8'—											
9'											
10'											
11'									$\dashv$		
12'									+		
13'									+		
— 14' —									+		
— 15' —									$\dashv$		
— 16' —									$\dashv$		
<ol> <li>Bedrock</li> <li>No topso</li> </ol>	tent lenses of redox f not encountered oil layer noted. ndwater encountered	eatures found typically around col	oles. Redox feature	es were as high	as 24" but	very sparatio	in forma	tion			
Т	Test Pit Plan	<u>Boulder Class</u> Letter Size Range	Proportion Used	ns	A F = Fine	bbreviations		ROUNDWA			
Γ		Designation Classification  A 6" - 17"  B 18" - 36"  C 36" +	TRACE (TR.)	0 - 10%	M = Med C = Coar	se	(	) Not Enc	ountere	ed epth	
L	1	C 36" +	LITTLE (LI.)  SOME (SO.)	10 - 20% 20 - 35%	F/C = Fir	ne to medium ne to coarse	Tim Rea	e to ding urs)	to G		
Volume =	cu. yd.	EEasy MModerate DDifficult	AND	35 - 50%	GR = Gra BN = Bro YEL = Ye	wn		N/A		N/A	
		2 Dimont							<u> </u>		



#### M1784-004 Wastwater Evlauation Mill Road Millerton, New York 12546


Test Pit No.	TP-6
Page No.	6 of 6
File No.	
Checked By:	

T&B Rep. R. Morrison  Weather		Contractor Operator	Village of Millerto Cole Lawrence	on DPW		Date Ground Ele	V.		10/12/18 Unkown		
		Make	Mod	lel		Time Starte			9:00 AN		
		Capacity	Rea		ft.	Time Comp			2:00 PN		
D		Call Danada				l DID I		InI			
Depth		Soil Descrip	otion		Sample No.	PID Reading (ppm)	Excav. Effort	Boul Cou Cla	nt/ N	lote No.	
		n Loam, Gravel 0-5% , Brown-Grey color, gravel 10	2 150/ pobbles 50	/	N/A	(ррпт)	M	Cia	33 1	<b>V</b> O.	
- <sub>1'</sub>	- 94 SIII LOam	, втоwn-Grey color, graver то	J-15%, CODDIES 57	o .			M				
— 3'—											
— 4' <del>—</del>											
5'											
<u> </u>											
7' —											
8'											
9'											
10'											
11'											
— 12' —											
13'											
— 14' —											
15'											
<del></del>									-		
Notes:											
<ol> <li>Inconsistent</li> <li>Purple magr</li> <li>Bedrock not</li> </ol>	nanes marks four encountered	eatures found typically around co nd in siil matrixs s not left open to equalize.	bles. Redox features	were as high	as 38" but	very sparatio	in formatio	on			
Test	Pit Plan	Boulder Class	December		_		GR	OUNDWA	TFR	-	
		Letter Size Range Designation Classification	Proportions Used TRACE (TR.)	0 - 10%	F = Fine M = Med		( X	) Encour ) Not Enc	ntered		
		A 6" - 17" B 18" - 36" C 36" +	LITTLE (LI.)	10 - 20%	C = Coar V = Very		Elaps		Dept	:h	
		<u>Excavation Effort</u> EEasy	SOME (SO.)	20 - 35%			Time Readi (Hour	ng	to Grou wate		
Volume =	cu. yd.	MModerate DDifficult	AND	35 - 50%	YEL = Ye		N	/A	!	51"	
		2 Dilliouit	·						i		

### **DUTCHESS COUNTY DEPARTMENT OF HEALTH**

#### PERCOLATION TEST DATA

Name TAX GF	:			(T)(V)	(C)		Dat	te:		
IAA Gr	# 									
Ву:			DCHD Ins	pector						
Lot No.	Test Hole No.	Test Hole Deptl	•	Soaked			TEST	RUNS		
		•	71	l	*	1	2	3	4	5
					Finish			_		
	1		Silty Loam	Yes	Start					
			Only Loan	103	Time					
					Finish					
					Start					
					Time					
					Finish					
	2		Cille I	Yes	Start					
	_		Silty Loam	163	Time					
					Finish					
					Start					
					Time					
				Finish						
	3		Silty Loam	Yes	Start					
			Only Louin	100	Time					
					Finish					
					Start					
					Time					
					Finish					
					Start					
					Time					
					Finish					
					Start					
					Time				_	<u> </u>
					Finish					
					Start					
					Time					
					Finish					
					Start					
					Time					
der my rect.	y direction:	on acco	_, the undersigned, cording to the standard p	ertify that the procedure. T Signature: _ License No	he data a	ınd resu	ılts pres	ented ar	e true ai	nd cor-



**APPENDIX I** 



# **ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST Alternative No. 2 - Biofiltration System with GGSF Absorption Field**

Item Description	Unit Cost	Units	Quantity		Cost
STEP Collection System				\$	4,739,000
Pump out Existing Septic Tanks and Abandon in Place	\$750	EA	141	\$	105,800
STEP System Installation (1,000 Gallon Tank)	\$9,200	EA	119	\$	1,094,800
STEP System Installation (1,500 Gallon Tank)	\$12,800		18	\$	230,400
STEP System Installation (4,000 Gallon Tank)	\$14,800		4	\$	59,200
Service Lateral Installation (1-1/2" HDPE)	\$4,000		141	\$	564,000
Restoration for STEP System/Service Lateral Installation	\$3,400		141	\$	479,400
2"-4" HDPE Forcemain Installation (Directional Drilling)	\$52		15050	\$	782,600
6" HDPE Forcemain Installation (Directional Drilling)	\$70		2600	\$	182,000
Excavation and Connection at Junctions Air Releases	\$5,700 \$4,000		54 9	\$ \$	307,800 36,000
Clean-outs	\$2,300		40	\$	92,000
Bridge Crossing	\$6,800		1	\$	6,800
Pavement Repairs	\$2,300		108	\$	248,400
Lawn Restoration	\$12		9800	\$	117,600
Clearing and Grubbing in Right-of-Ways	\$13,600		3	\$	40,800
NYSDOT Crossing	\$6,800		5	\$	34,000
Mobilization/Demobilization	5%		1	\$	219,100
Traffic Control	3%	LS	1	\$	138,100
Site Work				\$	36,000
Clearing and Grubbing	\$13,600	Acre	0.5	\$	6,800
Rough Grading for Access Roadway	\$4,000		1	\$	4,000
Prepare and Roll Subbase for Access Roadway	\$3		1300	\$	3,900
Stabilization Fabric for Access Roadway	\$2	SY	1300	\$	2,600
Gravel and Compaction for Access Roadway	\$10	SY	1300	\$	13,000
Culvert	\$1,700	EA	2	\$	3,400
Mobilization/Demobilization	5%	LS	1	\$	1,700
Electrical Service				\$	21,000
Utility Pole Installation	\$1,200		8	\$	9,600
Excavation for Underground Electrical Utilities	\$5	LF	200	\$	1,000
Bedding for Underground Conduits	\$7		200	\$	1,400
Direct Burial of PVC Conduits	\$7		200	\$	1,400
Service Entrance	\$5,700		1	\$	5,700
Mobilization/Demobilization	5%	LS	11	\$	1,000
Biofiltration Resource Recovery System				\$	2,719,000
Pre-anoxic/EQ Tanks	\$216,364		1	\$	216,400
Pre-anoxic/EQ Tanks Access and Pumping Equipment	\$14,000 30%		1	\$ \$	14,000
Pre-anoxic/EQ Tank Installation Orenco AdvanTex AX-MAX Phase I Units (10 Units)	\$1,084,364		1 1	\$	69,200 1,084,400
Orenco T-MAX Effluent Pump Tank	\$87,818		1	\$	87,900
Orenco Treatment Unit Ancillary Equipment	\$110,727		1	\$	110,800
Telemetry Control Panel	\$68,000		1	\$	68,000
Instrumentation/Flow Meter	\$18,100		1	\$	18,100
Control Building	\$80,000		1	\$	80,000
Water Service	\$5,000		<u>-</u> 1	\$	5,000
Orenco Treatment System Installation					
	20%	LS	1	_	
Contractor's Overhead & Profit on Treatment System	20% 15%		1 1	\$ \$	290,900 240,000
Contractor's Overhead & Profit on Treatment System  Backup Generator		LS		\$	290,900
•	15%	LS EA	1	\$ \$	290,900 240,000
Backup Generator	15% \$34,000	LS EA LS	1 1	\$ \$ \$	290,900 240,000 34,000
Backup Generator Electrical Work	15% \$34,000 20%	LS EA LS LS	1 1 1	\$ \$ \$	290,900 240,000 34,000 82,000
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization	15% \$34,000 20% 12%	LS EA LS LS	1 1 1 1	\$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training	15% \$34,000 20% 12% \$7,400	LS EA LS LS	1 1 1 1 1	\$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization	15% \$34,000 20% 12% \$7,400	LS EA LS LS LS LS	1 1 1 1 1	\$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 <b>1,140,000</b>
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging	15% \$34,000 20% 12% \$7,400 5% \$13,600 \$800	LS LS LS LS Acre Acre	1 1 1 1 1 1	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 <b>1,140,000</b> 6,800 2,800
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field	15% \$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000	LS EA LS LS LS Acre Acre LS	1 1 1 1 1 1 0.5 3.5	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 <b>1,140,000</b> 6,800 2,800 17,000
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field  Trenching and Backfill for Absorption Field Trenches	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9	LS LS LS LS Acre Acre LS	1 1 1 1 1 1 0.5 3.5 1 9800	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 <b>1,140,000</b> 6,800 2,800 17,000 88,200
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging Rough Grading for Absorption Field Trenching and Backfill for Absorption Field Trenches GGSF Product & System Sand	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27	LS LS LS LS Acre Acre LS LF	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 <b>1,140,000</b> 6,800 2,800 17,000 88,200 264,600
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging Rough Grading for Absorption Field Trenching and Backfill for Absorption Field Trenches GGSF Product & System Sand Placing System Sand	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27	LS LS LS LS Acre Acre LS LF LF	1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 <b>1,140,000</b> 6,800 2,800 17,000 88,200 264,600 68,600
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging Rough Grading for Absorption Field Trenching and Backfill for Absorption Field Trenches GGSF Product & System Sand Placing System Sand Vent Piping	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7	LS LS LS LS Acre Acre LS LF LF	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging Rough Grading for Absorption Field Trenching and Backfill for Absorption Field Trenches GGSF Product & System Sand Placing System Sand Vent Piping Trenching and Backfill for Tight Pipes	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7	LS LS LS LS Acre Acre LS LF LF LF	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging Rough Grading for Absorption Field Trenching and Backfill for Absorption Field Trenches GGSF Product & System Sand Placing System Sand Vent Piping Trenching and Backfill for Tight Pipes Schedule 40 Tight Pipe	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9	LS LS LS LS Acre Acre LS LF LF LF LF LF	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900 4900	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100
Backup Generator Electrical Work Material Shipping Commissioning and Operator Training Mobilization/Demobilization  GGSF Absorption Fields Clearing and Grubbing Brush Hogging Rough Grading for Absorption Field Trenching and Backfill for Absorption Field Trenches GGSF Product & System Sand Placing System Sand Vent Piping Trenching and Backfill for Tight Pipes Schedule 40 Tight Pipe GGSF System Installation Labor	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9 \$7	LS LS LS LS Acre Acre LS LF LF LF LF LF LF LF	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900 4900	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100 326,500
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field  Trenching and Backfill for Absorption Field Trenches  GGSF Product & System Sand  Placing System Sand  Vent Piping  Trenching and Backfill for Tight Pipes  Schedule 40 Tight Pipe  GGSF System Installation Labor  Final Grading, Mulch & Seed	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9 \$7 \$9 \$60% \$6	LS LS LS LS Acre Acre LS LF LF LF LF LF LF LF SY	1 1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 9800 4900 4900 4900 1 16940	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100 326,500 101,700
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field  Trenching and Backfill for Absorption Field Trenches  GGSF Product & System Sand  Placing System Sand  Vent Piping  Trenching and Backfill for Tight Pipes  Schedule 40 Tight Pipe  GGSF System Installation Labor  Final Grading, Mulch & Seed  Groundwater Monitoring Wells	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9 \$7 \$9 60% \$6 \$28,300	LS EA LS LS LS Acre Acre LS LF LF LF LF LF LF LF LF LF LS SY EA	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900 4900	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100 326,500 101,700 113,200
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field  Trenching and Backfill for Absorption Field Trenches  GGSF Product & System Sand  Placing System Sand  Vent Piping  Trenching and Backfill for Tight Pipes  Schedule 40 Tight Pipe  GGSF System Installation Labor  Final Grading, Mulch & Seed	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9 \$27 \$7	LS EA LS LS LS Acre Acre LS LF LF LF LF LF LF LF LS SY EA LS	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900 4900 1 16940 4	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100 326,500 101,700 113,200 54,300
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field  Trenching and Backfill for Absorption Field Trenches  GGSF Product & System Sand  Placing System Sand  Vent Piping  Trenching and Backfill for Tight Pipes  Schedule 40 Tight Pipe  GGSF System Installation Labor  Final Grading, Mulch & Seed  Groundwater Monitoring Wells	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9 \$27 \$7	LS EA LS LS LS Acre Acre LS LF LF LF LF LF LF LS SY EA Construct	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900 4900 1 16940 4	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 202,200 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100 326,500 101,700 113,200 54,300 8,655,000
Backup Generator  Electrical Work  Material Shipping  Commissioning and Operator Training  Mobilization/Demobilization  GGSF Absorption Fields  Clearing and Grubbing  Brush Hogging  Rough Grading for Absorption Field  Trenching and Backfill for Absorption Field Trenches  GGSF Product & System Sand  Placing System Sand  Vent Piping  Trenching and Backfill for Tight Pipes  Schedule 40 Tight Pipe  GGSF System Installation Labor  Final Grading, Mulch & Seed  Groundwater Monitoring Wells	\$34,000 20% 12% \$7,400 5% \$13,600 \$800 \$17,000 \$9 \$27 \$7 \$9 \$27 \$7	LS LS LS LS Acre LS LF LF LF LF LF LF LF LF CF LF CF CS CONSTRUCT	1 1 1 1 1 1 1 0.5 3.5 1 9800 9800 9800 1960 4900 4900 1 16940 4	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	290,900 240,000 34,000 82,000 7,400 108,100 1,140,000 6,800 2,800 17,000 88,200 264,600 68,600 17,700 34,300 44,100 326,500 101,700 113,200 54,300



## **ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST Alternative No. 3 - MBR System with Surface Return**

Pump out Existing Septic Tanks and Abandon in Place STEP System Installation (1,000 Gallon Tank) STEP System Installation (1,500 Gallon Tank) STEP System Installation (4,000 Gallon Tank) STEP System Installation (4,000 Gallon Tank) Service Lateral Installation (1-1/2" HDPE) Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)	\$750 \$9,200		141	<b>\$</b>	<b>4,739,000</b> 105,800
STEP System Installation (1,000 Gallon Tank) STEP System Installation (1,500 Gallon Tank) STEP System Installation (4,000 Gallon Tank) Service Lateral Installation (1-1/2" HDPE) Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)	\$9,200		141	\$	10E 900
STEP System Installation (1,500 Gallon Tank) STEP System Installation (4,000 Gallon Tank) Service Lateral Installation (1-1/2" HDPE) Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)		ГΛ			105,600
STEP System Installation (4,000 Gallon Tank) Service Lateral Installation (1-1/2" HDPE) Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)	#12 000	EA	119	\$	1,094,800
Service Lateral Installation (1-1/2" HDPE) Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)	\$12,800	EA	18	\$	230,400
Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)	\$14,800	EA	4	\$	59,200
2"-4" HDPE Forcemain Installation (Directional Drilling)	\$4,000	EA	141	\$	564,000
, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	\$3,400	EA	141	\$	479,400
	\$52	LF	15050	\$	782,600
6" HDPE Forcemain Installation (Directional Drilling)	\$70	LF	2600	\$	182,000
Excavation and Connection at Junctions	\$5,700	EA	54	\$	307,800
Air Releases	\$4,000	EA	9	\$	36,000
Clean-outs	\$2,300	EA	40	\$	92,000
Bridge Crossing	\$6,800		1	\$	6,800
Pavement Repairs	\$2,300		108	\$	248,400
Lawn Restoration	\$12		9800	\$	117,600
Clearing and Grubbing in Right-of-Ways	\$13,600		3	\$	40,800
NYSDOT Crossing	\$6,800		5	\$	34,000
Mobilization/Demobilization	5%		1	\$	219,100
Traffic Control	3%		1	\$	138,100
Site Work	3 70			<u>φ</u>	83,000
Clearing and Grubbing	\$13,600	Acro	1.5	<b>-y</b> -	20,400
Brush Hogging	\$13,600		2.0	\$ \$	1,600
	\$2,900		2.0 1	\$	2,900
Rough Grading for Access Road  Prepare and Roll Subbase for Access Road		SY	800	\$	2,900
·					
Stabilization Fabric for Access Road		SY	800	\$	1,600
Gravel and Compaction for Access Road	\$10		800	\$	8,000
Culvert for Access Road	\$1,700		2	\$	3,400
Secondary Access R.O.W.		SF	16000	\$	9,600
Rough Grading for Secondary Access Road	\$4,000		1	\$	4,000
Prepare and Roll Subbase for Secondary Access Road		SY	1067	\$	3,200
Stabilization Fabric for Secondary Access Road	·	SY	1067	\$	2,200
Gravel and Compaction for Secondary Access Road	\$10		1067	\$	10,700
Culvert for Secondary Access Road	\$1,700		1	\$	1,700
Final Grading, Mulch & Seed		SY	1111	\$	6,700
Mobilization/Demobilization	5%	LS	1	\$	4,000
Electrical Service				\$	21,000
Utility Pole Installation	\$1,200		8	\$	9,600
Excavation for Underground Electrical Utilities	\$5		200	\$	1,000
Bedding for Underground Conduits	\$7		200	\$	1,400
Direct Burial of PVC Conduits	\$7	LF	200	\$	1,400
Service Entrance	\$5,700	LS	1	\$	5,700
Mobilization/Demobilization	5%	LS	1	\$	1,000
MBR Resource Recovery System				\$	3,441,000
Ovivo MicroBLOX Treatment System	\$1,681,273	LS	1	\$	1,681,300
MBR Treatment System Installation, Testing, and Start-up	30%	LS	1	\$	504,400
Contractor's Overhead & Profit on Treatment System	15%	LS	1	\$	252,200
Rough Site Grading for Building and Tanks	\$2,900	EA	1	\$	2,900
Concrete Slab on Grade for Building	\$24	SF	4500	\$	108,000
Metal Building	\$46	SF	4500	\$	207,000
Water Service	\$5,000	LS	1	\$	5,000
Gantry Crane	\$11,400	LS	1	\$	11,400
Building Plumbing	20%		1	\$	36,400
Building HVAC	30%		1	\$	62,100
Backup Generator	\$45,300		1	\$	45,300
Building Electric Work	40%		1	\$	101,000
Instrumentation/Control	5%		1	\$	84,100
Interior Process Pipe Work	10%		1	\$	168,200
Lab Equipment	\$8,500		1	\$	8,500
Commissioning and Operator Training	\$11,400		1	\$	11,400
Mobilization/Demobilization	\$11,400		1	\$	151,100
Surface Return	1 5%	LJ	<u> </u>		,
	412.000	Λ σ σ σ	0.5	<b>\$</b>	56,000
Clearing and Grubbing	\$13,600		0.5	\$	6,800
Trenching and Backfill	\$8		400	\$	3,200
Gravity Outfall Piping	\$15		400	\$	6,000
Pipe Bedding	\$8		400	\$	3,200
Concrete Outfall Structure	\$22,700		1	\$	22,700
Rip Rap	\$115		33	\$	3,900
Final Grading, Mulch & Seed		SY	100	\$	600
Dewatering, Erosion Protection	\$6,800		1	\$	6,800
	5%		1	\$	2,700
Mobilization/Demobilization		onstruc	tion Subtotal	\$	8,340,000
Mobilization/Demobilization					0,510,000
Mobilization/Demobilization		Propert	y Acquisition gency (20%)	\$	1,668,000



# **ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST Alternative No. 4 - Biofiltration System with Surface Return**

Item Description	Unit Cost	Units	Quantity		Cost
STEP Collection System				\$	4,739,000
Pump out Existing Septic Tanks and Abandon in Place	\$750	EA	141	\$	105,800
STEP System Installation (1,000 Gallon Tank)	\$9,200		119	\$	1,094,800
STEP System Installation (1,500 Gallon Tank)	\$12,800		18	\$	230,400
STEP System Installation (4,000 Gallon Tank)	\$14,800		4	\$	59,200
Service Lateral Installation (1-1/2" HDPE)	\$4,000		141	\$	564,000
Restoration for STEP System/Service Lateral Installation 2"-4" HDPE Forcemain Installation (Directional Drilling)	\$3,400 \$52		141 15050	\$ \$	479,400 782,600
6" HDPE Forcemain Installation (Directional Drilling)	\$70		2600	\$	182,000
Excavation and Connection at Junctions	\$5,700		54	\$	307,800
Air Releases	\$4,000		9	\$	36,000
Clean-outs	\$2,300		40	\$	92,000
Bridge Crossing	\$6,800		1	\$	6,800
Pavement Repairs	\$2,300		108	\$	248,400
Lawn Restoration	\$12		9800	\$	117,600
Clearing and Grubbing in Right-of-Ways	\$13,600		3	\$	40,800
NYSDOT Crossing	\$6,800		5	\$	34,000
Mobilization/Demobilization Traffic Control	5% 3%		1 1	\$ \$	219,100
Site Work	3%	ĮLS .	L	<u> </u>	138,100 <b>83,000</b>
Clearing and Grubbing	\$13,600	Acre	1.5	<b>\$</b>	20,400
Brush Hogging	\$800		2.0	\$	1,600
Rough Grading for Access Road	\$2,900		1	\$	2,900
Prepare and Roll Subbase for Access Road		SY	800	\$	2,400
Stabilization Fabric for Access Road	\$2	SY	800	\$	1,600
Gravel and Compaction for Access Road	\$10	SY	800	\$	8,000
Culvert for Access Road	\$1,700		2	\$	3,400
Secondary Access R.O.W.		SF	16000	\$	9,600
Rough Grading for Secondary Access Road	\$4,000		1	\$	4,000
Prepare and Roll Subbase for Secondary Access Road	\$3	SY	1067	\$	3,200
Stabilization Fabric for Secondary Access Road		SY	1067	\$	2,200
Gravel and Compaction for Secondary Access Road  Culvert for Secondary Access Road	\$10 \$1,700		1067 1	\$ \$	10,700 1,700
Final Grading, Mulch & Seed		SY	1111	\$	6,700
Mobilization/Demobilization	5%		1	\$	4,000
Electrical Service			_	\$	21,000
Utility Pole Installation	\$1,200	EA	8	\$	9,600
Excavation for Underground Electrical Utilities	\$5	LF	200	\$	1,000
Bedding for Underground Conduits	\$7	LF	200	\$	1,400
Direct Burial of PVC Conduits		LF	200	\$	1,400
Service Entrance	\$5,700		1	\$	5,700
Mobilization/Demobilization	5%	LS	1	\$	1,000
Biofiltration Resource Recovery System	±2.064.264	lı C	4	<u>\$</u>	3,773,000
Treatment System Tanks and Componenents Treatment System Ancillary Equipment	\$2,064,364 \$48,364		1 1	\$ \$	2,064,400 48,400
UV Disinfection System	\$35,000		1	\$	35,000
Control Building	\$80,000	LS	1	\$	80,000
Water Service	\$5,000	LS	1	\$	5,000
Treatment System Installation	30%		1	\$	669,900
Material Shipping Contractor's Overhead & Profit on Treatment System	\$201,000		1 1	\$	201,000
Contractor's Overhead & Profit on Treatment System Backup Generator	15% \$34,000		1	\$ \$	322,200 34,000
Electrical Work	20%		1	\$	157,800
Mobilization/Demobilization	5%		1	\$	154,800
Surface Return				\$	56,000
Clearing and Grubbing	\$13,600	Acre	0.5	\$	6,800
Trenching and Backfill		LF	400	\$	3,200
Gravity Outfall Piping	\$15		400	\$	6,000
Pipe Bedding		LF	400	\$	3,200
Concrete Outfall Structure	\$22,700		1	\$	22,700
Rip Rap	\$115		33	\$	3,900
Final Grading, Mulch & Seed		SY	100	\$	600
Dewatering, Erosion Protection  Mobilization/Demobilization	\$6,800 5%		1 1	\$	6,800
Modifization/ Defilobilization		•	tion Subtotal	\$ <i>\$</i>	2,700 <i>8,672,000</i>
			y Acquisition		-
		Contin	gency (20%)	\$	1,734,000
	Total Esti	mated I	Project Cost	\$	10,406,000



## ENGINEER'S OPINION OF PROBABLE ANNUAL OPERATION & MAINTENANCE COST Alternative No. 2 - Biofiltration System with GGSF Absorption Field

Item Description	Unit Cost	Units	Quantity		Cost
STEP Collection System		l l		\$	46,700
Proactive System Maintenance	\$75	Hour	104	\$	7,800
Reactive System Maintenance	\$75	Hour	87	\$	6,500
STEP Tank Pumping	\$750	Each	27	\$	20,400
Equipment Repair and Replacement	\$12,000	Year	1	\$	12,000
Biofiltration Resource Recovery System					35,700
Regular System Maintenance	\$75	Hour	156	\$	11,700
Emergency Maintenance	\$75	Hour	26	\$	2,000
Energy Consumption (Treatment System)	\$0.10	kWh	116136	\$	11,700
Energy Consumption (Control Building)	\$0.10	kWh	7300	\$	800
Cellular Service for Communication	\$40	Month	12	\$	500
Treatment Tank Pumping	\$600	Year	1	\$	600
Textile Replacement	\$1,700	Year	1	\$	1,700
Pump Repair and Replacement	\$1,800	Year	1	\$	1,800
Float Replacement	\$460	Year	1	\$	500
Flow Meter Calibration	\$290		1	\$	300
Sampling Supplies	\$600	Year	1	\$	600
Laboratory Fees		Month	12	\$	1,200
Misc. Maintenance Supplies	\$750	Year	1	\$	800
Mowing around Treatment Units	\$50	Hour	30	\$	1,500
GGSF Absorption Field				\$	1,900
Mowing Absorption Field	\$50	Hour	30	\$	1,500
Laboratory Testing - Nitrite - Quarterly	\$50	Each	8	\$	400
		Ann	ual O&M Subtotal	\$	84,300
	Contingency (20%)				16,900
	Administra	Administration, Billing, & Accounting			
	Total Esti	mated A	nnual O&M Cost	\$	116,200



## ENGINEER'S OPINION OF PROBABLE ANNUAL OPERATION & MAINTENANCE COST Alternative No. 3 - MBR System with Surface Return

Item Description	Unit Cost	Units	Quantity		Cost
STEP Collection System				\$	46,700
Proactive System Maintenance	\$75	Hour	104	\$	7,800
Reactive System Maintenance	\$75	Hour	87	\$	6,500
STEP Tank Pumping	\$750	Each	27	\$	20,400
Equipment Repair and Replacement	\$12,000	Year	1	\$	12,000
MBR Resource Recovery System				\$	106,900
Regular System Maintenance	\$75	Hour	520	\$	39,000
Emergency Maintenance	\$75	Hour	26	\$	2,000
Energy Consumption (Treatment System)	\$0.10	kWh	225305	\$	22,600
Energy Consumption (Building)	\$0.10	kWh	18250	\$	1,900
Cellular Service for Communication	\$40	Month	12	\$	500
Chemical Usage	\$200	Year	1	\$	200
Sludge Handling Costs	\$20,200	Year	1	\$	20,200
MBR Equipment Repair and Replacement	\$9,000	Year	1	\$	9,000
MBR Equipment R&R Labor	\$75	Hour	22	\$	1,700
Flow Meter Calibration	\$290	Year	1	\$	300
Building Maintenance	\$1,000	Year	1	\$	1,000
Building Heating/Ventilation	\$250	Month	12	\$	3,000
Sampling Supplies	\$600	Year	1	\$	600
Laboratory Fees	\$200	Month	12	\$	2,400
Misc. Maintenance Supplies	\$1,000	Year	1	\$	1,000
Mowing Around Building	\$50	Hour	30	\$	1,500
Surface Return				\$	1,000
Cleaning/Maintenance	\$1,000		1	\$	1,000
			ual O&M Subtotal	\$	<i>154,600</i> 31,000
		Contingency (20%)			
			ing, & Accounting		15,000
	Total Esti	mated A	nnual O&M Cost	\$	201,000



## ENGINEER'S OPINION OF PROBABLE ANNUAL OPERATION & MAINTENANCE COST Alternative No. 4 - Biofiltration System with Surface Return

Item Description	Unit Cost	Units	Quantity		Cost
STEP Collection System	<b>-</b>			\$	46,700
Proactive System Maintenance	\$75	Hour	104	\$	7,800
Reactive System Maintenance	\$75	Hour	87	\$	6,500
STEP Tank Pumping	\$750	Each	27	\$	20,400
Equipment Repair and Replacement	\$12,000	Year	1	\$	12,000
Biofiltration Resource Recovery System					61,400
Regular System Maintenance	\$75	Hour	364	\$	27,300
Emergency Maintenance	\$75	Hour	26	\$	2,000
Energy Consumption (Treatment System)	\$0.10	kWh	171882	\$	17,200
Energy Consumption (Control Building)	\$0.10	kWh	7300	\$	800
Cellular Service for Communication	\$40	Month	12	\$	500
Treatment Tank Pumping	\$700	Year	1	\$	700
Textile Replacement	\$2,545	Year	1	\$	2,600
Pump Repair and Replacement	\$3,945	Year	1	\$	4,000
Float Replacement	\$500	Year	1	\$	500
Flow Meter Calibration	\$290	Year	1	\$	300
Sampling Supplies	\$600	Year	1	\$	600
Laboratory Fees	\$200	Month	12	\$	2,400
Misc. Maintenance Supplies	\$1,000	Year	1	\$	1,000
Mowing Around Treatment System	\$50	Hour	30	\$	1,500
Surface Return				\$	1,000
Cleaning/Maintenance	\$1,000		1	\$	1,000
			ual O&M Subtotal	\$ \$	109,100
		Contingency (20%)			21,900
			ing, & Accounting		15,000
	Total Esti	mated A	nnual O&M Cost	\$	146,000

**APPENDIX J** 



#### **Engineering Report Certification**

During the preparation of this Engineering Report, I have studied and evaluated the cost and effectiveness of the processes, materials, techniques, and technologies for carrying out the proposed project or activity for which assistance is being sought from the New York State Clean Water State Revolving Fund. In my professional opinion, I have recommended for selection, to the maximum extent practicable, a project or activity that maximizes the potential for efficient water use, reuse, recapture, and conservation, and energy conservation, taking into account the cost of constructing the project or activity, the cost of operating and maintaining the project or activity over the life of the project or activity, and the cost of replacing the project and activity.

Title of Engineering Report: <u>Wastewater Feasibility Evaluation – Village of Millerton</u>

March 2020, Revised June 2020, Revised April 2022, Date of Report:

Revised June 2024 For NYSDEC, Revised July 2025 For

NYSDEC

Professional Engineer's Name: Erin K. Moore, PE, BCEE

Moor

Signature:

Date: <u>July 17, 2025</u>

**APPENDIX K** 



### **Smart Growth Assessment Form**

This form should be completed by the applicant's project engineer or other design professional.<sup>1</sup>

Applicant Information Applicant: Project Name:	Project No.:
Is project construction complete? ☐ Yes, date:	□ No
Project Summary: (provide a short project summary in plain language in	ncluding the location of the area the project serves)
Section 1 – Screening Questions	
1. Prior Approvals	
1A. Has the project been previously approved for Environ Corporation (EFC) financial assistance?	mental Facilities ☐ Yes ☐ No
1B. If so, what was the project number(s) for the prior approval(s)?	Project No.:
Is the scope of the project substantially the same as tapproved?	that which was ☐ Yes ☐ No
IF THE PROJECT WAS PREVIOUSLY APPROVED BY OF THE PROJECT HAS NOT MATERIALLY CHANGED TO SMART GROWTH REVIEW. SKIP TO	, THE PROJECT IS <b>NOT</b> SUBJECT
2. New or Expanded Infrastructure	
2A. Does the project add new wastewater collection/new new wastewater treatment system/water treatment plant Note: A new infrastructure project adds wastewater collection/water wastewater treatment/water treatment plant where none existed p	ant? er mains or a
2B. Will the project result in either:	□ Yes □ No
An increase of the State Pollutant Discharge Eliminati (SPDES) permitted flow capacity for an existing treatn	
<u>OR</u>	
An increase such that a Department of Environmental (DEC) water withdrawal permit will need to be obtained result in the Department of Health (DOH) approving a capacity of the water treatment plant?	d or modified, or
Note: An expanded infrastructure project results in an increase of flow capacity for the wastewater treatment system, or an increase withdrawal or the permitted flow capacity for the water treatment s	of the permitted water

<sup>&</sup>lt;sup>1</sup> If project construction is complete and the project was not previously financed through EFC, an authorized municipal representative may complete and sign this assessment.

IF THE ANSWER IS "NO" TO BOTH "2A" and "2B" ON THE PREVIOUS PAGE, THE PROJECT IS NOT SUBJECT TO FURTHER SMART GROWTH REVIEW. SKIP TO SIGNATURE BLOCK.

3. Court or Administrative Consent Orders		
3A. Is the project expressly required by a court or administrative consent order?	□ Yes	□ No
3B. If so, have you previously submitted the order to EFC or DOH? If not, please attach.	□ Yes	□ No
Section 2 – Additional Information Needed for Relevant Smart Gre	owth Cr	iteria
EFC has determined that the following smart growth criteria are relevant for projects and that projects must meet each of these criteria to the extent practice.		ded
1. Uses or Improves Existing Infrastructure		
1A. Does the project use or improve existing infrastructure? <u>Please describe</u> :	□ Ye	s □ No
<ol> <li>Serves a Municipal Center         Projects must serve an area in either 2A, 2B or 2C to the extent practical     </li> </ol>	ble.	
2A. Does the project serve an area <b>limited</b> to one or more of the following more centers?	nunicipal	
<ul> <li>i. A City or incorporated Village</li> <li>ii. A central business district</li> <li>iii. A main street</li> <li>iv. A downtown area</li> <li>v. A Brownfield Opportunity Area</li> </ul>	□Ye: □Ye: □Ye □Ye	s □No s □No s □No
(for more information, go to <a href="www.dos.ny.gov">www.dos.ny.gov</a> & search "Brownfield")  vi. A downtown area of a Local Waterfront Revitalization Program Area (for more information, go to <a href="www.dos.ny.gov">www.dos.ny.gov</a> and search "Waterfront Revitalization")	□Ye	
vii. An area of transit-oriented development	□Ye	s □No
viii. An Environmental Justice Area (for more information, go to <a href="https://www.dec.ny.gov/public/899.html">www.dec.ny.gov/public/899.html</a> )	□Ye	s □No
ix. A Hardship/Poverty Area Note: Projects that primarily serve census tracts and block numbering areas with a poverty rate of at least twenty percent according to the latest census data	□Ye	s □No
Please describe all selections:		

2B. If the project serves an area located outside of a mur located adjacent to a municipal center which has clear concentrated development in a municipal or regional strong land use, transportation, infrastructure and economicipal center?	arly defined borders, designated for comprehensive plan and exhibit
Please describe:	
2C. If the project is not located in a municipal center as dedesignated by a comprehensive plan and identified in municipal center?	
Please describe and reference applicable plans:	
3. Resiliency Criteria	
3A. Was there consideration of future physical climate risk and/or flooding during the planning of this project?	k due to sea-level rise, storm surge, □Yes □No
Please describe:	
Signature Block: By entering your name in the box below, act on behalf of the applicant and that the information cont Assessment is true, correct and complete to the best of yo	ained in this Smart Growth
Applicant:	Phone Number:
(Name & Title of Project Engineer or Design Professional or Authorize	d Municipal Representative)
(Signature)	(Date)

**APPENDIX L** 

#### **PROJECT COSTS**

The project costs are comprised of two components, the capital cost and the operation and maintenance cost. The capital costs are the anticipated costs to construct the proposed sewer system. The operation and maintenance (O&M) costs are the annual costs for labor, materials, and accounting associated with a functional sewer system.

### **Capital Costs**

The anticipated total capital cost for construction of the water resource recovery system serving the Village of Millerton and Town of Northeast with grant and hardship financing is presented in Table 1, below.

**TABLE 1** - Total Project Cost and Funding

	I	Millerton	N	lortheast	(	Combined
Total Project Costs	\$	10,866,000	\$	2,964,000	\$	13,830,000
Less Other Sources of Funding						
-Dutchess County Grant	\$	165,000	\$	35,000	\$	200,000
-CFD Grant	\$	786,997	\$	172,755	\$	959,752
-EFC IMG	\$	4,167,321	\$	914,778	\$	5,082,099
Project Cost to be Financed	\$	5,746,682	\$	1,841,467	\$	7,588,149

The financing of the debt service costs are based on the number of Benefit Units (BU) per parcel. The assessments to pay the debt service costs are based on a reasonably estimated benefit associated with the availability of the sewer system based on the type of use. The Benefit Unit Schedule is presented in Table 2.

TABLE 2 - Benefit Unit Schedule

Type of Usage	Benefit Units
Auto Dealer/Repair	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup>
Bank	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup>
Commercial uses not included elsewhere in this schedule	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup>
Dentist	1 per business plus 1 per chair
Doctor/Therapist/Vet	1 per business plus 1 per practitioner
Fitness Studio, Gym	1 per business plus 1 per 1,000 square feet of building area 1 plus 1 per two shower stalls
Gas station, convenience store/mini mart - No food preparation	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup>
+ Additional food preparation, up to 12 seats	2 per business
Hairdresser, salon, spa, nails, barbershop	1 per business plus 1 per station with sink plus 1 per 4 chairs without sink
Hotel, motel, inn	1 per establishment plus 1 per two rooms
Kennel/Groomers	1 per business plus 1 per two runs/cages/stations
Library, Museum, Cultural Building, Religious	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup> , add for separate assembly hall
Office	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup>
Park	1 per parcel
+ Additional for Park facilities	1 per 1,000 square feet of building <sup>1</sup> , 1 per each restroom facility, 1 per each two shower units, 5 per swimming pool
Residence (1 to 3 bedrooms)	1 per residence
2-family residence (1 to 3 bedrooms per unit)	2 per residence
3-family residence (1 to 3 bedrooms per unit)	3 per residence
Apartments (1 to 3 bedrooms)	1 per apartment
+ Additional bedrooms over allowance	0.5 per bedroom
+ Grease trap cleanout charge	3 per cleanout
Retail	1 per business plus 1 per 1,000 sq ft of building area $^{\mathrm{1}}$
Supermarkets	1 per business plus 1 per 1,000 sq ft of building area <sup>1</sup>
Theater, Assembly Hall	1 per business plus 1 per 35 seats
	1 per parcel

<sup>&</sup>lt;sup>1</sup>Building area of first BU includes all buildings up to 1,000 sq ft. Additional area is rounded. Ex: An office of 600 sq ft will have 2 BUs. An office of 1,499 sq. ft. will have 2 Bus. An office of 1,501 sq ft will have 3 BUs.

There are a total of 378 benefit units, 88 residential and 290 commercial in the Village of Millerton. There is are a total of 67 benefit units in the Town of North East, all of which are commercial. Table 3 provides the cost per benefit unit for the Village and the Town.

<sup>&</sup>lt;sup>2</sup>If more than one use is associated with an individual parcel, the Benefit Units will be aggregated.

**TABLE 3** - Cost per Benefit Unit

	<b>Millerton</b> \$ 5,746,682 \$ 191,566		N	lortheast	C	Combined
Project Cost to be Financed	\$	5,746,682	\$	1,841,467	\$	7,588,149
Annual Cost at 0% and 30-year repayment period	\$	191,566	\$	61,382	\$	252,938
Benefit Units (BU)		378		67		445
Annual Cost per BU	\$	506.76	\$	916.15		

### **Operation & Maintenance Costs**

The anticipated annual O&M cost for the water resource recovery system is \$144,000. The O&M costs include maintenance of the collection system, septic tank pumping and maintenance, operator labor, electricity for the water resource recovery system, laboratory services, a contingency, and administrative costs. The O&M costs for the system is presented in Table 4, below.


TABLE 4 - O&M Cost

	M	illerton	No	rtheast	Co	ombined
Total O&M Costs	\$	118,100	\$	29,500	\$	144,000

Operation and maintenance costs are recovered based upon flow, with the assumption that water used becomes discharged as wastewater. In cases where parcels are not located on the Village water system, meters will be provided. The initial O&M fee is based upon existing flows, not future flow. There are both residential and commercial rates for O&M fees. Residential fees are based upon average daily flow, as residential flows are typical more consistently spread over the 24-hour period and represent average to low strength wastewater. The residential O&M Fee is \$197/year (\$16.41 per month) for up to a flow of 225 gpd which is a conservative single family water usage within the Village. Flows are allotted in increments of 225 gpd, for instance a 2-family home is allotted 450 gpd, and 3-family home 675 gpd. Flow beyond this volume will be charged at \$5.70 per 1,000 gallons based upon the annual O&M cost of \$144,000 divided by the total annual gallons ( $$144,000/70,000 \times 365$ days/1000 gallons). Billing and fees for flows over average usage will be assessed on a quarterly basis. For example, a 90-day billing period would result in a flow allocation of 20,250 gallons for a single family parcel (90 days x 225 gallons per day = 20,225 gallons). A single family parcel using 25,000 gallons during this period would be charged the standard fee for three months at \$16.41 per month (\$49.23) plus the overage (25,000 - 20,225 = 4,750gallons/1000 gallons =  $4.75 \times \$5.70 = \$27.08$ ) for a total quarterly operation and maintenance fee of \$76.81.

Commercial operation and maintenance fees are based upon a demand charge system where costs are based upon peak usage as this peak is what drives the cost of maintaining the treatment and collection system infrastructure. Unlike residential users, commercial users have a higher demand on the treatment system capacity including higher peak flows, higher strength wastewater concentrations and greater anticipated use of the system's capacity reserves. The peaking factor is established through the 10 States Standards (10 SS) peak

hour peaking factor computational methodology. A population of 600 has been assumed for the wastewater service area resulting in a peak hour peaking factor of 4.0.



**Figure 4.1**Ten States Standards Peak Hour Factor Calculation

The peak hourly usage per commercial user is anticipated to be 900 gpd (flow at peak hour), approximately four times the assumed residential rate of 225 gpd, resulting in a commercial 0&M Fee is \$788/year (\$75 per month) for average flows up to a flow of 225 gpd. Average flows are allotted in increments of 225 gpd based upon historical usage records. For actual billing purposes flows will be divided by 225 gpd and billed at the commercial rate. Flow beyond this volume will be charged at \$5.70 per 1,000 gallons as described earlier. Billing and fees for flows over average usage will be assessed on a quarterly basis. For example, a business using 45,000 gallons over a 90-day billing period would result in an average daily flow of 500 gpd. (45,000 gallons/90 days = 500 gpd). This is results in two increments of 225 gpd (225 gpd x 2 = 450 gpd), or \$1,576 per year (\$131.33 per month) The commercial parcel would be charged the standard commercial fee for three months at \$131.33 per month (\$394.00) plus the overage (45,000 – 40,500 = 4,500 gallons/1000 gallons = 4.5 x \$5.70 = \$25.65) for a total quarterly operation and maintenance fee of \$419.65.

### **Estimated First Year Annual Cost for a Typical Parcel**

The typical residential parcel in the Village is a single-family residence (1 BU). As previously noted, for the purposes of this estimate a flow of 225 gpd per single family residential parcel is used to provide anticipated operation & maintenance costs, however, users will be charged on actual water usage for the operation and maintenance portion of this user charge for flows in excess of 225 gpd increments.

The typical non-residential parcel in the system is a small commercial user (2 BU).

Table 5 & 6 provides the typical annual cost for typical users in Millerton and Northeast, respectively.

**TABLE 5** - Anticipated Example User Fees - Village of Millerton


User	Annual Capital Cost (BU)	Annual O&M Cost @225 gpd	Total Annual Cost	Total Monthly Cost			
Single Family Res. (1 BU)	\$ 506.76	\$ 197	\$ 703.76	\$ 58.64			
Small Commercial (2 BU)	\$ 1,013.52	\$ 788	\$ 1,801.52	<b>\$ 150.13</b>			

**TABLE 6** - Anticipated Example User Fees - Town of North East

User	Annual Capital Cost (BU)	Annual O&M Cost @225 gpd	Total Annual Cost	Total Monthly Cost
Single Family Res. (1 BU)	\$ 916.15	\$ 197	\$ 1,113.15	\$ 92.76
Small Commercial (2 BU)	\$ 1,832.30	\$ 788	\$ 2,620.30	\$ 218.36

Flow over the allotted quantity of 225 gpd increments will be charged additionally at a rate of \$5.60 per 1,000 gallons which is the equivalent O&M cost and presented previously.

**APPENDIX M** 



	Name	Duration	Start	Finish	Predecessors		Half 2, 2025	Half 1, 2026			Half 2, 2026		Half 2, 2026 Half 1, 2027 Half 2, 20	Half 2, 2026 Half 1, 2027 Half 2, 2027	Half 2, 2026 Half 1, 2027 Half 2, 2027	Half 2, 2026 Half 1, 2027 Half 2, 2027	Half 2, 2026 Half 1, 2027 Half 2, 2027	Half 2, 2026 Half 1, 2027 Half 2, 2027 Ha
						F M A M J	J A S O N [	J F M A M	1	1 J J A	1 J J A S O N I	1 J J A S O N D J F M A N			1 J J A S O N D J F M A M J J A S O N I	1 J J A S O N D J F M A M J J A S O N D		
48	Treatment System 90% Design	30 days	12/2/25 8:00 AM	1/12/26 5:00 PM	47													
49	Treatment System 90% Design Review Meeting	1 day	1/13/26 8:00 AM	1/13/26 5:00 PM	48			Ę.										
50	Treatment System Permit Set Edits	7 days	1/14/26 8:00 AM	1/22/26 5:00 PM	49			ii										
51	Submit Treatment System Design for Regulatory Review	1 day	1/23/26 8:00 AM	1/23/26 5:00 PM	50			H.										
52	Regulatory Review	60 days	1/26/26 8:00 AM	4/17/26 5:00 PM	51													
53	Regulator Review Meeting	1 day	4/20/26 8:00 AM	4/20/26 5:00 PM	52			<b>L</b>										
54	Treatment System Design Approval	1 day	4/21/26 8:00 AM	4/21/26 5:00 PM	53			The state of the s										
55	Permitting	217 days	7/9/25 8:00 AM	5/7/26 5:00 PM														
56	SPDES Permit Approval	60 days	7/9/25 8:00 AM	9/30/25 5:00 PM	43													
57	Joint Application for Permit (ACOE)	14 days	1/26/26 8:00 AM	2/12/26 5:00 PM	51													
58	Joint Application Approval	60 days	2/13/26 8:00 AM	5/7/26 5:00 PM	57													
59	DOT Permitting	30 days	1/26/26 8:00 AM	3/6/26 5:00 PM	32													
60	Bidding	64 days	5/8/26 8:00 AM	8/5/26 5:00 PM							<b>-</b>	₩	•	•	♥	₩	₩	♥
61	Advertise for Bidding	5 days	5/8/26 8:00 AM	5/14/26 5:00 PM	36;54;55			<b>Y</b>	,									
62	Bidding Period	45 days	5/15/26 8:00 AM	7/16/26 5:00 PM	61			Ĭ										
63	Bid Review	14 days	7/17/26 8:00 AM	8/5/26 5:00 PM	62													
64	Construction	427 days	8/7/26 8:00 AM	3/27/28 5:00 PM							∐							
65	Notice to Proceed	1 day	8/7/26 8:00 AM	8/7/26 5:00 PM	20;33;45				`	6	6							
66	Treatment System Construction	270 days	8/10/26 8:00 AM	8/20/27 5:00 PM	65							<b>V</b>						
67	Collection System Construction	365 days	8/10/26 8:00 AM	12/31/27 5:00 PM	65						V		<b>Y</b>	<b>Y</b>	<b>Y</b>	<b>Y</b>	<b>Y</b>	•
68	System Start-up/Testing	30 days	1/3/28 8:00 AM	2/11/28 5:00 PM	66;67													
69	Closeout	60 days	1/3/28 8:00 AM	3/24/28 5:00 PM	66;67													<u> </u>
70	Construction Complete	1 day	3/27/28 8:00 AM	3/27/28 5:00 PM	68;69													